

**DEPARTMENT OF TRANSPORTATION**

DES-OE MS #43  
1727 30TH Street, 2ND Floor  
Sacramento, CA 95816



**\*\* WARNING \*\* WARNING \*\* WARNING \*\* WARNING \*\***  
**This document is intended for informational purposes only.**

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

April 9, 2004

03-Pla-80-62.8/R89.7  
03-1A8014  
ACIM-080-4(175)145E

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in PLACER COUNTY FROM MAGRA OVERHEAD TO 0.5 KM WEST OF CARPENTER FLAT UNDERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on April 21, 2004.

This addendum is being issued to revise the Notice to Contractors and Special Provisions and the Proposal and Contract.

In the Special Provisions, Section 10-1.11 , "MAINTAINING TRAFFIC", is replaced as attached.

In the Proposal and Contract, the Engineer's Estimate Item 93 is revised as attached.

To Proposal and Contract book holders:

Replace page 7 of the Engineer's Estimate in the Proposal with the attached revised page 7 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 3  
Page 2  
April 9, 2004

03-Pla-80-62.8/R89.7  
03-1A8014  
ACIM-080-4(175)145E

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

**[http://www.dot.ca.gov/hq/esc/oe/weekly\\_ads/addendum\\_page.html](http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html)**

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief  
Office of Plans, Specifications & Estimates  
Office Engineer

Attachments

### 10-1.11 MAINTAINING TRAFFIC

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" and "Portable Changeable Message Sign" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

Attention is directed to "Traffic Plastic Drums" in these special provisions regarding using plastic drums in place of portable delineators, cones or Type I or II barricades. The mixing of construction area traffic control devices will not be allowed.

Lane and ramp closures shall conform to the provisions in section "Traffic Control System for Lane Closure" of these special provisions.

Personal vehicles of the Contractor's employees shall not be parked on the traveled way or shoulders including any section closed to public traffic.

The Contractor shall notify local authorities (including the California Highway Patrol (CHP), Placer County Sheriff's Department, State of California Department of Forestry, District 3 Whitmore Maintenance Station, and Local Fire Departments) of the Contractor's intent to begin work at least 5 days before work is begun. The Contractor shall cooperate with local authorities relative to handling traffic through the area and shall make arrangements relative to keeping the working area clear of parked vehicles.

Access and egress to the Whitmore Maintenance Station shall be maintained at all times.

Portable delineators shall be furnished and placed during stage construction as shown on the traffic handling plans. Full compensation for furnishing, placing, moving, maintaining and removing the portable delineators shown on the traffic handling plans shall be considered as included in the prices paid for the various items of work involved and no additional compensation will be allowed therefor.

On multilane roadways, whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

A portable changeable message sign shall be placed for each lane, ramp or shoulder closure and detour prior to the first advance warning sign shown on the plans, or as directed by the Engineer.

Two portable changeable message signs shall be in operation at all times during stage construction at locations directed by the Engineer.

One portable changeable message sign shall be in operation at all times for westbound truck brake inspection at locations directed by the Engineer.

On two-lane, two-way roadways, whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed with fluorescent traffic cones or portable delineators placed on a taper in advance of the parked vehicles or equipment and along the edge of the pavement at 7.5 m intervals to a point not less than 7.5 m past the last vehicle or piece of equipment. A minimum of 9 cones or portable delineators shall be used for the taper. A C23 (Road Work Ahead) or C24 (Shoulder Work Ahead) sign shall be mounted on a portable sign stand with flags. The sign shall be placed where designated by the Engineer.

Except as noted herein, lanes and ramps shall be closed only during the hours shown on the charts included in this section "Maintaining Traffic." Except work required under Sections 7-1.08 and 7-1.09, work that interferes with public traffic shall be performed only during the hours shown for lane closures.

The maximum length of lane closure shall be limited to 4.8 km in the westbound direction and 1.6 km in the eastbound direction unless otherwise permitted by the Engineer.

The Contractor shall notify the Engineer 7 calendar days prior to a ramp closure. A portable changeable message sign shall be placed a minimum of 3 calendar days in advance of closing the ramp. When a ramp is closed, public traffic shall be detoured to the next ramp or to an on-site detour as shown on the plans as directed by the Engineer. When portable changeable message signs are no longer required, they shall be removed as directed by the Engineer.

No two consecutive on-ramps or consecutive off-ramps in the same direction of travel shall be closed at the same time except as otherwise provided in these special provisions and as permitted by the Engineer.

Except as otherwise noted within the staging plans, no ramp closure will be permitted for any longer than one work shift.

The Contractor shall schedule his operations so that between October 15 and April 15, there is no vertical drop-off between adjacent traffic lanes, or between lanes and shoulders and the full width of the traveled way and shoulders shall be open for use by public traffic.

The Contractor shall complete temporary AC ramps at the westbound off-ramp and on-ramps at Baxter OC allowing public traffic use for detouring when required. The off-ramp at Baxter OC shall be completed before the on-ramp. After completing these temporary AC ramps at the aforementioned locations, the Contractor shall move to Alta Road UC and complete the temporary AC ramp at the westbound off-ramp. Next the Contractor shall move to Drum Forebay and begin PCC paving as shown in Stage 2 of the Stage Construction Traffic Handling Plans. All final PCC paving of ramps from Drum Forebay to Alta Road UC shall be completed in the construction year 2005 unless otherwise directed by the Engineer.

The Contractor will be allowed a 24 hour ramp closure for four consecutive working days to complete all work for the Putts Lake OC eastbound off-ramp at Nyack. The ramp closure will be allowed from on Sunday at 9.00 p.m. until Thursday at 9:00 p.m. Upon achieving an acceptable PCC beam test, the ramp shall be opened to public traffic.

No lane closures, shoulder closures, or other traffic restrictions will be allowed on the following day(s) during the annual "Hot August Nights" weekend celebration will occur in Reno area during the life of this contract. If notified by the Engineer, the Contractor shall keep all traffic lanes open for use by public traffic on the preceding Thursday, Friday; Saturday, Sunday in the eastbound direction and in the westbound direction on Monday during this celebration. If this requirement delays the controlling operation as specified in Section 8-1.06, "Time of Completion," of the Standard Specifications, the days will be considered a non-working day, except as otherwise noted within these special provisions .

Except as noted herein, the full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday. When a designated legal holiday falls on a Monday, the full width of the traveled way shall be open for use by public traffic on the preceding Friday, Saturday and Sunday.

Minor deviations from the requirements of this section concerning hours of work which do not significantly change the cost of the work may be permitted upon the written request of the Contractor, if in the opinion of the Engineer, public traffic will be better served and the work expedited. These deviations shall not be adopted by the Contractor until the Engineer has approved the deviations in writing. All other modifications will be made by contract change order.

<b>Chart No. 1</b>																												
<b>Multilane and Ramp Lane Requirements</b>																												
Direction: EASTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 73.6 (Alta Rd. UC to Towle OH)																
FROM HOUR TO HOUR	a.m.											p.m.																
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9		10	11	12		
Mondays through Wednesdays	1	1	1	1	1	1	1	1	1	1											1	1	1	1	1	1		
Thursdays	1	1	1	1	1	1	1	1	1	1															1	1	1	
Fridays	1	1	1	1	1	1	1																					
Saturdays	1	1	1	1	1	1	1																			1	1	
Sundays	1	1	1	1	1	1	1	1	1																1	1	1	1
Day before designated legal holiday & designated legal holidays																												
Legend:																												
1	One lane, a minimum of 3.3 m wide, shall be open in direction of travel.																											
	No closure allowed.																											
REMARKS: THIS CHART ONLY FOR PLACEMENT OF PORTLAND CEMENT CONCRETE (PCC) PAVEMENT BETWEEN JUNE 15 <sup>th</sup> AND LABOR DAY. Two Lanes Available. Ramp closure allowed during lane closure.																												

<b>Chart No. 2</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: WESTBOUND				Location 1: 03-Pla-80-KP 71.7 to KP 79.4 (Drum Forebay OC to Alta Rd. UC)																				
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays	1	1	1	1	1	1	1	1												1	1	1	1	1
Tuesdays through Thursdays	1	1	1	1	1	1	1	1	1											1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1													1	1	1
Saturdays	1	1	1	1	1	1	1	1														1	1	1
Sundays	1	1	1	1	1	1	1	1															1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

REMARKS: **THIS CHART ONLY FOR PLACEMENT OF PORTLAND CEMENT CONCRETE (PCC) PAVEMENT BETWEEN JUNE 15<sup>th</sup> AND LABOR DAY.**  
Two Lanes Available  
Ramp closure allowed during lane closure.

<b>Chart No. 3</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: EASTBOUND				Location 1: 03-Pla-80-KP 71.7 to KP 73.6 (Alta Rd. UC to Towle OH)																				
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Wednesdays	1	1	1	1	1	1	1	1	1	1	1						1	1	1	1	1	1	1	1
Thursdays	1	1	1	1	1	1	1	1	1	1								1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1															
Saturdays	1	1	1	1	1	1	1															1	1	1
Sundays	1	1	1	1	1	1	1	1	1													1	1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

REMARKS: **THIS CHART ONLY FOR PLACEMENT OF PORTLAND CEMENT CONCRETE (PCC) PAVEMENT BETWEEN LABOR DAY AND JUNE 15<sup>th</sup>.**  
Two Lanes Available.  
Ramp closure allowed during lane closure.

<b>Chart No. 4</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: WESTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 79.4 (Drum Forebay OC to Alta Rd. UC)												
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1												1	1	1
Saturdays	1	1	1	1	1	1	1	1														1	1	1
Sundays	1	1	1	1	1	1	1	1															1	1
Day before designated legal holiday & designated legal holidays																								
Legend:																								
<input type="checkbox"/> 1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel. <input type="checkbox"/> No closure allowed.																								
<b>REMARKS: THIS CHART ONLY FOR PLACEMENT OF PORTLAND CEMENT CONCRETE (PCC) PAVEMENT BETWEEN LABOR DAY AND JUNE 15<sup>th</sup>.</b> Two Lanes Available. Ramp closure allowed during lane closure.																								

<b>Chart No. 5</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: EASTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 73.6 (Alta Rd. UC to Towle OH)												
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Wednesdays	1	1	1	1	1	1	1	1	1	1	1							1	1	1	1	1	1	1
Thursdays	1	1	1	1	1	1	1	1	1	1	1							1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1														1
Saturdays	1	1	1	1	1	1	1	1										1	1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1								1	1	1	1	1	1	1
Day before designated legal holiday & designated legal holidays																								
Legend:																								
<input type="checkbox"/> 1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel. <input type="checkbox"/> No closure allowed.																								
<b>REMARKS: THIS CHART ONLY FOR PLACEMENT OF ASPHALT CONCRETE (AC) PAVEMENT BETWEEN JUNE 15<sup>th</sup> AND LABOR DAY.</b> Two Lanes Available. Ramp closure allowed during lane closure.																								

<b>Chart No. 6</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: WESTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 79.4 (Towle OH to Alta Rd. UC)												
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9		10
Mondays	1	1	1	1	1	1	1	1	1	1								1	1	1	1	1	1	1
Tuesdays through Thursdays	1	1	1	1	1	1	1	1	1	1	1					1	1	1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1								1	1	1	1	1	1	1
Saturdays	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1													1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

**REMARKS: THIS CHART ONLY FOR PLACEMENT OF ASPHALT CONCRETE (AC) PAVEMENT BETWEEN JUNE 15<sup>th</sup> AND LABOR DAY.**  
Two Lanes Available  
Ramp closure allowed during lane closure.

<b>Chart No. 7</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: EASTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 73.6 (Alta Rd. UC to Towle OH)												
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9		10
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1														1
Saturdays	1	1	1	1	1	1	1	1	1										1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1								1	1	1	1	1	1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

**REMARKS: THIS CHART ONLY FOR PLACEMENT OF ASPHALT CONCRETE (AC) PAVEMENT BETWEEN LABOR DAY AND JUNE 15<sup>th</sup>.**  
Two Lanes Available.  
Ramp closure allowed during lane closure.

<b>Chart No. 8</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: WESTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 79.4 (Towle OH to Alta Rd. UC)												
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9		10
Mondays	1	1	1	1	1	1	1	1	1	1							1	1	1	1	1	1	1	1
Tuesdays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1	1								1	1	1	1	1	1
Saturdays	1	1	1	1	1	1	1	1	1	1										1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1												1	1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

REMARKS: **THIS CHART ONLY FOR PLACEMENT OF ASPHALT CONCRETE (AC) PAVEMENT BETWEEN LABOR DAY AND JUNE 15<sup>th</sup>.**  
Two Lanes Available.  
Ramp closure allowed during lane closure.

<b>Chart No. 9</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: EASTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 73.6 (Alta Rd. UC to Towle OH)												
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9		10
Mondays through Wednesdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Thursdays	1	1	1	1	1	1	1	1	1	1	1	1						1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1														1
Saturdays	1	1	1	1	1	1	1	1											1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

REMARKS: **THIS CHART FOR ALL OTHER WORK BETWEEN JUNE 15<sup>th</sup> AND LABOR DAY EXCEPT AS NOTED HEREIN.**  
Two Lanes Available.  
Ramp closure allowed during lane closure.

<b>Chart No. 10</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: WESTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 79.4 (Drum Forebay OC to Alta Rd. UC)												
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9		10
Mondays	1	1	1	1	1	1	1	1	1	1							1	1	1	1	1	1	1	1
Tuesdays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1	1
Saturdays	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1												1	1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

REMARKS: **THIS CHART FOR ALL OTHER WORK BETWEEN JUNE 15<sup>th</sup> AND LABOR DAY EXCEPT AS NOTED HEREIN.**  
Two Lanes Available.  
Ramp closure allowed during lane closure.

<b>Chart No. 11</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: EASTBOUND												Location 1: 03-Pla-80-KP 71.7 to KP 73.6 (Alta Rd. UC to Towle OH)												
FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9		10
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1	1	1											1	1
Saturdays	1	1	1	1	1	1	1											1	1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1								1	1	1	1	1	1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

REMARKS: **THIS CHART FOR ALL OTHER WORK BETWEEN LABOR DAY AND JUNE 15<sup>th</sup> EXCEPT AS NOTED HEREIN.**  
Two Lanes Available.  
Ramp closure allowed during lane closure.

**Chart No. 12  
Multilane and Ramp Lane Requirements**

Direction: WESTBOUND      Location 1: 03-Pla-80-KP 71.7 to KP 79.4 (Drum Forebay OC to Alta Rd. UC)

FROM HOUR TO HOUR	a.m.											p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1
Saturdays	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1													1	1	1
Day before designated legal holiday & designated legal holidays																								

Legend:

1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel.

No closure allowed.

**REMARKS: THIS CHART FOR ALL OTHER WORK BETWEEN LABOR DAY AND JUNE 15<sup>th</sup> EXCEPT AS NOTED HEREIN.**  
Two Lanes Available.  
Ramp closure allowed during lane closure.

**Chart No. 13  
Multilane Lane Requirements**

Direction: EASTBOUND/WESTBOUND      Location 2: 03-Pla-80-KP 78.1 to KP 90.2

FROM HOUR TO HOUR	a.m.											p.m.													
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1	1	1															1	1	1
Fridays	1	1	1	1	1	1	1																		
Saturdays	1	1	1	1	1	1	1																1	1	
Sundays	1	1	1	1	1	1	1	1															1	1	
Day before designated legal holiday & designated legal holidays																									

Legend:

1 One lane, a minimum of 3.3 m wide shall be open in each direction of travel.

No closure allowed.

**REMARKS: THIS CHART ONLY FOR CONSTRUCTING MEDIAN CROSS-OVER.**

Chart No. 14																								
Multilane and Ramp Lane Requirements																								
Direction: EASTBOUND Location 2: 03-Pla-80-KP 78.1 to KP 90.2 (Drum Forebay OC to Carpenter Flat UC)																								
FROM HOUR TO HOUR	a.m.												p.m.											
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Thursdays	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Fridays	2	2	2	2	2	2	2	2	2													2	2	2
Saturdays	2	2	2	2	2	2	2	2														2	2	2
Sundays	2	2	2	2	2	2	2	2	2													2	2	2
Day before designated legal holiday & designated legal holidays																								
Legend:																								
<input type="checkbox"/> 2 Two lanes open in direction of travel. <input type="checkbox"/> No closure allowed.																								
REMARKS: <b>THIS CHART FOR ALL WORK WITH MEDIAN CROSS-OVER IN EFFECT EXCEPT AS NOTED HEREIN.</b> Ramp closure allowed during lane closure.																								

Chart No. 15																									
Multilane and Ramp Lane Requirements																									
Direction: WESTBOUND Location 2: 03-Pla-80-KP 78.1 to KP 90.2 (Carpenter Flat UC to Drum Forebay OC)																									
FROM HOUR TO HOUR	a.m.												p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1											1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1													1	1	1
Saturdays	1	1	1	1	1	1	1	1														1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1															1	1
Day before designated legal holiday & designated legal holidays																									
Legend:																									
<input type="checkbox"/> 1 One lane, a minimum of 3.3 m wide, shall be open in direction of travel. <input type="checkbox"/> No closure allowed.																									
REMARKS: <b>THIS CHART FOR ALL WORK.</b> Ramp closure allowed during lane closure.																									

<b>Chart No. 16</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: EASTBOUND Location 2: 03-Pla-80-KP 78.1 to KP 84.8 (Drum Forebay OC to Blue Canyon UC)																								
FROM HOUR TO HOUR	a.m.												p.m.											
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Thursdays	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Fridays	2	2	2	2	2	2	2	2	2	2														2
Saturdays	2	2	2	2	2	2	2	2											2	2	2	2	2	2
Sundays	2	2	2	2	2	2	2	2	2	2									2	2	2	2	2	2
Day before designated legal holiday & designated legal holidays																								
Legend:																								
<input type="checkbox"/> 2 Two lanes open in direction of travel. <input type="checkbox"/> No closure allowed.																								
REMARKS: <b>THIS CHART FOR ALL WORK WHEN MEDIAN CROSS-OVER IS NOT IN EFFECT.</b> Where three Lanes are normally available. Ramp closure allowed during lane closure.																								

<b>Chart No. 17</b>																								
<b>Multilane and Ramp Lane Requirements</b>																								
Direction: EASTBOUND Location 2: 03-Pla-80-KP 84.8 to KP 90.2 (Blue Canyon UC to Carpenter Flat UC)																								
FROM HOUR TO HOUR	a.m.												p.m.											
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Wednesdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Thursdays	1	1	1	1	1	1	1	1	1	1	1	1						1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1														1
Saturdays	1	1	1	1	1	1	1	1											1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	1	1	1									1	1	1	1	1	1
Day before designated legal holiday & designated legal holidays																								
Legend:																								
<input type="checkbox"/> 1 One lane, a minimum of 3.6 m wide, shall be open in direction of travel. <input type="checkbox"/> No closure allowed.																								
REMARKS: <b>THIS CHART FOR ALL WORK WHEN MEDIAN CROSS-OVER IS NOT IN EFFECT.</b> Where two Lanes are normally available. Ramp closure allowed during lane closure.																								

**ENGINEER'S ESTIMATE  
03-1A8014**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
81	377501	SLURRY SEAL	TONN	320		
82	390095	REPLACE ASPHALT CONCRETE SURFACING	M3	850		
83	390155	ASPHALT CONCRETE (TYPE A)	TONN	15 600		
84	394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	M2	620		
85	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	2650		
86	394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	M	1860		
87	394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	M	1750		
88	394049	PLACE ASPHALT CONCRETE DIKE (TYPE F)	M	1890		
89	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	14		
90	401000	CONCRETE PAVEMENT	M3	74 800		
91	032317	INTERMEDIATE PAVEMENT ANCHOR	EA	12		
92	401082	SHOULDER RUMBLE STRIP (PCC, GROUND-IN INDENTATIONS)	STA	18		
93	404092	SEAL PAVEMENT JOINT	M	111 000		
94	BLANK					
95 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	3		
96	049597	STRUCTURE CONCRETE APPROACH SLAB (TYPE R(9D))	M3	217		
97	049598	STRUCTURE CONCRETE APPROACH SLAB (TYPE(9S))	M3	153		
98	032318	MINOR CONCRETE (SHOULDER BARRIER SLAB AND FOOTING)	M3	920		
99 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	304		
100	510800	PAVING NOTCH EXTENSION	M3	5.5		