

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY (916) 227-8454



*Flex your power!
Be energy efficient!*

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

October 30, 2006

03-Sac-51-1.7/8.2
03-1E6804

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SACRAMENTO COUNTY FROM 1.7 KM NORTH OF THE 50/99/51 SEPARATION TO 0.6 KM SOUTH OF THE MARCONI AVENUE OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on November 8, 2006.

This addendum is being issued to revise the Notice to Contractors and Special Provisions.

In the Special Provisions, Section 4, "BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES," the third sentence is revised as follows:

"The work shall be diligently prosecuted to completion before the expiration of **80 WORKING DAYS** beginning on the date that work begins or beginning on the sixtieth day after approval of the contract, whichever occurs first."

In the Special Provisions, Section 10-1.255, "RAPID STRENGTH CONCRETE (STRUCTURE APPROACH SLAB)," is added as attached.

In the Special Provisions, Section 10-1.25, "STRUCTURE APPROACH SLABS (TYPE R)," subsection "MEASUREMENT AND PAYMENT," the fourth paragraph is revised as follows:

"Full compensation for aggregate base (approach slab) shall be considered as included in the contract unit price paid per cubic meter for structural concrete approach slab (Type R) and no separate payment will be made therefor."

Addendum No. 1
Page 2
October 30, 2006

03-Sac-51-1.7/8.2
03-1E6804

To Proposal and Contract book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO CONTRACTORS section of the Notice to Contractors and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum is available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

JODY JONES
District 3 Director

Attachment

10-1.255 RAPID STRENGTH CONCRETE (Structure Approach Slab)

At the Contractor's option, rapid strength concrete for structure approach slabs may be used.

Rapid Strength Concrete (RSC) shall be a concrete made with hydraulic cement that develops opening age and 28 day specified compressive strength.

The opening age is the age at which the concrete will achieve the specified strength for opening to public or Contractor traffic.

RSC shall attain a compressive strength of 25 Mpa at opening age.

Requirements of Sections 40-1.015, "Cement Content," 40-1.05, "Proportioning," and 90-1.01, "Description," of the Standard Specifications shall not apply.

Combined aggregate grading used in RSC shall be either the 37.5-mm, maximum grading, or 25-mm, maximum grading, at the option of the Contractor.

Cement for RSC shall be hydraulic cement as defined in ASTM Designation: C 219 and shall conform to the following requirements:

Test Description	Test Method	Requirement
Contraction in Air	California Test 527, W/C Ratio = 0.39 ± 0.010	0.053 %, max.
Mortar Expansion in Water	ASTM Designation: C 1038	0.04 %, max.
Soluble Chloride*	California Test 422	0.05 %, max.
Soluble Sulfates*	California Test 417	0.30 %, max.
Thermal Stability	California Test 553	60 %, min.
Compressive Strength @ 3 days	ASTM Designation: C 109	17 MPa

*Test is to be done on a cube specimen, fabricated in conformance with the requirements in ASTM Designation: C 109, cured at least 14 days and then pulverized to 100% passing the 300- μ m sieve

At least 45 days prior to intended use, the Contractor shall furnish a sample of cement from each lot proposed for use and all admixtures proposed for use in the quantities ordered by the Engineer.

The Contractor shall submit uniformity reports for cement used in RSC to the Engineer. Uniformity reports shall conform to the requirements in ASTM Designation: C 917, except that testing age and water content may be modified to suit the particular material. Uniformity reports shall be submitted at least every 30 days during RSC pavement operations.

Type C accelerating chemical admixtures conforming to the provisions in Section 90-4, "Admixtures," of the Standard Specifications may be used. In addition to the admixtures listed on the Department's current list of approved admixtures, citric acid or borax may be used if requested in writing by the cement manufacturer and a sample is submitted to the Engineer. Chemical admixtures, if used, shall be included in the testing for requirements listed in the table above.

At least 10 days prior to use in the trial slab, the Contractor shall submit a mix design for each RSC that shall include the following:

- A. Opening age
- B. Proposed aggregate gradings
- C. Mix proportions of hydraulic cement and aggregate
- D. Types and amounts of chemical admixtures
- E. Maximum time allowed between batching RSC and placing roadway pavement
- F. Range of ambient temperatures over which the mix design is effective (10°C maximum range)
- G. Final set time of the concrete
- H. Any special instructions or conditions, including but not limited to, water temperature requirements when appropriate

Concrete pavement penetration requirements in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications shall not apply to RSC.

Compressive strength at early age may be estimated using the correlation established during trial slab placement or by using results from cylinder specimens cured under atmospheric conditions and at a temperature within 3°C of the pavement. Compressive strength at other ages will be determined using cylinders cured and tested in conformance with California Tests 521 and 540. The Engineer will perform the testing to determine compressive strength values of the RSC pavement. The compressive strength as determined above, will be the basis for accepting or rejecting the RSC pavement for compressive strength requirements.

Proportioning

Weighing, measuring and metering devices used for proportioning materials shall conform to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications and these special provisions.

Over and under dials, and other indicators for weighing and measuring systems used in proportioning materials shall be grouped so that the smallest increment for each indicator can be accurately read from the point at which the proportioning operation is controlled for ingredients batched at a central batch plant. In addition, indicators for weighing and measuring cement batched from a remote weighing system shall also be placed so that each indicator can be accurately read from the point at which the proportioning operation is controlled.

Aggregates shall be handled and stored in conformance with the provisions in Section 90-5.01, "Storage of Aggregates," of the Standard Specifications. Liquid admixtures shall be proportioned in conformance with the provisions in Section 90-4.10, "Proportioning and Dispensing Liquid Admixtures," of the Standard Specifications. Mineral admixtures shall be protected from exposure to moisture until used. Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures to easily track the materials that are entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.

Weighing equipment shall be insulated against vibration or movement of other operating equipment. When the plant is in operation, the mass of each draft of material shall not vary from the designated mass by more than the tolerances specified herein. Each scale graduation shall be 0.001 of the usable scale capacity.

Aggregate shall be weighed cumulatively and equipment for the weighing of aggregate shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the aggregate. Equipment for the separate weighing of the cement or mineral admixture shall have a zero tolerance of ± 0.5 percent of their designated individual batch drafts. Equipment for measuring water shall have a zero tolerance of ± 0.5 percent of its designated mass or volume.

The mass indicated for any individual batch of material shall not vary from the preselected scale setting by more than the following:

Material	Tolerance
Aggregate	± 1.0 percent of designated batch mass
Cement	± 0.5 percent of designated batch mass
Mineral Admixture	± 1.0 percent of designated batch mass
Water	± 1.5 percent of designated batch mass or volume

Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement, mineral admixture and water as provided in these special provisions. Dry ingredients shall be proportioned by mass. Liquid ingredients shall be proportioned by mass or volume.

At the time of batching, aggregates shall have been dried or drained sufficiently to result in stable moisture content, so that no visible separation of water from aggregate will take place during the proportioning process. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

If separate supplies of aggregate material of the same size group with different moisture content or specific gravity or surface characteristics affecting workability are available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another supply.

Cement shall be kept separate from the aggregates until released for discharge into the mixer. Cement shall be free of lumps and clods when discharged into the mixer. Fabric containers used for transportation or proportioning of cement shall be clean and free of residue before reuse.

Weigh systems for proportioning aggregate, cement, and mineral admixture shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and distinct material-weighing device.

For batches with a volume of one cubic meter or more, proportioning equipment shall conform to one of the following methods:

- A. All ingredients shall be batched at a central batch plant and charged into a mixer truck for transportation to the pour site. Ingredient proportioning shall meet the requirements of Section 90-5, "Proportioning," of the Standard Specifications.
- B. All ingredients except the cement shall be batched at a central batch plant and charged into a mixer truck for transportation to a remote located silo and weigh system for the proportioning of the cement. The remote system shall proportion cement for charging the mixer truck.

- C. All ingredients except the cement shall be batched at a central batch plant and charged into a mixer truck for transportation to a remote location where pre-weighed, containerized cement shall be added to the mixer truck. The cement pre-weighing operation shall utilize a platform scale. The platform scale shall have a maximum capacity of 2.5 tonnes with a maximum graduation size of 0.5 kilograms. Cement shall be pre-weighed into a fabric container. The minimum amount of cement to be proportioned into any single container shall be one half of the total amount required for the load of RSC being produced.
- D. Cement, water, and aggregate shall be proportioned volumetrically in conformance with these special provisions.

In order to check the accuracy of batch masses, the gross mass and tare mass of truck mixers shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

The Contractor shall install and maintain in operating condition an electrically actuated moisture meter. The meter shall indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched. The meter shall have a sensitivity of 0.5 percent by mass of the fine aggregate.

No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced. Water added to the truck mixer at the job site shall be measured through a meter that conforms to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications.

Aggregate discharged from several bins shall be controlled by gates or by mechanical conveyors. The means of discharge from the bins and from the weigh hopper shall be interlocked so that no more than one bin can discharge at a time, and so that the weigh hopper can not be discharged until the required quantity from each of the bins has been deposited in the weigh hopper.

Weighmaster Certificates

Weighmaster certificates for RSC, regardless of the proportioning method used, shall include all information necessary to trace the manufacturer, and manufacturer's lot number for the cement being used. When proportioned into fabric containers the weighmaster certificates for the cement shall contain date of proportioning, location of proportioning and actual net draft mass of the cement. When proportioned at the pour site from a storage silo the weighmaster certificates shall contain date of proportioning, location of proportioning and the net draft mass of the cement used in the load.

Volumetric Proportioning

When RSC is proportioned by volume, the method shall conform to requirements specified herein.

Aggregates shall be handled and stored in conformance with the provisions in Section 90-5.01, "Storage of Aggregates," of the Standard Specifications. Liquid admixtures shall be proportioned in conformance with the provisions in Section 90-4.10, "Proportioning and Dispensing Liquid Admixtures," of the Standard Specifications. Mineral admixtures shall be protected from exposure to moisture until used. Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures in order to prevent any but the specified mineral admixtures from entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the batch-mixer storage hopper or in the feed line.

Batch-mixer trucks shall be equipped to proportion cement, water, aggregate and additives by volume. Aggregate feeders shall be connected directly to the drive on the cement vane feeder. The cement feed rate shall be tied directly to the feed rate for the aggregate and other ingredients. Any change in the ratio of cement to aggregate shall be accomplished by changing the gate opening for the aggregate feed. The drive shaft of the aggregate feeder shall be equipped with a revolution counter reading to the nearest full or partial revolution of the aggregate delivery belt.

Aggregate shall be proportioned using a belt feeder operated with an adjustable cutoff gate delineated to the nearest quarter increment. Height of the gate opening shall be readily determinable. Cement shall be proportioned by a method that conforms to the accuracy requirements of these special provisions. Water shall be proportioned by a meter conforming to the provisions in Section 9-1.01, "Measurement and Payment," of the Standard Specifications and these special provisions.

Delivery rate of aggregate and cement per revolution of the aggregate feeder shall be calibrated at appropriate gate settings for each batch-mixer truck used on the project and for each aggregate source. Batch-mixer trucks shall be calibrated at 3 different aggregate gate settings that are commensurate with production needs. Two or more calibration runs shall be required at each of the different aggregate gate openings. The actual mass of material delivered for aggregate proportioning device calibrations shall be determined by a platform scale as specified in these special provisions.

Aggregate belt feeder shall deliver aggregate to the mixer with volumetric consistency so that deviation for any individual aggregate delivery rate check-run shall not exceed 1.0 percent of the mathematical average of all runs for the same gate opening and aggregate type. Each test run shall be at least 500 kg. Fine aggregate used for calibration shall not be reused for device calibration.

At the time of batching, aggregates shall be dried or drained sufficiently to result in stable moisture content, so that no visible separation of water from aggregate takes place during the proportioning process. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

If separate supplies of aggregate material of the same size group with different moisture content or specific gravity or surface characteristics affecting workability are available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting another supply.

Rotating and reciprocating equipment on batch-mixer trucks shall be covered with metal guards.

The cement proportioning system shall deliver cement to the mixer with a volumetric consistency so that the deviation for any individual delivery rate check-run shall not exceed 1.0 percent of the mathematical average of 3 runs of at least 500 kg each. Cement used for calibration shall not be reused for device calibration.

Water meter accuracy shall be such that, when operating between 50 percent and 100 percent of production capacity, the difference between the indicated mass of water delivered and the actual mass delivered shall not exceed 1.5 percent of the actual mass for each of two individual runs of 1200 liters. The water meter shall be calibrated in conformance with the requirements of California Test 109 and shall be equipped with a resettable totalizer and display the operating rate.

Calibration tests for aggregate, cement and water proportioning devices shall be conducted with a platform scale located at the calibration site. Weighing of test run calibration material shall be performed on a platform scale having a maximum capacity not exceeding 2.5 tonnes with maximum graduations of 0.5-kg. The platform scale shall be error tested within 8 hours of calibration of batch-mixer truck proportioning devices. Error testing shall be performed with test masses conforming to California Test 109 and shall produce a witness scale that is within 2 graduations of the test mass load. The scale shall be available for use at the production site throughout the production period. Equipment needed for the calibration of proportioning systems shall remain available at the production site throughout the production period. A Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished with each delivery of aggregate, cement, and admixtures used for calibration tests and shall be submitted to the Engineer with a certified copies of the mass of each delivery. The Certificate of Compliance shall state that the source of materials used for the calibration tests is from the same source as to be used for the planned work. The Certificate of Compliance shall state that the material supplied conforms to the Standard Specifications and these Special Provisions and shall be signed by an authorized representative who shall have the authority to represent and act for the Contractor.

The batch-mixer truck shall be equipped so that an accuracy check can be made prior to the first operation for the project and at any other time as directed by the Engineer. Further calibration of proportioning devices shall be required every 30 days after production begins or when the source or type of any ingredient is changed. A spot calibration shall consist of calibration of the cement proportioning system only. A two run spot re-calibration of the cement proportioning system shall be performed each time 50 tonnes of cement has passed through the batch-mixer truck. Should the spot re-calibration of the cement proportioning system fall outside the limitations specified herein, a full calibration of the cement proportioning system shall be completed before the resumption of production.

Liquid admixtures shall be proportioned by a meter.

Cement storage shall be located immediately before the cement feeder and shall be equipped with a device that will automatically shut down the power to the cement feeder and aggregate belt feeder when the cement storage level is lowered to a point where less than 20 percent of the total volume is left in storage.

The Contractor shall furnish aggregate moisture determinations, made in conformance with the requirements of California Test 223, at least every 2 hours during proportioning and mixing operations. Moisture determinations shall be recorded and presented to the Engineer at the end of the production shift.

Each aggregate bin shall be equipped with a device that will automatically shut down the power to the cement feeder and the aggregate belt feeder when the aggregate discharge rate is less than 95 percent of the scheduled discharge rate of any bin.

Indicators specified herein shall be in working order prior to commencing proportioning and mixing operations and shall be visible when standing near the batch-mixer truck.

Identifying numbers of batch-mixer trucks shall be at least 75 mm in height, and be located on the front and rear of the vehicles.

Volumetric proportioned RSC shall be mixed in a mechanically operated mixer of adequate size and power for the type of RSC to be placed. Mixers may be of the auger type and shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers that have an accumulation of hard concrete or mortar shall be removed from service until cleaned. Other types of mixers may be used provided mixing quality will meet the requirements of these special provisions.

Charge or rate of feed to the mixer shall not exceed that which will permit complete mixing of the materials. Dead areas in the mixer, where material does not move or is not sufficiently agitated, shall be corrected by a reduction in the volume of material or by other adjustments. The mixer shall be designed to provide sufficient mixing action and movement to produce properly mixed RSC. Mixing shall continue until a homogeneous mixture is produced at discharge from the mixer. There shall be no lumps or evidence of non-dispersed cement at discharge from the mixer. No water shall be added to the RSC after discharge from the mixer.

Equipment having components made of aluminum or magnesium alloys, which may have contact with plastic concrete during mixing or transporting of RSC, shall not be used.

Uniformity of concrete mixtures will be determined by differences in penetration measurement made in conformance with the requirements in California Test 533. Difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 15 mm. The Contractor shall furnish samples of freshly mixed concrete and provide facilities for obtaining the samples. Sampling facilities shall be safe, accessible, clean and produce a sample which is representative of production. Sample devices and sampling methods shall also conform to the requirements of California Test 125.

Ice shall not be used to cool RSC directly. When ice is used to cool water used in the mix, all of the ice shall be melted before entering the mixer.

Cement shall be proportioned and charged into the mixer by means that will result in no losses of cement due to wind, or due to accumulation on equipment, or other conditions which will vary the required quantity of cement.

Each mixer shall have a metal plate or plates, prominently attached, on which the following information is provided:

- A. Uses for which the equipment is designed.
- B. Manufacturer's guaranteed capacity of the mixer in terms of the volume of mixed concrete.
- C. Speed of rotation of the mixer.

Consistency and workability of mixed concrete when discharged at the delivery point shall be suitable for placement and consolidation.

Information generated by volumetric devices will not be used for payment calculations.

The device that controls the proportioning of cement, aggregate and water shall produce a log of production data. The log of production data shall consist of a series of snapshots captured at 15-minute intervals throughout the period of daily production. Each snapshot of production data shall be a register of production activity at that time and not a summation of the data over the preceding 15 minutes. The amount of material represented by each snapshot shall be the amount produced in the period of time from 7.5 minutes before to 7.5 minutes after the capture time. The daily log shall be submitted to the Engineer, in electronic or printed media, at the end of each production shift or as requested by the Engineer, and shall include the following:

- A. Mass of cement per revolution count.
- B. Mass of each aggregate size per revolution count.
- C. Gate openings for each aggregate size being used.
- D. Mass of water added to the concrete per revolution count.
- E. Moisture content of each aggregate size being used.
- F. Individual volume of all other admixtures per revolution count.
- G. Time of day.
- H. Day of week.
- I. Production start and stop times.
- J. Batch-mixer truck identification.
- K. Name of supplier.
- L. Specific type, size, or designation of concrete being produced.
- M. Source of the individual aggregate sizes being used.
- N. Source, brand and type of cement being used.
- O. Source, brand and type of individual admixtures being used.
- P. Name and signature of operator.

Required report items may be input by hand into a pre-printed form or captured and printed by the proportioning device. Electronic media containing recorded production data shall be presented in a tab delimited format on a 90-mm diskette with a capacity of at least 1.4 megabytes. Each snapshot of the continuous production shall be followed by a line-feed carriage-return with allowances for sufficient fields to satisfy the amount of data required by these specifications. The reported data shall be in the above order and shall include data titles at least once per report.

Spreading, Compacting and Shaping

Metal or wood side forms may be used. Wood side forms shall not be less than 38-mm thick. Side forms shall be of sufficient rigidity, both in the form and in the connection with adjoining forms, that movement will not occur under the force from subgrading and paving equipment or from the pressure of concrete.

Side forms shall remain in place until the pavement edge no longer requires the protection of forms. Side forms shall be thoroughly cleaned and oiled prior to each use.

Consolidation of RSC shall be by means of high-frequency internal vibrators after the RSC is deposited on the subgrade. Vibrating shall be done in a manner to assure uniform consolidation adjacent to forms and across the full paving width. RSC shall be placed as nearly as possible in its final position and use of vibrators for extensive shifting of the mass of RSC will not be permitted.

RSC shall be spread and shaped by suitable powered finishing machines and supplemented by hand finishing as necessary. Methods of spreading, shaping and consolidating that result in segregation, voids or rock pockets shall be discontinued. The Contractor shall use methods that will produce dense homogeneous pavement conforming to the required cross section.

After the RSC has been mixed and placed, no additional water shall be added to the surface to facilitate finishing. Surface finishing additives, when used, shall be as recommended by the manufacturer of the cement and shall be approved by the Engineer prior to use.

Curing Method

The curing method for replacement pavement shall be as recommended by the manufacturer of the cement and as approved by the Engineer.

If the ambient temperature is below 18°C during the curing period, an insulating layer or blanket shall cover the surface. The insulation layer or blanket shall have an R-value rating given in the table below. At the Contractor's option, a heating tent may be used in lieu of or in combination with the insulating layer or blanket:

Temperature range during curing period	R-value, minimum
13°C to 18°C	1
7°C to 13°C	2
4°C to 7°C	3