

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

July 31, 2002

03-Yub-70-0.7/11.8
03-376104
ACNH-P070(078)E

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in YUBA COUNTY ABOUT 12 KM SOUTH OF MARYSVILLE FROM 0.1 KM NORTH OF FEATHER RIVER BOULEVARD TO MCGOWAN PARKWAY.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on August 13, 2002.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, the Proposal and Contract, and the Federal Minimum Wages with Modification Number 12 dated 7-19-02. A copy of the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

Project Plan Sheets 149 and 152 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.30, "EROSION CONTROL (DRILL SEED)", the second sentence of the second paragraph is revised as follows:

"A strip 1 meter wide adjacent to the edge of pavement shall not be seeded."

03-Yub-70-0.7/11.8
03-376104
ACNH-P070(078)E

In the Special Provisions, Section 10-1.30, "EROSION CONTROL (DRILL SEED)", subsection "MATERIALS," the table for item "E" under "Legume Seed" is revised as follows:

| LEGUME SEED | | |
|---|----------------------------------|--|
| Botanical Name (Common Name) | Percent Germination (Minimum) | Kilograms Pure Live Seed Per Hectare (Slope Measurement) |
| * Lotus purshianus (Purshings Lotus) | 40 | 3.0 |
| * Lupinus nanus (Lupinus nanus) | 40 | 4.0 |
| * Lupinus bicolor (Lupine) | 50 | 5.0 |

Note: Pure live seed shall be determined by multiplying the percentage of purity by the percentage of germination.

* California Native

In the Special Provisions, Section 10-1.30, "EROSION CONTROL (DRILL SEED)", subsection "MATERIALS," the table under "Non-Legume Seed," is revised as follows:

| NON-LEGUME SEED | | |
|---|----------------------------------|--|
| Botanical Name (Common Name) | Percent Germination (Minimum) | Kilograms Pure Live Seed Per Hectare (Slope Measurement) |
| *Nessella pulchra (Purple Needlegrass) | 40 | 6.0 |
| *Bromus carinatus (California Brome) | 40 | 6.0 |
| *Elymus glaucus (Blue Wildrye) | 40 | 10.0 |
| Leymus triticoides (Creeping Wildrye) | 40 | 12.0 |
| *Poa secunda (Pine Bluegrass) | 40 | 2.0 |
| *Gilia tricolor (Bird's Eyes) | 40 | 1.0 |

Note: Pure live seed shall be determined by multiplying the percentage of purity by the percentage of germination.

* California Native

03-Yub-70-0.7/11.8
03-376104
ACNH-P070(078)E

In the Special Provisions, Section 10-1.32, "EROSION CONTROL (TYPE C)," subsection "APPLICATION," the table under item "B" is revised as follows:

| Material | Kilograms Per Hectare (Slope Measurement) |
|-----------------------|--|
| Legume Seed | 12 |
| Non-Legume Seed | 37 |
| Fiber | 1000 |
| Compost | 4000 |
| Commercial Fertilizer | 800 |

In the Special Provisions, Section 10-1.33, "EROSION CONTROL (TYPE D)," subsection "APPLICATION," the table under item "A" is revised as follows:

| Material | Kilograms Per Hectare (Slope Measurement) |
|-----------------------|--|
| Legume Seed | 12 |
| Non-Legume Seed | 37 |
| Fiber | 500 |
| Compost | 1500 |
| Commercial Fertilizer | 400 |

In the Proposal and Contract, the Engineer's Estimate Items 58 and 59 are revised as attached.

To Proposal and Contract book holders:

Attached is a copy of the Materials Information which is the revised foundation recommendation dated November 26, 2001.

Replace page 5 of the Engineer's Estimate in the Proposal with the attached revised page 5 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY:

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

ENGINEER'S ESTIMATE

03-376104

| Item | Item Code | Item | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|--------|-----------|--|-----------------|--------------------|------------|------------|
| 41 (S) | 024233 | COLD PLANE ASPHALT CONCRETE PAVEMENT (65 MM MAXIMUM) | M2 | 4460 | | |
| 42 | 024234 | REMOVE CONCRETE (BRIDGE) | M3 | 65 | | |
| 43 | 160101 | CLEARING AND GRUBBING | LS | LUMP SUM | LUMP SUM | |
| 44 | 190101 | ROADWAY EXCAVATION | M3 | 45 000 | | |
| 45 | 190110 | LEAD COMPLIANCE PLAN | LS | LUMP SUM | LUMP SUM | |
| 46 (F) | 192003 | STRUCTURE EXCAVATION (BRIDGE) | M3 | 655 | | |
| 47 (F) | 193003 | STRUCTURE BACKFILL (BRIDGE) | M3 | 402 | | |
| 48 | 198001 | IMPORTED BORROW | M3 | 343 000 | | |
| 49 | 198007 | IMPORTED MATERIAL (SHOULDER BACKING) | TONN | 3930 | | |
| 50 (S) | 203003 | STRAW (EROSION CONTROL) | TONN | 30 | | |
| 51 (S) | 024235 | STRAW (DRILL SEED) | TONN | 95 | | |
| 52 (S) | 203014 | FIBER (EROSION CONTROL) | KG | 5250 | | |
| 53 (S) | 024236 | FIBER (DRILL SEED) | KG | 27 000 | | |
| 54 (S) | 203024 | COMPOST (EROSION CONTROL) | KG | 21 000 | | |
| 55 (S) | 024237 | MYCORRHIZAL INOCULUM (DRILL SEED) | KG | 240 | | |
| 56 (S) | 024238 | COMPOST (DRILL SEED) | KG | 108 000 | | |
| 57 | 203026 | MOVE-IN/MOVE-OUT (EROSION CONTROL) | EA | 6 | | |
| 58 (S) | 203045 | PURE LIVE SEED (EROSION CONTROL) | KG | 260 | | |
| 59 (S) | 024239 | PURE LIVE SEED (DRILL SEED) | KG | 1330 | | |
| 60 (S) | 203056 | COMMERCIAL FERTILIZER (EROSION CONTROL) | KG | 4200 | | |