

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.  
Help save water!*

September 19, 2014

03-Sac-50-17.1

03-4F0704

Project ID 0314000020

ACNH-P050(135)

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SACRAMENTO COUNTY AT NATOMA OVERHEAD.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, September 24, 2014.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, and the *Bid* book.

Project plan sheet 54 is replaced and attached for substitution for the like-numbered sheet.

Project plan sheet 103A is added and attached for addition to the project plans.

In the *Notice to Bidders and Special Provisions*, in the "STANDARD PLANS LIST," the following Standard Plans are added as follows:

"T54 and T55."

In the Special Provisions, Section 12-4.05C, "Chart no. 3," is replaced as attached.

In the *Bid* book, pages 5 and 6 are replaced as attached.

The *Information Handout* is replaced as attached.

Addendum No. 2  
Page 2  
September 19, 2014

03-Sac-50-17.1  
03-4F0704  
Project ID 0314000020  
ACNH-P050(135)

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/03/03-4F0704](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/03/03-4F0704)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



AMARJEET BENIPAL  
District Director

Attachments

Replace "Reserved" in section 12-4.05C with:

Chart no. 3 Complete Expressway Closure Hours																									
County: Sac.													Route/Direction: US 50 EB										PM: 17.1		
Closure limits: Folsom Blvd- NB or SB																									
Hour	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon-Thu	C	C	C	C																					
Fri	C	C	C	C																					
Sat																									
Sun																									

Legend:

C Expressway may be closed completely

No complete Expressway closure is allowed

REMARKS:

1. This complete closure chart to be used at Folsom Blvd one direction at a time using RSP-T12, only during bridge falsework installing, removing or lowering operations.
2. When implementing RSP-T12, deploy flaggers to control all legs of intersections and place traffic signals on flashing red operation.
3. When SB Folsom Blvd is closed to public traffic, EB off ramp shall be closed.
4. When NB Folsom Blvd is closed to public traffic, WB off ramp shall be closed.
5. When a ramp is closed, public traffic shall be detoured to the preceding or next ramp as directed by the Engineer.

**BID ITEM LIST**  
**03-4F0704**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	150608	REMOVE CHAIN LINK FENCE	LF	50		
42	150661	REMOVE GUARDRAIL	LF	230		
43	150668	REMOVE FLARED END SECTION	EA	2		
44	027789	REMOVE THERMOPLASTIC TRAFFIC STRIPE (WATER BLASTING)	LF	8,650		
45	027790	REMOVE THERMOPLASTIC PAVEMENT MARKING (WATER BLASTING)	SQFT	380		
46	150742	REMOVE ROADSIDE SIGN	EA	19		
47	150808	REMOVE CULVERT (EA)	EA	1		
48	150814	REMOVE DOWNDRAIN (EA)	EA	2		
49	150820	REMOVE INLET	EA	2		
50	150857	REMOVE ASPHALT CONCRETE SURFACING	SQFT	21,270		
51	152320	RESET ROADSIDE SIGN	EA	1		
52	027791	ADJUST OVERHEAD CONTACT SYSTEM LINE FOR RT (RAILROAD WORK)	LS	LUMP SUM	LUMP SUM	
53	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	9,540		
54	153226	REFINISH BRIDGE DECK	SQFT	547		
55	153240	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK) (CY)	CY	11		
56	157560	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM	LUMP SUM	
57	190101	ROADWAY EXCAVATION	CY	4,510		
58	190185	SHOULDER BACKING	TON	53		
59 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	CY	708		
60 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	CY	505		

**BID ITEM LIST**  
**03-4F0704**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	198010	IMPORTED BORROW (CY)	CY	19,600		
62	202006	SOIL AMENDMENT	CY	3.3		
63	202038	PACKET FERTILIZER	EA	160		
64	204035	PLANT (GROUP A)	EA	65		
65	204036	PLANT (GROUP B)	EA	51		
66	204038	PLANT (GROUP U)	EA	12		
67	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM	LUMP SUM	
68	205035	WOOD MULCH	CY	110		
69	206005	EDGING	LF	380		
70	206400	CHECK AND TEST EXISTING IRRIGATION FACILITIES	LS	LUMP SUM	LUMP SUM	
71	206560	CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM	LUMP SUM	
72	206562	1" REMOTE CONTROL VALVE	EA	2		
73	206564	1 1/2" REMOTE CONTROL VALVE	EA	1		
74	208445	TREE WELL SPRINKLER ASSEMBLY	EA	68		
75	208448	RISER SPRINKLER ASSEMBLY	EA	94		
76	208575	2" GATE VALVE	EA	2		
77 (F)	208595	1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	1,130		
78 (F)	208596	1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	185		
79 (F)	208597	1 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	40		
80 (F)	208598	2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	75		