

**DEPARTMENT OF TRANSPORTATION**

ES-OE MS #43  
1727 30TH Street, 2ND Floor  
Sacramento, CA 95816



July 2, 2001

07-LA-5743  
07-115654

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for construction ADJACENT TO STATE HIGHWAY IN LOS ANGELES COUNTY IN MONROVIA AT FOOTHILL MAINTENANCE STATION AT 850 EAST HUNTINGTON DRIVE.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on July 12, 2001, instead of the original date of June 28, 2001.

This addendum is being issued to set a new bid opening date as shown herein, and to revise the Project Plans and the Notice to Contractors and Special Provisions.

Project Plan Sheet 60 is deleted.

Project Plan Sheet 60A is added. A half-sized copy of the added sheet is attached for addition to the Project Plans.

On Project Plan Sheet 25, on the right side of the sheet, the "10,999" dimension is changed to "15,927".

On Project Plan Sheet No. 18, the sheet number in the upper right hand corner, is revised to Sheet No. 22.

On Project Plan Sheet No. 19, the sheet number in the upper right hand corner, is revised to Sheet No. 23.

On Project Plan Sheet No. 20, the sheet number in the upper right hand corner, is revised to Sheet No. 18.

On Project Plan Sheet No. 21, the sheet number in the upper right hand corner, is revised to Sheet No. 19.

On Project Plan Sheet No. 22, the sheet number in the upper right hand corner, is revised to Sheet No. 20.

On Project Plan Sheet No. 23, the sheet number in the upper right hand corner, is revised to Sheet No. 21.

In the Special Provisions, Section 12-1.01, "SCOPE," the second paragraph is revised as follows:

"The building work to be done consists, in general, of demolishing the existing regional maintenance office building; constructing a new 600 square meter maintenance office building with concrete foundation, reinforced concrete tilt-up panel walls, wide flange beams with metal roof decking and torch applied roofing; constructing two canopies over existing material storage bins, one 270 square meters and one 140 square meters with cast-in-drilled-hole piles and steel tube columns; wide flange beams, prefinished metal wall panels and metal roof decking; constructing a 167 square meter bulk storage building with concrete

Addendum No. 2  
Page 2  
July 2, 2001

07-LA-5743  
07-115654

foundation, reinforced concrete tilt-up wall panels, wide flange beams with metal decking and torch applied roofing; constructing a 648 square meter equipment storage building with concrete foundation, reinforced concrete tilt-up panel walls, wide flange beams with metal roof decking and torch applied roofing; constructing a 22 square meter gas/oil log building with concrete foundation, concrete masonry walls; constructing fuel island, canopy and washrack with mud rinse slab; including mechanical and electrical and such other items or details, not mentioned above, that are required by the plans, Standard Specifications, or these special provisions shall be performed, placed, constructed or installed."

To Proposal and Contract book holders:

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief  
Plans, Specifications & Estimates Branch  
Office of Office Engineer

Attachment