

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!  
Be energy efficient!*

November 23, 2011

07-Ven,SB-101-R39.8/R43.6,0.0/2.2

07-260704

Project ID 0700000490

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN VENTURA AND SANTA BARBARA COUNTIES FROM MOBILE PIER UNDERCROSSING TO 0.4 MILE SOUTH OF CASITAS PASS ROAD.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, December 1, 2011.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions and the Bid book.

Project Plan Sheets 571, 572, 650 and 651 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.61, "SOUND WALL," subsection "DESCRIPTION," the first sentence of the first paragraph is revised as follows:

"This work shall consist of constructing sound walls of masonry block, including concrete pilasters, as shown on the plans."

In the Special Provisions, Section 10-1.61, "SOUND WALL," the following subsection is added after the subsection "SOUND WALL (MASONRY BLOCK)":

**"CONCRETE PILASTERS**

Concrete pilasters consist of reinforced cast-in-place colored concrete segments that are architecturally textured, as shown on the plans.

Concrete shall be structural concrete conforming to Section 90, "PORTLAND CEMENT CONCRETE," of the Standard Specifications.

Reinforcement shall conform to "REINFORCEMENT," of these special provisions.

Concrete coloring shall conform to "COLORED CONCRETE," of these special provisions, except that test panels are not required.

Architectural texturing shall be as shown on the plans and shall conform to "ARCHITECTURAL TREATMENT," of these special provisions, except that test panels are not required."

07-Ven,SB-101-R39.8/R43.6,0.0/2.2  
07-260704  
Project ID 0700000490

In the Special Provisions, Section 10-1.61, "SOUND WALL," subsection "MEASUREMENT AND PAYMENT," the following sentence is added after the first sentence of the first paragraph:

"The length for any sound wall shall be measured along the layout line of the wall from beginning to end without any breaks."

In the Special Provisions, Section 10-1.61, "SOUND WALL," subsection "MEASUREMENT AND PAYMENT," the following paragraph is added after the second paragraph:

"Full compensation for constructing concrete pilasters, complete in place, as shown on the plans, including reinforcement, coloring concrete and architectural texturing, shall be considered as included in the contract price paid per square foot for sound wall of the types designated in the Engineer's Estimate and no additional compensation will be allowed therefor."

In the Special Provisions, Section 10-1.63, "ARCHITECTURAL TREATMENT," subsection "CURING," the first paragraph is revised as follows:

"Concrete surfaces with architectural treatment shall be cured only by the forms-in-place."

In the Special Provisions, Section 10-1.64, "COLORED CONCRETE," the eleventh paragraph is revised as follows:

"Colored concrete shall be cured only by the forms-in-place."

In the Special Provisions, Section 10-1.66, "WATERPROOFING," is deleted.

In the Bid book, in the "Bid Item List," Item 136 is deleted as attached.

To Bid book holders:

Replace page 9 of the "Bid Item List" in the Bid book with the attached revised page 9 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 3  
Page 3  
November 23, 2011

07-Ven,SB-101-R39.8/R43.6,0.0/2.2  
07-260704  
Project ID 0700000490

This addendum and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/07/07-260704](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/07/07-260704)**

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



*FOR*

REBECCA D. HARNAGEL  
Chief, Office of Plans, Specifications & Estimates  
Office Engineer  
Division of Engineering Services

Attachments

# BID ITEM LIST

07-260704

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
121 (F)	510526	MINOR CONCRETE (BACKFILL)	CY	13		
122	510800	PAVING NOTCH EXTENSION	CF	189		
123 (F)	043389	ARCHITECTURAL TEXTURE (SEASIDE MOTIF)	SQFT	13,026		
124 (F)	511035	ARCHITECTURAL TREATMENT	SQFT	33,615		
125	043390	JACKING SUPERSTRUCTURE	LS	LUMP SUM	LUMP SUM	
126 (F)	518002	SOUND WALL (MASONRY BLOCK)	SQFT	14,092		
127	043391	JOINT SEAL (TYPE A) (MODIFIED)	LF	100		
128	519088	JOINT SEAL (MR 1")	LF	438		
129 (F)	043392	BAR REINFORCING STEEL (SLAB)	LB	5,630		
130 (F)	520102	BAR REINFORCING STEEL (BRIDGE)	LB	375,500		
131 (F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	340,952		
132 (F)	043393	BAR REINFORCING STEEL (EPOXY COATED) (RETAINING WALL)	LB	310,220		
133 (F)	520107	BAR REINFORCING STEEL (BOX CULVERT)	LB	9,984.6		
134 (F)	043394	BAR REINFORCING STEEL (EPOXY COATED) (BOX CULVERT)	LB	11,688		
135 (F)	520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	LB	34,819		
136	BLANK					
137 (F)	560218	FURNISH SIGN STRUCTURE (TRUSS)	LB	16,824		
138 (F)	560219	INSTALL SIGN STRUCTURE (TRUSS)	LB	16,824		
139	560245	FURNISH LAMINATED PANEL SIGN (1"-TYPE B)	SQFT	580		
140	560246	FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B)	SQFT	340		