

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

**NOTICE TO CONTRACTORS
INSTRUCTIONS TO BIDDERS
GENERAL CONDITIONS
AND
SPECIAL PROVISIONS
FOR BUILDING CONSTRUCTION ON STATE HIGHWAY
IN VENTURA COUNTY AT THE CONEJO WESTBOUND WEIGH STATION**

CONTRACT NO. 07-4H9104

07-Ven-101-14.6

Bids Open: July 10, 2003
Dated: June 9, 2003

OSD

IMPORTANT SPECIAL NOTICES

- The time allotted for the successful bidder to execute the contract and return it, together with the contract bonds, to the Department, has been revised. See Division 0.03, "Award and Execution of Contract," of these special provisions. Additional time will no longer be granted for return of the executed documents.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS	1
INSTRUCTIONS TO BIDDERS	4
GENERAL CONDITIONS	8
SPECIAL PROVISIONS	47
DIVISION 0 BIDDING AND CONTRACT REQUIREMENTS	47
0.01 INSTRUCTIONS TO BIDDERS AND GENERAL CONDITIONS	47
0.02 PROPOSAL REQUIREMENTS AND CONDITIONS	47
0.024 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)	47
0.025 DVBE GOAL FOR THIS PROJECT	48
0.026 SUBMISSION OF DVBE INFORMATION	48
0.027 SMALL BUSINESS PREFERENCE	49
0.028 CALIFORNIA COMPANY PREFERENCE	50
0.03 AWARD AND EXECUTION OF CONTRACT	50
0.04 BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	51
0.052 DIFFERING SITE CONDITIONS	51
0.053 INTEREST ON PAYMENTS	52
0.054 FINAL PAYMENT AND CLAIMS	52
0.055 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES	52
0.067 YEAR 2000 COMPLIANCE	53
0.07 SUBCONTRACTOR AND DVBE RECORDS	53
0.075 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS	53
0.077 SUBCONTRACTING	53
0.082 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	54
0.10 GUARANTEE	54
DIVISION 1. GENERAL REQUIREMENTS	56
1.01 SCOPE	56
1.02 FIRST ORDER OF WORK	56
1.03 AREAS FOR CONTRACTOR'S USE	56
1.04 COOPERATION	56
1.05 MEASUREMENT AND PAYMENT	56
1.06 SUBMITTALS	56
1.07 SCHEDULE OF VALUES	57
1.08 OBSTRUCTIONS	57
1.09 PRESERVATION OF PROPERTY	57
1.10 TEMPORARY CONTROLS	57
1.11 PUBLIC SAFETY	58
PAYMENT	59
1.12 WATER POLLUTION CONTROL	59
RETENTION OF FUNDS	60
STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS	61
COST BREAK-DOWN	62
SWPPP IMPLEMENTATION	65
MAINTENANCE	66
REPORTING REQUIREMENTS	66
PART 4.--PAYMENT	66
1.13 UTILITY CONNECTION	67
1.14 TEMPORARY UTILITIES	67
1.15 SANITARY FACILITIES	68

1.16 REFERENCES	68
1.17 PROJECT RECORD DRAWINGS	68
1.18 FIELD ENGINEERING	68
1.19 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	69
DIVISION 2. SITEWORK	81
2.01 EARTHWORK FOR BUILDING WORK	81
2.02 AGGREGATE BASE	85
2.03 GUARD POSTS	86
DIVISION 3. THRU 4. (NOT USED)	87
DIVISION 5. METALS	87
5.01 BUILDING MISCELLANEOUS METAL	87
DIVISION 13. SPECIAL CONSTRUCTION	90
13.01 MODULAR BUILDING	90
PART 1. GENERAL	90
DELIVERY, STORAGE, AND HANDLING	91
PART 2. PRODUCTS.--	92
DIVISION 14. (NOT USED)	97
DIVISION 15. MECHANICAL	97
15.01 MECHANICAL WORK	97
15.02 PIPE, FITTINGS AND VALVES	98
15.03 MECHANICAL INSULATION	104
15.04 PLUMBING FIXTURES	106
15.05 WHEELCHAIR ACCESSIBLE SHOWER UNIT	108
15.06 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS	109
DIVISION 16. ELECTRICAL	113
16.01 ELECTRICAL WORK	113
16.02 BASIC MATERIALS AND METHODS	113
16.03 SERVICE AND DISTRIBUTION	120
16.04 ELECTRICAL EQUIPMENT	121
16.05 LIGHTING	122

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 07-4H9104

07-Ven-101-14.6

Sealed proposals for the work shown on the plans entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR BUILDING
CONSTRUCTION ON STATE HIGHWAY IN VENTURA COUNTY AT THE CONEJO WESTBOUND WEIGH
STATION**

will be received at the Department of Transportation, 3347 Michelson Drive, Suite 100, Irvine, CA 92612-1692, until 2 o'clock p.m. on July 10, 2003, at which time they will be publicly opened and read in Room C - 1116 at the same address.

Proposal forms for this work are included in a separate book entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR
BUILDING CONSTRUCTION ON STATE HIGHWAY IN VENTURA COUNTY AT THE CONEJO
WESTBOUND WEIGH STATION**

General work description: EXISTING CHP OFFICE TRAILER TO BE REMOVED AND PERMANENT MODULAR OFFICE BUILDING TO BE CONSTRUCTED.

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No prebid meeting is scheduled for this project.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class B license or a combination of Class C licenses which constitutes a majority of work.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Preference will be granted to bidders properly certified as a "Small Business" as determined by the Department of General Services, Office of Small Business and Disabled Veteran Business Enterprise Certification (OSDC), at the time of bid opening in conformance with the provisions in Section 2-1.05, "Small Business Preference," of the special provisions, and Section 1896 et seq, Title 2, California Code of Regulations. A form for requesting a "Small Business" preference is included with the bid documents. Applications for status as a "Small Business" must be submitted to the Department of General Services, Office of Small Business and Disabled Veteran Business Enterprise Certification, 707 Third Street, West Sacramento, CA 95605, Telephone Nos. (800) 559-5529 or (916) 375-4940.

A reciprocal preference will be granted to "California company" bidders in conformance with Section 6107 of the Public Contract Code. (See Divisions 2 and 3 of the special provisions.) A form for indicating whether bidders are or are not a "California company" is included in the bid documents and is to be filled in and signed by all bidders.

Contract No. 07-4H9104

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated June 9, 2003

JRR

Contract No. 07-4H9104

STATE OF CALIFORNIA

DEPARTMENT OF TRANSPORTATION

**INSTRUCTIONS TO BIDDERS
AND
GENERAL CONDITIONS
FOR
BUILDING CONSTRUCTION**

JANUARY 2002

Issued by

DEPARTMENT OF TRANSPORTATION



Contract No. 07-4H9104

INSTRUCTIONS TO BIDDERS

SECTION 1

PROPOSAL REQUIREMENTS AND CONDITIONS

1-1.01 GENERAL

- The bidder shall carefully examine the instructions contained herein and shall be satisfied as to the conditions with which the bidder must comply prior to bid and to the conditions affecting the award of contract.
- These instructions form a part of the contract documents.
- Attention is directed to Section 1-1.01, "General," of the General Conditions regarding the use of masculine gender pronouns in these Instructions to Bidders.

1-1.02 CONTRACTOR'S LICENSING LAWS

- Attention is directed to the provisions of Chapter 9 of Division 3 of the Business and Professions Code concerning the licensing of contractors.
- All bidders and contractors shall be licensed in conformance with the laws of this State and any bidder or contractor not so licensed is subject to the penalties imposed by those laws.
- Attention is also directed to the requirements in Public Contract Code Section 10164. In all projects where Federal funds are involved, the Contractor shall be properly licensed at the time the contract is awarded.

1-1.03 EXAMINATION OF PLANS, SPECIAL PROVISIONS AND SITE OF THE WORK

- The bidder shall examine carefully the site of the work contemplated, the plans and special provisions and these instructions to bidders and contract forms therefor. The submission of a bid shall be conclusive evidence that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and scope of work to be performed, the quantities of materials to be furnished, and as to the requirements of these instructions to bidders, plans, special provisions, and the contract.
- Where the Department has made investigations of site conditions, including subsurface conditions in areas where work is to be performed under the contract, bidders or Contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.
- Where there has been prior construction by the Department or other public agencies within the project limits, records of the prior construction that are currently in the possession of the Department and which have been used by, or are known to, the designers and administrators of the project will be made available for inspection by bidders or Contractors, upon written request, subject to the conditions hereinafter set forth. Those records may include, but are not limited to, as-built drawings, design calculations, foundation and site studies, project reports and other data assembled in connection with the investigation, design, construction and maintenance of those prior projects.
- Inspection of those records of investigations and project records may be made at the office of the district in which the work is situated, or in the case of records of investigations related to structure work, at the Transportation Laboratory, Sacramento, California. The records of investigations and project records are not a part of the contract and are available solely for the convenience of the bidder or contractor. It is expressly understood and agreed that the Department assumes no responsibility whatsoever in respect to the sufficiency or accuracy of the investigations thus made, the records thereof, or of project records, or of the interpretations set forth therein or made by the Department in its use thereof and there is no warranty or guaranty, either express or implied, that the conditions indicated by the investigations or records are representative of those existing in or throughout those areas, or any part thereof, or that unlooked-for developments may not occur, or that materials other than, or in proportions different from those indicated, may not be encountered.
- No information derived from the inspection of investigations or compilation thereof made by the Department or from the Engineer, or his assistants, will in any way relieve the bidder or contractor from any risk or from properly fulfilling the terms of the contract.

1-1.04 PROPOSAL FORMS

- The Department will furnish to each bidder a standard proposal form, which, when filled out and executed may be submitted as that bidder's bid. Bids not presented on forms so furnished, and copies or facsimiles of the bidder's completed and executed proposal forms submitted as a bid will be rejected.
- The proposal form is bound together with the contract in a book entitled "Proposal and Contract." The proposal shall set forth the bid price, in clearly legible figures, in the space provided, and shall be signed by the bidder, who shall fill out all blanks in the proposal form as therein required.
- The proposal shall be submitted as directed in the "Notice to Contractors" under sealed cover plainly marked as a proposal, and identifying the project to which the proposal relates and the date of the bid opening therefor. Proposals which

are not properly marked may be disregarded.

- All proposal forms other than for "District Opening" projects shall be obtained from the Department of Transportation, Plans and Bid Documents, Room 0200, Transportation Building, 1120 N Street, California 95814, or as otherwise designated in the "Notice to Contractor."
- Proposals for "District Opening" projects shall be made on forms obtained from the District Director of Transportation in whose district the work is to be performed, but in all other respects the provisions in this Section 1-1.04 shall apply.

1-1.05 REQUIRED LISTING OF PROPOSED SUBCONTRACTORS

- Each proposal shall have listed therein the name and address of each subcontractor to whom the bidder proposes to subcontract portions of the work in an amount in excess of one-half of one percent of the total bid, in conformance with the Subletting and Subcontracting Fair Practices Act, commencing with Section 4100 of the Public Contract Code. The bidder's attention is invited to other provisions of the Act related to the imposition of penalties for a failure to observe its provisions by using unauthorized subcontractors or by making unauthorized substitutions.
- A sheet for listing the subcontractors, as required herein, is included in the "Proposal and Contract" book.

1-1.055 STATE EMPLOYEES AND DESIGN ENGINEERS MAY NOT BID ON CONSTRUCTION CONTRACTS

- No employee of the State shall be eligible to submit a proposal for, nor to subcontract for any portion of, nor to supply any materials for any contract administered by the Department.
- No engineering or architectural firm which has provided design services for a project shall be eligible to submit a proposal for the contract to construct the project nor to subcontract for any portion of the work. The ineligible firms include the prime contractor for design, subcontractors of portions of the design, and affiliates of either. An affiliate is a firm which is subject to the control of the same persons, through joint ownership or otherwise.

1-1.06 PREVIOUS DISQUALIFICATION, REMOVAL OR OTHER PREVENTION OF BIDDING

- Pursuant to Section 10162 of the Public Contract Code the bidder shall complete, under penalty of perjury, the questionnaire in the Proposal relating to previous disqualification, removal or other prevention of bidding of the bidder, or officers or employees of the bidder because of violation of law or a safety regulation.
- A bid may be rejected on the basis of a bidder, any officer of the bidder, or any employee of the bidder who has a proprietary interest in the bidder, having been disqualified, removed, or otherwise prevented from bidding on, or completing a Federal, State, or local project because of a violation of law or a safety regulation.

1-1.07 PROPOSAL GUARANTY

- All bids shall be presented under sealed cover and accompanied by one of the following forms of bidder's security:

Cash, a cashier's check, a certified check, or a bidder's bond executed by an admitted surety insurer, made payable to the Director of Transportation.

- The security shall be in an amount equal to at least 10 percent of the amount bid. A bid will not be considered unless one of the forms of bidder's security is enclosed with it.
- The bidder's bond shall conform to the bond form in the book entitled "Proposal and Contract" for the project and shall be properly filled out and executed. The bidder's bond form included in that book may be used. Upon request, "Bidder's Bond" forms may be obtained from the Department of Transportation.

1-1.08 COMPLIANCE WITH ORDERS OF THE NATIONAL LABOR RELATIONS BOARD

- Pursuant to Public Contract Code Section 10232, the Contractor shall swear by a statement, under penalty of perjury, that no more than one final, unappealable finding of contempt of court by a Federal court has been issued against the Contractor within the immediately preceding 2-year period because of the Contractor's failure to comply with an order of a Federal court which orders the Contractor to comply with an order of the National Labor Relations Board. For purposes of Section 10232 a finding of contempt does not include any finding which has been vacated, dismissed, or otherwise removed by the court because the Contractor has complied with the order which was the basis for the finding. The State may rescind any contract in which the Contractor falsely swears to the truth of the statement required by Section 10232.
- The statement required by Public Contract Code Section 10232 is on the page preceding the signature page of the Proposal.

1-1.09 WITHDRAWAL OF PROPOSALS

- Any bid may be withdrawn at any time prior to the date and time fixed for the opening of bids only by written request for the withdrawal of the bid filed at the location at which the bid was received by the Department. The request shall be executed by the bidder or the bidder's duly authorized representative. The withdrawal of a bid does not prejudice the right of

the bidder to file a new bid. Whether or not bids are opened exactly at the time fixed for opening bids, a bid will not be received after that time, nor may any bid be withdrawn after the time fixed for the opening of bids.

1-1.10 PUBLIC OPENING OF PROPOSALS

- Proposals will be opened and read publicly at the time and place indicated in the Notice to Contractors. Bidders or their authorized agents are invited to be present.

1-1.11 REJECTION OF PROPOSALS

- Proposals may be rejected if they have been transferred to another bidder, or if they show any alterations of form, additions not called for, conditional bids, incomplete bids, erasures, or irregularities of any kind.
- When proposals are signed by an agent, other than the officer or officers of a corporation authorized to sign contracts on its behalf or a member of a partnership, a "Power of Attorney" must be on file with the Department prior to opening bids or shall be submitted with the proposal; otherwise, the proposal may be rejected as irregular and unauthorized.

1-1.12 COMPETITIVE BIDDING

- If more than one proposal be offered by any individual, firm, copartnership, corporation, association, or any combination thereof, under the same or different names, all of those proposals may be rejected. A party who has quoted prices on materials or work to a bidder is not thereby disqualified from quoting prices to other bidders, or from submitting a bid directly for the materials or work.
- All bidders are put on notice that any collusive agreement to control or affect the awarding of this contract is in violation of the competitive bidding requirements of the State Contract Act and the Business and Professions Code and may render void any contract let under those circumstances.

1-1.13 RELIEF OF BIDDERS

- Attention is directed to the provisions of Public Contract Code Sections 5100 to 5107, inclusive, concerning relief of bidders and in particular to the requirement therein, that if the bidder claims a mistake was made in the bid presented, the bidder shall give the Department written notice within 5 days after the opening of the bids of the alleged mistake, specifying in the notice in detail how the mistake occurred.

1-1.14 INELIGIBILITY TO CONTRACT

- Public Contract Code Section 10285.1 provides as follows:

Any State agency may suspend, for a period of up to three years from the date of conviction, any person from bidding upon, or being awarded, a public works or services contract with the agency under this part or from being a subcontractor at any tier upon the contract, if that person, or any partner, member, officer, director, responsible managing officer, or responsible managing employee thereof, has been convicted by a court of competent jurisdiction of any charge of fraud, bribery, collusion, conspiracy, or any other act in violation of any State or Federal antitrust law in connection with the bidding upon, award of, or performance of, any public works contract, as defined in Section 1101, with any public entity, as defined in Section 1100, including, for the purposes of this article, the Regents of the University of California or the Trustees of the California State University. A State agency may determine the eligibility of any person to enter into a contract under this article by requiring the person to submit a statement under penalty of perjury declaring that neither the person nor any subcontractor to be engaged by the person has been convicted of any of the offenses referred to in this section within the preceding three years.

- A form for the statement required by Section 10285.1 is included in the Proposal.

SECTION 2

AWARD AND EXECUTION OF CONTRACT

2-1.01 AWARD OF CONTRACT

• The right is reserved to reject any and all proposals. The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed. The award, if made, will be made within 30 days after the opening of the proposals. This period will be subject to extension for any further period as may be agreed upon in writing between the Department and the bidder concerned.

2-1.02 RETURN OF PROPOSAL GUARANTIES

• The proposal guaranties accompanying the proposals of the first, second and third lowest responsible bidders will be retained until the contract has been finally executed, after which all those proposal guaranties, except bidders' bonds and any guaranties which have been forfeited, will be returned to the respective bidders whose proposals they accompany. The proposal guaranties, other than bidder's bonds, submitted by all other unsuccessful bidders will be returned upon determination, by the Department, of the first, second and third lowest responsible bidders.

2-1.03 CONTRACT BONDS

• The successful bidder shall furnish the 2 bonds required by the State Contract Act. One bond shall secure the payment of the claims of laborers, mechanics or materialmen employed on the work under the contract and the other bond shall guarantee the faithful performance of the contract. The bond forms will be furnished to the successful bidder by the Department.

• Except as otherwise provided in Section 3248 of the Civil Code and Section 30154 of the Streets and Highways Code, the payment bond shall be in a sum equal to the contract price and the performance bond shall be in a sum equal to at least one-half of the contract price.

• All alterations, extensions of time, extra and additional work, and other changes authorized by the General Conditions, the special provisions or any part of the contract may be made without securing the consent of the surety or sureties on the contract bonds.

2-1.04 EXECUTION OF CONTRACT

• The contract shall be signed by the successful bidder and returned, together with the contract bonds, within 8 days, not including Saturdays, Sundays and legal holidays, after the bidder has received the contract for execution.

2-1.05 FAILURE TO EXECUTE CONTRACT

• Failure of the lowest responsible bidder, the second lowest responsible bidder, or the third lowest responsible bidder to execute the contract and file acceptable bonds as provided herein within 8 days, not including Saturdays, Sundays and legal holidays, after that bidder has received the contract for execution shall be just cause for the forfeiture of the bidder's security. The successful bidder may file with the Department a written notice, signed by the bidder or the bidder's authorized representative, specifying that the bidder will refuse to execute the contract if it is presented. The filing of this notice shall have the same force and effect as the failure of the bidder to execute the contract and furnish acceptable bonds within the time hereinbefore prescribed.

GENERAL CONDITIONS
SECTION 1
DEFINITIONS AND TERMS

1-1.01 GENERAL

- Unless the context otherwise requires, wherever in the specifications and other contract documents the following abbreviations and terms, or pronouns in place of them, appear in the contract documents, the intent and meaning shall be interpreted as provided in this Section 1.
- Working titles having a masculine gender, such as "workman" and "journeyman" and pronouns, such as "he" and "himself", are utilized in these General Conditions, the Instructions to Bidders and the special provisions for the sake of brevity, and are intended to refer to persons of either gender.

1-1.02 ACCEPTANCE

- The formal written acceptance by the Director of Transportation of an entire contract which has been completed in all respects in conformance with the contract documents and any modifications thereof previously approved.

1-1.03 ADDENDUM

- A document or written communication issued by the Department during the bidding period which modifies, supersedes, or supplements the original contract documents.

1-1.04 BIDDER

- Any individual, firm, partnership, corporation, or combination thereof, submitting a proposal for the work contemplated, acting directly, or through a duly authorized representative.

1-1.05 CONTRACT

- The written agreement covering the performance of the work and the furnishing of labor, materials, tools and equipment in the construction of the work. The contract shall include the notice to contractors, Instructions to Bidders, proposal, plans, General Conditions, special provisions and contract bonds; also any and all supplemental agreements amending or extending the work contemplated and which may be required to complete the work in a substantial and acceptable manner. Supplementary agreements are written agreements covering alterations, amendments, or extensions to the contract and include contract change orders.

1-1.06 CONTRACTOR

- The person or persons, firm, partnership, corporation, or combination thereof, private or municipal, who have entered into a contract with the Department of Transportation, as party or parties of the second part or their legal representatives.

1-1.07 DAYS

- Unless otherwise designated, days as used in the contract documents will be understood to mean calendar days.

1-1.08 DEPARTMENT

- The Department of Transportation of the State of California, as created by law.

1-1.09 DIRECTOR

- The executive officer of the Department of Transportation, as created by law.

1-1.10 ENGINEER

- The Chief Engineer, Department of Transportation, acting either directly or through properly authorized agents, the agents acting within the scope of the particular duties delegated to them.

1-1.11 GENERAL NOTES

- The written instructions, provisions, conditions or other requirements appearing on the plans, and so identified thereon, which pertain to the performance of the work.

1-1.12 LABORATORY

- The Division of Engineering Services - Materials Engineering and Testing Services and the Division of Engineering Services - Geotechnical Services of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Engineering Services - Materials Engineering and Testing Services and the Division of Engineering Services - Geotechnical Services, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

1-1.13 LEGAL HOLIDAYS

- Those days designated as State holidays in the Government Code.

1-1.14 LIQUIDATED DAMAGES

- The amount prescribed in the special provisions, pursuant to the authority of Public Contract Code Section 10226, to be paid to the State or to be deducted from any payments due or to become due the Contractor for each day's delay in completing the whole or any specified portion of the work beyond the time allowed in the special provisions.

1-1.15 PLANS

- The official drawings including plans, elevations, sections, detail drawings, diagrams, plates, general notes, information and schedules thereon, or exact reproductions thereof, approved by the Engineer, which show the location, character, dimensions and details of the work to be performed. The plans include any drawings or plates bound within the special provisions.

1-1.16 PREMISES

- The area of State-owned property which surrounds the work site, limited by the property lines thereof. In some cases the premises may coincide with the work site.

1-1.17 PROPOSAL

- The offer of the bidder for the work when made out and submitted on the prescribed proposal form, properly signed and guaranteed.

1-1.18 PROPOSAL FORM

- The approved form upon which the Department of Transportation requires formal bids be prepared and submitted for the work.

1-1.19 PROPOSAL GUARANTY

- The cash, cashier's check, certified check, or bidder's bond accompanying the proposal submitted by the bidder, as a guaranty that the bidder will enter into a contract with the Department of Transportation for the performance of the work if the contract is awarded to the bidder.

1-1.20 SPECIAL PROVISIONS

- The special provisions are specific clauses setting forth conditions or requirements of the work and supplementary to these General Conditions and the Instructions to Bidders. The Department of Transportation publication entitled Labor Surcharge And Equipment Rental Rates is to be considered as a part of the special provisions.

1-1.21 STATE

- The State of California.

1-1.22 STATE CONTRACT ACT

- An act to regulate contracts for the erection, construction, alteration, repair or improvement of any state structure, building, road, or other State improvements of any kind, to be found in Chapter 1, Division 2 of the Public Contract Code.

1-1.23 WORK

- The furnishing of all labor, and the furnishing and installing of all materials, articles, supplies and equipment as specified, designated, or required by the contract.

1-1.24 WORKING DAY

- Every day except Saturdays, Sundays, legal holidays, and those days not charged as working days pursuant to Section 6-1.07, "Time of Completion," of these General Conditions.

1-1.25 WORK SITE

- The area of actual construction and the areas immediately adjacent thereto.

1-1.26 ABBREVIATIONS

AAMA	Architectural Aluminum Manufacturers' Association
AAN	American Association of Nurserymen
AASHTO	American Association of State Highway and Transportation Officials
ACI	American Concrete Institute
AGA	American Gas Association
AISC	American Institute of Steel Construction
AISI	American Iron and Steel Institute
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association
ANSI	American National Standards Institute
APA	American Plywood Association
APHA	American Public Health Association
API	American Petroleum Institute.
AREA	American Railway Engineering Association
ARI	American Refrigeration Institute
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
AWG	American Wire Gage
AWPA	American Wood Preservers' Association
AWS	American Welding Society
AWWA	American Water Works Association
CBC	California Building Code
CEC	California Electrical Code
CS	Commercial Standards (US Department of Commerce)
EIA	Electronic Industries Association
ESO	Electrical Safety Orders
FGMA	Flat Glass Marketing Association
FM	Factory Mutual
FS	Federal Specification
IEEE	Institute of Electrical and Electronics Engineers
ICBO	International Conference of Building Officials
NAAMM	National Association of Architectural Metal Manufacturers
NBFU	National Board Fire Underwriters
NEC	National Electrical Code
NEMA	National Electrical Manufacturers' Association
NFPA	National Fire Protection Association
PEI	Porcelain Enamel Institute
PS	Product Standard (US Department of Commerce)
RIS	Redwood Inspection Service
SCPI	Structural Clay Products Institute
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
TCA	Tile Council of America
TPI	Truss Plate Institute
UBC	Uniform Building Code
UL	Underwriters' Laboratory
UPC	Uniform Plumbing Code
WCLB	Grade Stamp for WCLIB
WCLIB	West Coast Lumber Inspection Bureau (Grade Stamped WCLB)
WIC	Woodwork Institute of California
WWPA	Western Wood Products' Association

Units of Measurement

- Some of the symbols for units of measurement used in the specifications are defined as follows. The symbols for other units of measurement used in the specifications are as defined in ASTM Designation: E-380, or in the various specifications and test referenced in the specifications.

Symbols as used in the Specifications	Definitions
A	amperes
g	gram
kg	kilogram
ha	hectare (10 000 m ²)
h	hour
J	joule
L	liter
m	meter
km	kilometer
mm	millimeter
μm	micrometer
nm	nanometer
m ²	square meter
m ³	cubic meter
N	newton
N·m	newton meter
Ω	ohm
Pa	pascal
kPa	kilopascal
MPa	megapascal
s	second
tonne	metric ton (1000 kg)
W	watt
V	volt

SECTION 2

CONTROL AND SCOPE OF THE WORK

2-1.01 AUTHORITY OF ENGINEER

• The Engineer shall decide all questions which may arise as to the quality or acceptability of materials furnished and work performed and as to the manner of performance and rate of progress of the work; all questions which may arise as to the interpretation of the plans and special provisions; all questions as to the acceptable fulfillment of the contract on the part of the Contractor; and all questions as to compensation. The Engineer's decision shall be final, and the Engineer shall have authority to enforce and make effective those decisions and orders which the Contractor fails to carry out promptly.

2-1.02 INTENT OF PLANS AND SPECIAL PROVISIONS

• The intent of the plans and special provisions is to prescribe the details for the construction and completion of the work which the Contractor undertakes to perform in conformance with the terms of the contract. Where the plans or special provisions describe portions of the work in general terms, but not in complete detail, it is understood that only the best general practice is to prevail and that only materials and workmanship of the first quality are to be used. Unless otherwise specified, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals, and do all the work involved in executing the contract in a satisfactory and workmanlike manner.

2-1.03 COORDINATION AND INTERPRETATION OF CONTRACT DOCUMENTS

• These General Conditions, the plans, special provisions, contract change orders, and all supplementary documents are essential parts of the contract, and a requirement occurring in one is as binding as though occurring in all. They are intended to be complementary, and to describe and provide for a complete work.

• Plans shall govern over these General Conditions; the special provisions shall govern over both these General Conditions and the plans.

• Should it appear that the work to be done or any of the matters relative thereto are not sufficiently detailed or explained in these General Conditions, the special provisions, or the plans, the Contractor shall apply to the Engineer for further explanations as may be necessary and shall conform to them as part of the contract. In the event of any doubt or question arising respecting the true meaning of these General Conditions, the special provisions or the plans, reference shall be made to the Engineer, whose decision thereon shall be final.

• In the event of any discrepancy, between any drawing and the figures written thereon, the figures shall be taken as correct. Detail drawings shall prevail over general drawings and general notes shall prevail over drawings.

2-1.04 SHOP DRAWINGS, DESCRIPTIVE DATA, SAMPLES, AND ALTERNATIVES

• It shall be the Contractor's responsibility to submit, so as to cause no delay in the work, all shop drawings, descriptive data, samples for the various trades as required by the special provisions, and offers of alternatives, if any. The submittals shall be checked and coordinated by the Contractor with the work of other trades involved before they are submitted to the Engineer for examination.

• Submittals shall be delivered to the locations indicated in the special provisions.

• Work requiring the submittal of shop drawings, descriptive data or samples shall not begin prior to approval of that submittal by the Engineer. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Approval of submittals shall not operate to waive any of the requirements of the plans and specifications or relieve the Contractor of any obligation thereunder, and defective work, materials and equipment may be rejected notwithstanding the approval of that submittal. Should the Engineer fail to complete his review within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted pursuant to the provisions in Section 6-1.08, "Liquidated Damages," of these General Conditions, and no additional compensation will be allowed for the delay.

• Submittals shall be made by a letter of transmittal which shall contain a list of all matter submitted and identification of all variations from the plans and special provisions contained in the submittal. The letter and all items accompanying the same shall be fully identified as to project name and location, Contractor's name, district, county, and contract number, with ample cross references to the contract documents, to facilitate identification of items and their location in the work. Additional specific requirements shall be as follows:

Shop Drawings

• The Contractor shall submit at least 5 copies of all shop drawings required by the special provisions. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal. Shop drawings include any drawing which requires execution by a draftsman as distinguished from printed matter. The size of shop drawings shall be

559 mm x 864 mm or 279 mm x 432 mm in size.

Descriptive Data

- The Contractor shall submit 5 copies of each set of manufacturer's brochures or other data required by the special provisions. The State will examine the submittals and return 2 copies either approved for use or returned for correction and resubmittal.

Samples

- The Contractor shall submit samples of articles, materials or equipment as required by the special provisions. The work shall be in conformance with the approved samples. Samples shall be removed from State property when directed or may be incorporated in the work if approved by the Engineer. Samples not removed by the Contractor will become the property of the State or, at the State's option, will be removed or disposed of by the State at the Contractor's expense.

Alternatives

- For convenience in designation on the plans or in the special provisions, certain materials, articles, or equipment may be designated by a brand or a trade name or the name of the manufacturer together with catalog designation or other identifying information, hereinafter referred to generically as "designated by brand name". An alternative material, article, or equipment which is of equal quality and of the required characteristics for the purpose intended may be proposed for use provided the Contractor complies with the following requirements:

- 1 The Contractor shall submit his proposal for an alternative in writing. The request shall be made in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.
- 2 No proposal will be considered unless accompanied by complete information and descriptive data, necessary to determine the equality of the offered materials, articles, or equipment. Samples shall be provided when requested by the Engineer. The Contractor shall satisfy the Engineer as to the comparative quality, suitability, or performance of the offered materials, articles, or equipment. In the event that the Engineer rejects the use of the alternative materials, articles, or equipment, then one of the particular products designated by brand name shall be furnished.

- Approval of submittals by the Engineer shall not relieve the Contractor from responsibility for the successful completion of the work, nor shall it relieve the Contractor from responsibility for errors in the submittals. A failure by the Contractor to identify in the letter of transmittal, material deviations from the plans or specifications shall void the submittal and any action taken thereon by the Engineer. When specifically requested by the Engineer, the Contractor shall resubmit the shop drawings, descriptive data and samples as may be required.

- If any mechanical, electrical, structural, or other changes are required for the proper installation and fit of alternative materials, articles, or equipment, or because of deviations from the contract plans and special provisions, the changes shall not be made without the approval of the Engineer and shall be made without additional cost to the State.

2-1.045 DIFFERING SITE CONDITIONS

- During the progress of the work, if subsurface or latent physical conditions are encountered at the site differing materially from those indicated in the contract or if unknown physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract, are encountered at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

- Upon written notification, the Engineer will investigate the conditions, and if the Engineer determines that the conditions materially differ and cause an increase or decrease in the cost or time required for the performance of any work under the contract, an adjustment, excluding loss of anticipated profits, will be made and the contract modified in writing accordingly. The Engineer will notify the Contractor of his determination whether or not an adjustment of the contract is warranted.

- No contract adjustment which results in a benefit to the Contractor will be allowed unless the Contractor has provided the required written notice.

- No contract adjustment will be allowed under the provisions specified in this section for any effects caused on unchanged work.

- Any contract adjustment warranted due to differing site conditions will be made in conformance with the provisions in Section 3-1.01, "Changes," of these General Conditions, except as otherwise provided.

2-1.05 PRESERVATION AND CLEANING

- The Contractor shall clean up the work at frequent intervals and at other times when directed by the Engineer. While finish work is being accomplished, floors shall be kept clean, free of dust, construction debris and trash. Upon completion of

the work, the Contractor shall remove from the premises the Contractor's construction equipment and any waste materials not previously disposed of, leaving the premises thoroughly clean and ready for final inspection.

2-1.06 LIMITATIONS ON WORK SITE AND PREMISES

- The Contractor shall limit the Contractor's construction operations to the work site unless otherwise shown on the plans or specified. The Contractor shall perform no operations of any nature over or on the premises except those operations as are authorized by the plans or special provisions, or as authorized by the Engineer.

2-1.07 SUPERINTENDENCE

- The Contractor shall designate in writing before starting work, an authorized representative who shall have the authority to represent and act for the Contractor.
- When the Contractor is comprised of 2 or more persons, firms, partnerships, or corporations functioning on a joint venture basis, the Contractor shall designate in writing before starting work, the name of one authorized representative who shall have the authority to represent and act for the Contractor.
- The authorized representative shall be present at the site of the work at all times while work is actually in progress on the contract. When work is not in progress and during periods when work is suspended, arrangements acceptable to the Engineer shall be made for any emergency work which may be required.
- Whenever the Contractor or the Contractor's authorized representative is not present on any particular part of the work where it may be desired to give direction, orders will be given by the Engineer, which shall be received and obeyed by the superintendent or foreman who may have charge of the particular work in reference to which the orders are given.
- Any order given by the Engineer, not otherwise required by the specifications to be in writing, will on request of the Contractor, be given or confirmed by the Engineer in writing.

2-1.08 CHARACTER OF WORKMEN

- If any subcontractor or person employed by the Contractor shall appear to the Engineer to be incompetent or to act in a disorderly or improper manner, they shall be discharged immediately on the request of the Engineer, and that person shall not again be employed on the work.

2-1.09 INSPECTION

- The Contractor shall at all times permit the Engineer and the Engineer's authorized agents to inspect the work or any part thereof. The Contractor shall maintain proper facilities and provide safe access for inspection by the Engineer to all parts of the work, and to the shops where the work is in preparation. Work shall not be covered up until authorized by the Engineer and the Contractor shall be solely responsible for notifying the Engineer where and when the work is in readiness for inspection and testing. Should any work be covered without authorization, it shall, if so ordered, be uncovered at the Contractor's expense.
- Whenever the Contractor intends to perform work on Saturday, Sunday, or a legal holiday, the Contractor shall give notice to the Engineer of the Contractor's intention 48 hours prior to performing that work, or a longer period as may be specified so that the Engineer may make necessary arrangements.

2-1.10 REMOVAL OF REJECTED AND UNAUTHORIZED WORK

- All work which has been rejected shall be remedied, or removed and replaced by the Contractor in a manner acceptable to the Engineer and no compensation will be allowed to the Contractor for the removal, replacement, or remedial work.
- Any work done beyond the lines shown on the plans or established by the Engineer, or any work done without written authority will be considered as unauthorized work and will not be paid for. Upon order of the Engineer, unauthorized work shall be remedied, removed, or replaced at the Contractor's expense.
- Upon failure of the Contractor to comply promptly with any order of the Engineer made under this Section 2-1.10, the Department may cause rejected or unauthorized work to be remedied, removed, or replaced, and the costs thereof will be deducted from any moneys due or to become due the Contractor.

2-1.11 COST REDUCTION INCENTIVE

- The Contractor may submit to the Engineer, in writing, proposals for modifying the plans, special provisions or other requirements of the contract for the sole purpose of reducing the total cost of construction. The cost reduction proposal shall not impair, in any manner, the essential functions or characteristics of the project, including but not limited to service life, economy of operation, ease of maintenance, desired appearance, or design and safety standards.
- Prior to preparing a cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept and to determine the merit of the cost reduction proposal. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, and review times required by the Department and other agencies.

- Cost reduction proposals shall contain the following information:
 1. A description of both the existing contract requirements for performing the work and the proposed changes.
 2. An itemization of the contract requirements that must be changed if the proposal is adopted.
 3. A detailed estimate of the cost of performing the work under the existing contract and under the proposed change. The estimates of cost shall be determined in the same manner as if the work were to be paid for as a change in the work as provided in Section 3, "Changes in the Work," of these General Conditions.
 4. A statement of the time within which the Engineer must make a decision thereon.
 5. The contract work affected by the proposed changes, including any quantity variation attributable thereto.
- The provisions of this Section 2-1.11 shall not be construed to require the Engineer to consider any cost reduction proposal which may be submitted hereunder; proposed changes in basic design will not be considered as an acceptable cost reduction proposal; and the Department will not be liable to the Contractor for failure to accept or act upon any cost reduction proposal submitted pursuant to this section nor for any delays to the work attributable to any cost reduction proposal. If a cost reduction proposal is similar to a change in the plans or special provisions, under consideration by the Department for the project, at the time the proposal is submitted or if the proposal is based upon or similar to standard special provisions adopted by the Department after the advertisement for the contract, the Engineer will not accept the proposal, and the Department reserves the right to make the changes without compensation to the Contractor under the provisions of this section.
- The Contractor shall continue to perform the work in conformance with the requirements of the contract until an executed change order, incorporating the cost reduction proposal has been issued. If an executed change order has not been issued by the date upon which the Contractor's cost reduction proposal specifies that a decision thereon should be made, or such other date as the Contractor may subsequently have specified in writing, the cost reduction proposal shall be deemed rejected.
- The Engineer shall be the sole judge of the acceptability of a cost reduction proposal and of the estimated net savings in construction costs from the adoption of all or any part of the proposal. In determining the estimated net savings, the right is reserved to disregard the schedules of values if, in the judgment of the Engineer, the schedule does not represent a fair measure of the value of work to be performed or to be deleted.
- The Department reserves the right where it deems action is appropriate, to require the Contractor to share in the Department's costs of investigating a cost reduction proposal submitted by the Contractor as a condition of considering the proposal. Where this condition is imposed, the Contractor shall indicate acceptance thereof in writing, and that acceptance shall constitute full authority for the Department to deduct amounts payable to the Department from any moneys due or that may become due to the Contractor under the contract.
- If the Contractor's cost reduction proposal is accepted in whole or in part the acceptance will be by a contract change order, which shall specifically state that it is executed pursuant to this Section 2-1.11. The change order shall incorporate the changes in the plans and special provisions which are necessary to permit the cost reduction proposal or that part of it as has been accepted to be put into effect, and shall include any conditions upon which the Department's approval thereof is based if the approval of the Department is conditional. The change order shall also set forth the estimated net savings in construction costs attributable to the cost reduction proposal effectuated by the change order, and shall further provide that the Contractor be paid 50 percent of that estimated net savings amount. The Contractor's cost of preparing the cost reduction incentive proposal and the Department's costs of investigating a cost reduction incentive proposal, including any portion thereof paid by the Contractor, shall be excluded from consideration in determining the estimated net savings in construction costs.
- Acceptance of the cost reduction proposal and performance of the work thereunder shall not extend the time of completion of the contract unless specifically provided for in the contract change order authorizing the use of the cost reduction proposal.
- The amount specified to be paid to the Contractor in the change order which effectuates a cost reduction proposal shall constitute full compensation to the Contractor for the cost reduction proposal and the performance of the work thereof pursuant to the change order.
- The Department expressly reserves the right to adopt a cost reduction proposal for general use on contracts administered by the Department when it determines that the proposal is suitable for application to other contracts. When an accepted cost reduction proposal is adopted for general use, only the Contractor who first submitted that proposal will be eligible for compensation pursuant to this section, and in that case, only as to those contracts awarded to that Contractor prior to submission of the accepted cost reduction proposal and as to which the cost reduction proposal is also submitted and accepted. Cost reduction proposals identical or similar to previously submitted proposals will be eligible for consideration and compensation under the provisions of this Section 2-1.11 if the identical or similar previously submitted proposals were

not adopted for general application to other contracts administered by the Department. Subject to the provisions contained herein, the State or any other public agency shall have the right to use all or any part of any submitted cost reduction proposal without obligation or compensation of any kind to the Contractor.

- This Section 2-1.11 shall apply only to contracts awarded to the lowest bidder pursuant to competitive bidding.

SECTION 3

CHANGES IN THE WORK

3-1.01 CHANGES

- The Department reserves the right to order changes in the contract at any time prior to the acceptance of the work by the Director, and the Contractor shall comply with the ordered changes. Changes or deviations from the contract shall not be made without authority in writing from the Engineer, and changes to the work without the Engineer's written approval will be considered unauthorized work and will not be paid for.
- On the basis set forth in this Section 3, the contract lump sum price will be adjusted for any ordered change which results in a change in the cost of the work.
- When ordered by the Engineer, the Contractor shall halt work in the area affected by a proposed change. Whenever it appears to the Contractor that a change is necessary, the Contractor shall immediately notify the Engineer of the reasons for that change; however, work in the area affected shall not be discontinued unless ordered by the Engineer.
- For any approved change in the work, the Contractor shall be entitled to an adjustment in time equal to the number of working days which completion of the entire work is delayed due to the changed work, and the State will be entitled to an adjustment in time equal to the number of working days which completion of the entire work is advanced due to the changed work. For ordinary changes, the Contractor's cost estimate for the changed work shall state the amount of extra time, if any, that the Contractor considers should be allowed for making the requested change. Failure to request additional time when submitting the estimate, or failure to submit the estimate, shall constitute a waiver of the right to later claim any adjustment in time based upon changed work. For ordinary changes which decrease the amount of work and for indeterminate type changes, an adjustment in time commensurate with the changed work will be determined by the Engineer. Disagreement as to time adjustments shall not affect contract price adjustments, nor shall it be cause for not proceeding with the changed work when ordered by the Engineer. The Contractor shall have the right, however, to further pursue a time adjustment in the event agreement is not reached.

3-1.01A Ordinary Changes

- The Engineer will notify the Contractor in writing of any proposed changes and describe the intended change. Within 15 days after receipt of a written request, the Contractor shall submit his proposed price to be added or deducted from the contract price due to the change. The Contractor's proposed price to be added to or deducted from the contract price shall be supported by detailed estimates of cost prepared by the Contractor. The Contractor shall also provide information to support any request for an adjustment in contract time which is directly attributable to the changed work. The Contractor shall, upon request by the Engineer, permit inspection of his original contract estimate, subcontract agreements or purchase orders relating to the change.
- If agreement is reached on the adjustment in compensation as provided in Section 3-1.01C, "Agreed Cost for Changes," of these General Conditions, the Contractor shall proceed with the work at the agreed price.
- If the Contractor and the Engineer fail to agree as to the adjustment in compensation for the performance of the changed work, the Contractor, upon written order from the Engineer, shall proceed immediately with the changed work and the contract price will be adjusted in conformance with the provisions in Section 3-1.01D, "Failure to Agree to the Cost of Changes," of these General Conditions.
- If the Contractor fails to submit his cost estimate within the specified 15 day period, the specified period may be extended in writing by the Engineer. If the Engineer does not so extend the specified period, or if the Contractor fails to submit his cost estimate within the extended time period, the Contractor shall commence the work immediately upon receipt of written order from the Engineer and the contract price will be adjusted in conformance with the provisions in Section 3-1.01D, "Failure to Agree to the Cost of Changes," of these General Conditions.

3-1.01B Indeterminate Type Changes

- Changes in the work of a kind where the cost of the work cannot be determined until completed, may be authorized by the Engineer in writing. The written order shall state that it is issued pursuant to this Section 3-1.01B. Upon receipt of a written order from the Engineer, the Contractor shall proceed with the ordered work and the contract price will be adjusted in conformance with the provisions in Section 3-1.01D, "Failure to Agree to the Cost of Changes," of these General Conditions.

3-1.01C Agreed Cost For Changes

- If the Engineer and the Contractor agree as to the adjustment in compensation for the performance of changed work on the basis of the Contractor's proposed cost estimate of the work, the contract lump sum price will be adjusted accordingly. The adjustment in compensation shall be agreed to in writing and executed by both parties.

3-1.01D Failure To Agree To The Cost Of Changes

- When a proposed change order decreases the cost of the work and the Engineer and the Contractor fail to agree upon the decreased cost thereof, the Engineer's estimated decrease in cost will be deducted from the contract price. The Contractor will be allowed 15 days after receipt of a contract change order approved by the Engineer, in which to file a written protest setting forth in what respects the Contractor differs from the Engineer's estimate of decreased cost, otherwise the decision of the Engineer to deduct the Engineer's estimate of decreased cost shall be deemed to have been accepted by the Contractor as correct.
- In the event the Engineer and the Contractor fail to agree on the cost of a change order which increases the cost of the work, the Engineer will maintain a daily job record containing a detailed summary of all labor, materials and equipment required by the ordered change. At the end of each day's work, the Contractor shall review the Engineer's daily job record comparing with the Contractor's own records, and after agreement is reached, the daily job record shall be signed by both the Engineer and the Contractor and shall become the basis for payment for the changed work. Upon completion of the work under the change order, the Contractor shall submit an invoice listing only those items of labor, materials and equipment that were agreed to by both the Engineer and the Contractor to be in addition to the requirements of the contract, together with allowable markups.
- When there is a failure to agree as to cost, no payment for the changed work will be made to the Contractor until all work called for in the change order has been completed, except that progress payments may be made on those portions of the changed work which the Contractor and the Engineer agree as to cost.

3-1.01E Allowable Costs For Changes

- The only costs which will be allowed because of changed work and the manner in which these costs shall be computed are set forth in Sections 3-1.01E(1) through 3-1.01E(5) of these General Conditions. Where the term "actual cost" is used in the aforesaid sections, it shall be deemed to mean "estimated cost" where the adjustment in compensation is of a necessity based upon estimated costs.

3-1.01E(1) Labor

- The Contractor will be paid an amount based on the actual cost for labor and supervision directly required for the performance of the changed work, including payments, assessment of benefits required by lawful labor union collective bargaining agreements; compensation insurance payments; contributions made to the State pursuant to the Unemployment Insurance Code, and for taxes paid to the Federal Government pursuant to the Social Security Act of August 14, 1935, as amended. No labor cost will be recognized at a rate in excess of the wages prevailing in the locality at the time the work is performed, nor will the use of a labor classification which would increase the cost be permitted unless the Contractor establishes to the complete satisfaction of the Engineer the necessity for payment at a higher rate.

3-1.01E(2) Materials

- The Contractor will be paid an amount based on the actual cost of the materials directly required for the performance of the changed work. The cost of materials may include the costs of procurement, transportation and delivery if necessarily incurred. If a cash or trade discount by the actual supplier is available to the Contractor, it shall be credited to the State. If the materials are obtained from a supply or source owned wholly or in part by the Contractor, payment therefor will not exceed the current wholesale price for the materials. If, in the opinion of the Engineer, the cost of materials is excessive, or if the Contractor fails to furnish satisfactory evidence of the cost to the Engineer from the actual supplier, the cost of the materials shall be deemed to be the lowest current wholesale price at which similar materials are available in the quantities required. The Department reserves the right to furnish the materials required by the change order as it deems advisable, and the Contractor shall have no claim for cost or markups on material furnished by the Department.

3-1.01E(3) Equipment

- The Contractor will be paid an amount based on the actual cost for the use of equipment directly required and approved by the Engineer in the performance of the changed work. No payment will be made for time while equipment is inoperative due to breakdowns or on days when no work is performed. In addition, the rental time shall include the time required to move the equipment to the work from the nearest available source of the required equipment, and to return it to the source. If the equipment is not moved by its own power, then loading and transportation costs will be paid. Moving time, loading and transportation costs will only be paid if the equipment is used exclusively on the changed work during the time between move in and move out. Individual pieces of equipment having a replacement value of \$500 or less shall be considered to be tools or small equipment, and no payment will be made therefor. For equipment owned, furnished, or rented by the Contractor, no cost therefor shall be recognized in excess of the rental rates established by distributors or equipment rental agencies in the locality where the work is performed.

3-1.01E(4) Markups

- When a change order increases the cost of the work, the Contractor may add the following maximum markups to the actual costs of labor, materials, or equipment rental:

33 percent for labor;
15 percent for materials; and
15 percent for equipment rental.

- The above markups include full compensation for bonds, profit and overhead.
- When a change order decreases the cost of the work, the reduction in cost shall include a 5 percent markup on the estimated cost for furnishing the labor, materials and equipment which would have been used on the work had the change order not been issued.
- When a change order involves both added work and deleted work, the markup or markups to be used shall be as follows:

The actual costs of labor, materials, and equipment rental for added and deleted work shall be calculated separately without adding markups. If the difference between the calculated costs for labor results in an increased cost, a markup of 33 percent shall be applied to the increased cost. If the difference between the calculated costs of materials or equipment rental results in an increased cost, a markup of 15 percent shall be applied to the increased costs of materials or equipment rental, as the case may be. If the difference between the calculated costs for labor, materials or equipment rental results in a decreased cost, a markup of 5 percent shall be applied to the decreased costs of labor, materials or equipment rental, as the case may be.

- When added or deleted work is performed by an authorized subcontractor, approved in conformance with the provisions in Section 1-1.05, "Required Listing of Proposed Subcontractors," of the Instructions to Bidders, an additional 5 percent will be added to the total cost of the work including all markups specified in this Section 3-1.01E(4). The additional 5 percent markup shall reimburse the Contractor for additional administrative costs, and no other additional payment will be made by reason of performance of the work by a subcontractor.

3-1.01E(5) General Limitation

- In no event shall any actual cost for added work be recognized in excess of market values prevailing at the time of the change, unless the Contractor can establish to the satisfaction of the Engineer that the Contractor investigated all possible means of obtaining the added work at prevailing market values and that the excess cost could not be avoided by the Contractor. The Engineer will determine the necessity for incurring the costs enumerated above, and as to whether they are directly required for the performance of the changed work. Lump sum quotations may be accepted at the option of the Engineer. When a change order deletes work from the contract, the computation of the cost thereof shall be the values which prevailed at the time bids for the work were opened.

- When work under this Section 3 is performed by forces other than the Contractor's organization, no additional payment will be made by the State by reason of the performance of the work by a subcontractor or other forces, except as provided elsewhere in this Section 3.

SECTION 4

CONTROL OF MATERIALS

4-1.01 MATERIALS

- The Contractor shall furnish all materials required to complete the work, except materials that are designated in the special provisions to be furnished by the State and materials furnished by the State in conformance with Section 3, "Changes in the Work," of these General Conditions.
- Unless otherwise specified in the special provisions, materials furnished by the Contractor for incorporation into the work shall be new. When the quality or kind of materials, articles, or equipment is not specifically indicated, then the quality or kind thereof shall be similar to those which are indicated.
- Articles or materials to be incorporated in the work shall be stored in such a manner as to insure the preservation of their quality and fitness for the work, and to facilitate inspection.
- All materials which do not conform to the requirements of the plans and special provisions, as determined by the Engineer, will be rejected whether in place or not. Rejected material shall be removed immediately from the site of the work, unless otherwise permitted by the Engineer. No rejected material, the defects of which have been subsequently corrected, shall be used in the work, unless approval in writing has been given by the Engineer. Upon failure of the Contractor to comply promptly with any order of the Engineer made under these provisions, the Engineer shall have authority to cause the removal and replacement of rejected material and to deduct the cost thereof from any moneys due or to become due the Contractor.
- Manufacturers' warranties, guaranties, instruction sheets and parts lists, which are furnished with certain materials incorporated in the work, shall be delivered to the Engineer before acceptance of the contract.
- Unless otherwise designated in the special provisions, materials furnished by the State will be delivered to the job site. Materials furnished by the State that are designated in the special provisions as available at locations other than the job site shall be hauled to the site of the work by the Contractor at his expense, including any necessary loading and unloading that may be involved.
- The Contractor will be held responsible for all materials furnished to him, and he shall pay all demurrage and storage charges. State-furnished materials lost or damaged from any cause whatsoever shall be replaced by the Contractor. The Contractor will be liable to the Department for the cost of replacing State-furnished material and those costs may be deducted from any moneys due or to become due the Contractor.

4-1.02 PRODUCT AND REFERENCE STANDARDS

- When descriptive catalog designations, including manufacturer's name, product brand name, or model number are referred to in the contract documents, those designations shall be considered as being those found in industry publications in effect on the day the Notice to Contractors for the work is dated.
- When standards or test designations are referred to in the contract documents by specific date of issue, they shall be considered a part of the contract. When those references do not bear a date of issue, the edition in effect on the day the Notice to Contractors for the work is dated shall be considered as part of the contract.

4-1.03 SAMPLING AND TESTING OF MATERIALS

- Unless otherwise specified, all tests shall be performed in conformance with the methods used by the Department of Transportation and shall be made by the Engineer or his designated representative.
- The Department has developed methods for testing the quality of materials and work. These methods are identified by number and are referred to as California Test. Up to five copies of individual California Tests are available at the Division of New Technology, Materials and Research, located at 5900 Folsom Boulevard, (P.O. Box 19128), Sacramento, CA 95819, and will be furnished to interested persons upon request. If a complete set of California Test Methods is desired, it can be purchased from the Department's Office of Business Management, Materiel Operations Branch, 1900 Royal Oaks Drive, Sacramento, CA 95815.
- Whenever a reference is made in the special provisions to a California Test by number, it shall mean the California Test in effect on the day the Notice to Contractors for the work is dated.
- Whenever the special provisions provide an option between 2 or more tests, the Engineer will determine the test method to be used.
- Whenever a specification, manual, or test designation provides for test reports (such as certified mill test reports) from the manufacturer, copies of those reports, identified as to the lot of material, shall be furnished to the Engineer. The manufacturer's test reports shall supplement the inspection, sampling and testing provisions of this Section 4-1.03 and shall not constitute a waiver of the State's right to inspect. When material which cannot be identified with specific test reports is proposed for use, the Engineer may, at his discretion, select random samples from the lot for testing. Testing specimens from

the random samples, including those required for retest, shall be prepared in conformance with the referenced specification and furnished by the Contractor at his expense. The number of samples and test specimens shall be entirely at the discretion of the Engineer.

- When requested by the Engineer, the Contractor shall furnish, without charge, samples of all materials entering into the work, and no material shall be used prior to approval by the Engineer, except as provided in Section 4-1.04, "Certificates of Compliance," of these General Conditions.

4-1.035 TESTING BY CONTRACTOR

- The Contractor shall be responsible for controlling the quality of the material entering the work and of the work performed, and shall perform testing as necessary to ensure quality control. The test methods used for quality control testing by the Contractor shall be as determined by the Contractor. The results of those quality control tests shall be made available to the Engineer upon request. Contractor performed quality control tests are for the Contractor's use in controlling the work and will not be accepted for use as acceptance tests.

4-1.04 CERTIFICATES OF COMPLIANCE

- A Certificate of Compliance shall be furnished prior to the use of any materials for which the special provisions require that a Certificate of Compliance be furnished. In addition, the Engineer may permit the use of certain materials or assemblies prior to sampling and testing if accompanied by a Certificate of Compliance. The certificate shall be signed by the manufacturer of the material or the manufacturer of assembled materials and shall state that the materials involved comply in all respects with the requirements of the special provisions. A Certificate of Compliance shall be furnished with each lot of such materials delivered to the work and the lot so certified shall be clearly identified in the certificate.
- Materials used on the basis of a Certificate of Compliance may be sampled and tested at any time. The fact that material is used on the basis of a Certificate of Compliance shall not relieve the Contractor of responsibility for incorporating material in the work which conforms to the requirements of the plans and special provisions and any material not conforming to those requirements will be subject to rejection whether in place or not.
- The Department reserves the right to refuse to permit the use of material on the basis of a Certificate of Compliance.
- The form of the Certificate of Compliance and its disposition shall be as directed by the Engineer.

SECTION 5

LEGAL RELATIONS AND RESPONSIBILITIES

5-1.01 LAWS TO BE OBSERVED

• The Contractor shall keep informed of and observe, and comply with and cause all of his agents and employees to observe and comply with all prevailing Federal and State laws, and rules and regulations made pursuant to the Federal and State laws, and county and municipal ordinances, and regulations, which in any way affect the conduct of the work of the contract. If any conflict arises between provisions of the contract and any laws above referred to, the Contractor shall notify the Engineer at once in writing. The Contractor shall protect and indemnify the State or any of its officers, agents, and servants against any claim or liability arising from or based on the violation of any law, rule, or regulation, whether by the Contractor or the Contractor's agents or employees.

5-1.01A Hours of Labor

• Eight hours labor constitutes a legal day's work. The Contractor or any subcontractor under the Contractor shall forfeit, as a penalty to the State of California, \$25 for each worker employed in the execution of the contract by the respective Contractor or subcontractor for each calendar day during which that worker is required or permitted to work more than 8 hours in any one calendar day and 40 hours in any one calendar week in violation of the provisions of the Labor Code, and in particular, Section 1810 to Section 1815, thereof, inclusive, except that work performed by employees of Contractors in excess of 8 hours per day, and 40 hours during any one week, shall be permitted upon compensation for all hours worked in excess of 8 hours per day at not less than one and one-half times the basic rate of pay, as provided in Section 1815 thereof.

5-1.01B Labor Nondiscrimination

• Attention is directed to Section 1735 of the Labor Code, which reads as follows:

"No discrimination shall be made in the employment of persons upon public works because of the race, religious creed, color, national origin, ancestry, physical handicap, medical condition, marital status, or sex of such persons, except as provided in Section 12940 of the Government Code and every contractor for public works violating this section is subject to all the penalties imposed for a violation of this chapter."

• Attention is directed to the following "Nondiscrimination Clause" that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations:

NONDISCRIMINATION CLAUSE

1. During the performance of this contract, contractor and its subcontractors shall not unlawfully discriminate against any employee or applicant for employment because of race, religion, color, national origin, ancestry, physical handicap, medical condition, marital status, age (over 40) or sex. Contractors and subcontractors shall ensure that the evaluation and treatment of their employees and applicants for employment are free of such discrimination. Contractors and subcontractors shall comply with the provisions of the Fair Employment and Housing Act (Gov. Code, Section 12990 et seq.) and the applicable regulations promulgated thereunder (California Code of Regulations, Title 2, Section 7285.0 et seq.). The applicable regulations of the Fair Employment and Housing Commission implementing Government Code, Section 12990, set forth in Chapter 5 of Division 4 of Title 2 of the California Code of Regulations are incorporated into this contract by reference and made a part hereof as if set forth in full. Contractor and its subcontractors shall give written notice of their obligations under this clause to labor organizations with which they have a collective bargaining or other agreement.
2. This Contractor shall include the nondiscrimination and compliance provisions of this clause in all subcontracts to perform work under the contract.

**STANDARD CALIFORNIA NONDISCRIMINATION CONSTRUCTION
CONTRACT SPECIFICATIONS (GOVERNMENT CODE, SECTION 12990)**

These specifications are applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth herein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5,000 or more.

1. As used in the specifications:
 - a. "Administrator" means Administrator, Office of Compliance Programs, California Department of Fair Employment and Housing, or any person to whom the Administrator delegates authority;
 - b. "Minority" includes:
 - (i) Black (all persons having primary origins in any of the black racial groups of Africa, but not of Hispanic origin);
 - (ii) Hispanic (all persons of primary culture or origin in Mexico, Puerto Rico, Cuba, Central or South America or other Spanish derived culture or origin regardless of race);
 - (iii) Asian/Pacific Islander (all persons having primary origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent or the Pacific Islands); and
 - (iv) American Indian/Alaskan Native (all persons having primary origins in any of the original peoples of North America and who maintain culture identification through tribal affiliation or community recognition).
2. Whenever the contractor or any subcontractor subcontracts a portion of the work, it shall physically include in each subcontract of \$5,000 or more the nondiscrimination clause in this contract directly or through incorporation by reference. Any subcontract for work involving a construction trade shall also include the Standard California Construction Contract Specifications, either directly or through incorporation by reference.
3. The contractor shall implement the specific nondiscrimination standards provided in paragraphs 6(a) through (e) of these specifications.
4. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the contractor's obligations under these specifications, Government Code, Section 12990, or the regulations promulgated pursuant thereto.
5. In order for the nonworking training hours of apprentices and trainees to be counted, such apprentices and trainees must be employed by the contractor during the training period, and the contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor or the California Department of Industrial Relations.
6. The contractor shall take specific actions to implement its nondiscrimination program. The evaluation of the contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The contractor must be able to demonstrate fully its efforts under Steps a. through e. below:
 - a. Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and at all facilities at which the contractor's employees are assigned to work. The contractor, where possible, will assign two or more women to each construction project. The contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the contractor's obligations to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.
 - b. Provide written notification within seven days to the director of DFEH when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.
 - c. Disseminate the Contractor's equal employment opportunity policy by providing notice of the policy to unions and training, recruitment and outreach programs and requesting their cooperation in assisting the Contractor to meet its obligations; and by posting the company policy on bulletin boards accessible to all employees at each location where construction work is performed.
 - d. Ensure all personnel making management and employment decisions regarding hiring, assignment, layoff, termination, conditions of work, training, rates of pay or other employment decisions, including all supervisory

personnel, superintendents, general foremen, on-site foremen, etc., are aware of the Contractor's equal employment opportunity policy and obligations, and discharge their responsibilities accordingly.

- e. Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the equal employment opportunity policy and the Contractor's obligations under these specifications are being carried out.
7. Contractors are encouraged to participate in voluntary associations which assist in fulfilling their equal employment opportunity obligations. The efforts of a contractor association, joint contractor-union, contractor-community, or other similar group of which the contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under these specifications provided that the contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female workforce participation, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's.
8. The Contractor is required to provide equal employment opportunity for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Fair Employment and Housing Act (Gov. Code, Section 12990 et seq.) if a particular group is employed in a substantially disparate manner.
9. Establishment and implementation of a bona fide affirmative action plan pursuant to Section 8104 (b) of this Chapter shall create a rebuttal presumption that a contractor is in compliance with the requirements of Section 12990 of the Government Code and its implementing regulations.
10. The Contractor shall not use the nondiscrimination standards to discriminate against any person because of race, color, religion, sex, national origin, ancestry, physical handicap, medical condition, marital status or age over 40.
11. The Contractor shall not enter into any subcontract with any person or firm decertified from state contracts pursuant to Government Code Section 12990.
12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and the nondiscrimination clause, including suspension, termination and cancellation of existing subcontracts as may be imposed or ordered pursuant to Government Code Section 12990 and its implementing regulations by the awarding agency. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Government Code Section 12990.
13. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company equal employment opportunity policy is being carried out, to submit reports relating to the provisions hereof as may be required by OCP and to keep records. Records shall at least include for each employee the name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status, (e.g., mechanic, apprentice trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in any easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, contractors shall not be required to maintain separate records.

NOTE: Authority cited: Sections 12935(a) and 12990(d), Government Code. Reference: Section 12990, Government Code.

5-1.01C Prevailing Wage

• The Contractor and any subcontractor under the Contractor shall comply with Labor Code Sections 1774 and 1775. Pursuant to Section 1775, the Contractor and any subcontractor under the Contractor shall forfeit to the State or political subdivision on whose behalf the contract is made or awarded a penalty of not more than fifty dollars (\$50) for each calendar day, or portion thereof, for each worker paid less than the prevailing rates as determined by the Director of Industrial Relations for the work or craft in which the worker is employed for any public work done under the contract by the Contractor or by any subcontractor under the Contractor in violation of the provisions of the Labor Code and in particular, Labor Code Sections 1770 to 1780, inclusive. The amount of this forfeiture shall be determined by the Labor Commissioner and shall be based on consideration of the mistake, inadvertence, or neglect of the Contractor or subcontractor in failing to pay the correct rate of prevailing wages, or the previous record of the Contractor or subcontractor in meeting their respective prevailing wage obligations, or the willful failure by the Contractor or subcontractor to pay the correct rates of prevailing wages. A mistake, inadvertence, or neglect in failing to pay the correct rate of prevailing wages is not excusable if the Contractor or subcontractor had knowledge of their obligations under the Labor Code. In addition to the penalty and pursuant to Labor Code Section 1775, the difference between the prevailing wage rates and the amount paid to each worker

for each calendar day or portion thereof for which each worker was paid less than the prevailing wage rate shall be paid to each worker by the Contractor or subcontractor. If a worker employed by a subcontractor on a public works project is not paid the general prevailing per diem wages by the subcontractor, the prime contractor of the project is not liable for the penalties described above unless the prime contractor had knowledge of that failure of the subcontractor to pay the specified prevailing rate of wages to those workers or unless the prime contractor fails to comply with all of the following requirements:

1. The contract executed between the contractor and the subcontractor for the performance of work on the public works project shall include a copy of the provisions of Sections 1771, 1775, 1776, 1777.5, 1813, and 1815 of the Labor Code.
2. The contractor shall monitor the payment of the specified general prevailing rate of per diem wages by the subcontractor to the employees, by periodic review of the certified payroll records of the subcontractor.
3. Upon becoming aware of the subcontractor's failure to pay the specified prevailing rate of wages to the subcontractor's workers, the contractor shall diligently take corrective action to halt or rectify the failure, including, but not limited to, retaining sufficient funds due the subcontractor for work performed on the public works project.
4. Prior to making final payment to the subcontractor for work performed on the public works project, the contractor shall obtain an affidavit signed under penalty of perjury from the subcontractor that the subcontractor has paid the specified general prevailing rate of per diem wages to the subcontractor's employees on the public works project and any amounts due pursuant to Section 1813 of the Labor Code.

• Pursuant to Section 1775 of the Labor Code, the Division of Labor Standards Enforcement shall notify the Contractor on a public works project within 15 days of the receipt by the Division of Labor Standards Enforcement of a complaint of the failure of a subcontractor on that public works project to pay workers the general prevailing rate of per diem wages. If the Division of Labor Standards Enforcement determines that employees of a subcontractor were not paid the general prevailing rate of per diem wages and if the Department did not retain sufficient money under the contract to pay those employees the balance of wages owed under the general prevailing rate of per diem wages, the contractor shall withhold an amount of moneys due the subcontractor sufficient to pay those employees the general prevailing rate of per diem wages if requested by the Division of Labor Standards Enforcement. The Contractor shall pay any money retained from and owed to a subcontractor upon receipt of notification by the Division of Labor Standards Enforcement that the wage complaint has been resolved. If notice of the resolution of the wage complaint has not been received by the Contractor within 180 days of the filing of a valid notice of completion or acceptance of the public works project, whichever occurs later, the Contractor shall pay all moneys retained from the subcontractor to the Department. These moneys shall be retained by the Department pending the final decision of an enforcement action.

• Pursuant to the provisions of Section 1773 of the Labor Code, the Department has obtained the general prevailing rate of wages (which rate includes employer payments for health and welfare, pension, vacation, travel time, and subsistence pay as provided for in Section 1773.8 of the Labor Code, apprenticeship or other training programs authorized by Section 3093 of the Labor Code, and similar purposes) applicable to the work to be done, for straight time, overtime, Saturday, Sunday and holiday work. The holiday wage rate listed shall be applicable to all holidays recognized in the collective bargaining agreement of the particular craft, classification or type of workmen concerned. The general prevailing wage rates and any applicable changes to these wage rates are available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated. For work situated in District 9, the wage rates are available at the Labor Compliance Office at the offices of the District Director of Transportation for District 6, located at Fresno. General prevailing wage rates are also available from the California Department of Industrial Relations' internet web site at: <http://www.dir.ca.gov>.

• The wage rates determined by the Director of Industrial Relations for the project refer to expiration dates. Prevailing wage determinations with a single asterisk after the expiration date are in effect on the date of advertisement for bids and are good for the life of the contract. Prevailing wage determinations with double asterisks after the expiration date indicate that the wage rate to be paid for work performed after this date has been determined. If work is to extend past this date, the new rate shall be paid and incorporated in the contract. The Contractor shall contact the Department of Industrial Relations as indicated in the wage rate determinations to obtain predetermined wage changes.

• Pursuant to Section 1773.2 of the Labor Code, general prevailing wage rates shall be posted by the Contractor at a prominent place at the site of the work.

• Changes in general prevailing wage determinations which conform to Labor Code Section 1773.6 and Title 8 California Code of Regulations Section 16204 shall apply to the project when issued by the Director of Industrial Relations at least 10 days prior to the date of the Notice to Contractors for the project.

- The State will not recognize any claim for additional compensation because of the payment by the Contractor of any wage rate in excess of the prevailing wage rate set forth in the contract. The possibility of wage increases is one of the elements to be considered by the Contractor in determining the bid, and will not under any circumstances be considered as the basis of a claim against the State on the contract.

5-1.01D Travel And Subsistence Payments

Attention is directed to the requirements in Section 1773.8 of the Labor Code. The Contractor shall make travel and subsistence payments to each workman, needed to execute the work, in conformance with the requirements in Labor Code Section 1773.8.

5-1.01E Payroll Records

- Attention is directed to the provisions of Labor Code Section 1776, a portion of which is quoted below. Regulations implementing Labor Code Section 1776 are located in Sections 16016 through 16019 and Sections 16207.10 through 16207.19 of Title 8, California Code of Regulations.

"1776. (a) Each contractor and subcontractor shall keep accurate payroll records, showing the name, address, social security number, work classification, straight time and overtime hours worked each day and week, and the actual per diem wages paid to each journeyman, apprentice, worker, or other employee employed by him or her in connection with the public work. Each payroll record shall contain or be verified by a written declaration that it is made under penalty of perjury, stating both of the following:

- (1) The information contained in the payroll record is true and correct.
- (2) The employer has complied with the requirements of Sections 1771, 1811, and 1815 for any work performed by his or her employees on the public works project.

"(b) The payroll records enumerated under subdivision (a) shall be certified and shall be available for inspection at all reasonable hours at the principal office of the contractor on the following basis:

- (1) A certified copy of an employee's payroll record shall be made available for inspection or furnished to the employee or his or her authorized representative on request.
- (2) A certified copy of all payroll records enumerated in subdivision (a) shall be made available for inspection or furnished upon request to a representative of the body awarding the contract, the Division of Labor Standards Enforcement, and the Division of Apprenticeship Standards of the Department of Industrial Relations.
- (3) A certified copy of all payroll records enumerated in subdivision (a) shall be made available upon request by the public for inspection or for copies thereof. However, a request by the public shall be made through either the body awarding the contract, the Division of Apprenticeship Standards, or the Division of Labor Standards Enforcement. If the requested payroll records have not been provided pursuant to paragraph (2), the requesting party shall, prior to being provided the records, reimburse the costs of preparation by the contractor, subcontractors, and the entity through which the request was made. The public shall not be given access to the records at the principal office of the contractor.

"(c) The certified payroll records shall be on forms provided by the Division of Labor Standards Enforcement or shall contain the same information as the forms provided by the division.

"(d) A contractor or subcontractor shall file a certified copy of the records enumerated in subdivision (a) with the entity that requested the records within 10 days after receipt of a written request.

"(e) Any copy of records made available for inspection as copies and furnished upon request to the public or any public agency by the awarding body, the Division of Apprenticeship Standards, or the Division of Labor Standards Enforcement shall be marked or obliterated in a manner so as to prevent disclosure of an individual's name, address, and social security number. The name and address of the contractor awarded the contract or the subcontractor performing the contract shall not be marked or obliterated.

"(f) The contractor shall inform the body awarding the contract of the location of the records enumerated under subdivision (a), including the street address, city and county, and shall, within five working days, provide a notice of a change of location and address.

"(g) The contractor or subcontractor shall have 10 days in which to comply subsequent to receipt of a written notice requesting the records enumerated in subdivision (a). In the event that the contractor or subcontractor fails to comply within the 10-day period, he or she shall, as a penalty to the state or political subdivision on whose behalf

the contract is made or awarded, forfeit twenty-five dollars (\$25) for each calendar day, or portion thereof, for each worker, until strict compliance is effectuated. Upon the request of the Division of Apprenticeship Standards or the Division of Labor Standards Enforcement, these penalties shall be withheld from progress payments then due. A contractor is not subject to a penalty assessment pursuant to this section due to the failure of a subcontractor to comply with this section."

- The penalties specified in subdivision (g) of Labor Code Section 1776 for noncompliance with the provisions of Section 1776 may be deducted from any moneys due or which may become due to the Contractor.
- A copy of all payrolls shall be submitted weekly to the Engineer. Payrolls shall contain the full name, address and social security number of each employee, the employee's correct classification, rate of pay, daily and weekly number of hours worked, itemized deductions made and actual wages paid. They shall also indicate apprentices and ratio of apprentices to journeymen. The employee's address and social security number need only appear on the first payroll on which that name appears. The payroll shall be accompanied by a "Statement of Compliance" signed by the employer or the employer's agent indicating that the payrolls are correct and complete and that the wage rates contained therein are not less than those required by the contract. The "Statement of Compliance" shall be on forms furnished by the Department or on any form with identical wording. The Contractor shall be responsible for the submission of copies of payrolls of all subcontractors.
- If by the 15th of the month, the Contractor has not submitted satisfactory payrolls for all work performed during the monthly period ending on or before the 1st of that month, the Department will retain an amount equal to 10 percent of the estimated value of the work performed during the month from the next monthly estimate, except that this retention shall not exceed \$10,000 nor be less than \$1,000. Retentions for failure to submit satisfactory payrolls shall be additional to all other retentions provided for in the contract. The retention for failure to submit payrolls for any monthly period will be released for payment on the monthly estimate for partial payments next following the date that all the satisfactory payrolls for which the retention was made are submitted.
- The Contractor and each subcontractor shall preserve their payroll records for a period of 3 years from the date of completion of the contract.

5-1.01F Trench Safety

- Attention is directed to the provisions of Section 6705 of the Labor Code concerning trench excavation safety plans.
- The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.
- Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.
- No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.
- If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.
- In addition to these provisions detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans for excavations on or affecting railroad property shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

5-1.01G Apprentices

- Attention is directed to Sections 1777.5, 1777.6 and 1777.7 of the California Labor Code and Title 8, California Code of Regulations Section 200 et seq. To ensure compliance and complete understanding of the law regarding apprentices, and specifically the required ratio thereunder, each contractor or subcontractor should, where some question exists, contact the Division of Apprenticeship Standards, 455 Golden Gate Avenue, San Francisco, CA 94102, or one of its branch offices prior to commencement of work on the public works contract. Responsibility for compliance with this section lies with the prime Contractor.

- It is State policy to encourage the employment and training of apprentices on public works contracts as may be permitted under local apprenticeship standards.

5-1.01H Fair Labor Standards Act

- The attention of bidders is invited to the fact that the State of California, Department of Transportation, has been advised by the Wage and Hour Division, U.S. Department of Labor, that contractors engaged in construction work are required to meet the provisions of the Fair Labor Standards Act of 1938 and as amended (52 Stat. 1060).

5-1.01I Workers' Compensation

- Pursuant to the requirements in Section 1860 of the Labor Code, the Contractor will be required to secure the payment of workers' compensation to the Contractor's employees in conformance with the requirements in Section 3700 of the Labor Code.
- Prior to the commencement of work, the Contractor shall sign and file with the Engineer a certification in the following form:

"I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with the provisions of Section 3700 before commencing the performance of the work of this contract."

- This certification is included in the contract, and signature and return of the contract as provided in Section 2-1.04, "Execution of Contract," of the Instructions to Bidders shall constitute signing and filing of the certificate.

5-1.01J Air Pollution Control

- The Contractor shall comply with all air pollution control rules, regulations, ordinances and statutes which apply to any work performed pursuant to the contract, including any air pollution control rules, regulations, ordinances and statutes, specified in Section 11017 of the Government Code.
- Unless otherwise provided in the special provisions, material to be disposed of shall not be burned, either inside or outside the premises.

5-1.01K Use Of Pesticides

- The Contractor shall comply with all rules and regulations of the Department of Food and Agriculture, the Department of Health, the Department of Industrial Relations and all other agencies which govern the use of pesticides required in the performance of the work on the contract.
- Pesticides shall include but shall not be limited to herbicides, insecticides, fungicides, rodenticides, germicides, nematocides, bactericides, inhibitors, fumigants, defoliant, desiccants, soil sterilants, and repellents.
- Any substance or mixture of substances intended for preventing, repelling, mitigating, or destroying weeds, insects, diseases, rodents, or nematodes and any substance or mixture of substances intended for use as a plant regulator, defoliant or desiccant shall be considered a pesticide.

5-1.01L Sound Control Requirements

- The Contractor shall comply with all local sound control and noise level rules, regulations and ordinances which apply to any work performed pursuant to the contract.
- Each internal combustion engine, used for any purpose on the job or related to the job, shall be equipped with a muffler of a type recommended by the manufacturer. No internal combustion engine shall be operated on the project without the muffler.

5-1.01M Environmental Clearances

- The Department will obtain all environmental clearances and authorizations necessary for the project as set forth in the plans and specifications. The Contractor shall comply with the provisions, including giving notices during construction when required, of these authorizations. In the event the obtaining of these authorizations delays completion of all or any portion of the work, an extension of time determined pursuant to the provisions in Section 6-1.08, "Liquidated Damages," of these General Conditions will be granted and the Contractor shall not be entitled to any additional compensation because of the delays.

5-1.01N Permits And Licenses

- The Contractor shall procure all permits and licenses, pay all charges and fees, and give all notices necessary and incident to the due and lawful prosecution of the work.
- The Environmental Quality Act (Public Resources Code, Sections 21000 to 21176, inclusive) may be applicable to permits, licenses and other authorizations which the Contractor must obtain from local agencies in connection with

performing the work of the contract. The Contractor shall comply with the provisions of those statutes in obtaining the permits, licenses and other authorizations and they shall be obtained in sufficient time to prevent delays to the work.

- In the event that the Department has obtained permits, licenses or other authorizations, applicable to the work, in conformance with the requirements in the Environmental Quality Act, the Contractor shall comply with the provisions of those permits, licenses and other authorizations.

5-1.01O Assignment Of Antitrust Actions

- The Contractor's attention is directed to the following requirements in Public Contract Code 7103.5 and Government Code Sections 4553 and 4554, which shall be applicable to the Contractor and the Contractor's subcontractors:

"In entering into a public works contract or a subcontract to supply goods, services, or materials pursuant to a public works contract, the contractor or subcontractor offers and agrees to assign to the awarding body all rights, title, and interest in and to all causes of action it may have under Section 4 of the Clayton Act (15 U.S.C. Sec. 15) or under the Cartwright Act (Chapter 2 (commencing with Section 16700) of Part 2 of Division 7 of the Business and Professions Code), arising from purchases of goods, services, or materials pursuant to the public works contract or the subcontract. This assignment shall be made and become effective at the time the awarding body tenders final payment to the contractor, without further acknowledgement by the parties."

"If an awarding body or public purchasing body receives, either through judgment or settlement, a monetary recovery for a cause of action assigned under this chapter, the assignor shall be entitled to receive reimbursement for actual legal costs incurred and may, upon demand, recover from the public body any portion of the recovery, including treble damages, attributable to overcharges that were paid by the assignor but were not paid by the public body as part of the bid price, less the expenses incurred in obtaining that portion of the recovery.

"Upon demand in writing by the assignor, the assignee shall, within one year from such demand, reassign the cause of action assigned under this part if the assignor has been or may have been injured by the violation of law for which the cause of action arose and (a) the assignee has not been injured thereby, or (b) the assignee declines to file a court action for the cause of action."

5-1.01P Safety And Health Provisions

- The Contractor shall conform to all applicable occupational safety and health standards, rules, regulations and orders established by the State of California.
- Working areas utilized by the Contractor to perform work during the hours of darkness, shall be lighted to conform to the minimum illumination intensities established by California Division of Occupational Safety and Health Construction Safety Orders.
- All lighting fixtures shall be mounted and directed in a manner precluding glare to approaching traffic.

5-1.01Q Suits To Recover Penalties And Forfeitures

- Attention is directed to Sections 1730 to 1733, inclusive, of the Labor Code concerning suits to recover amounts withheld from payment for failure to comply with requirements of the Labor Code or contract provisions based on those laws.
- Those sections provide that a suit on the contract for alleged breach thereof in not making the payment is the exclusive remedy of the Contractor or the Contractor's assignees with reference to amounts withheld for those penalties or forfeitures; and that the suit must be commenced and actual notice thereof received by the awarding authority prior to 90 days after completion of the contract and the formal acceptance of the job.
- Submission of a claim under Section 7-1.07, "Final Payment and Claims," of these General Conditions for the amounts withheld from payment for those penalties and forfeitures is not a prerequisite for those suits and these claims will not be considered.

5-1.01R Water Pollution

- The Contractor shall exercise every reasonable precaution to protect streams, lakes, reservoirs, bays, and coastal waters from pollution with fuels, oils, bitumens, calcium chloride and other harmful materials and shall conduct and schedule operations so as to avoid or minimize muddying and silting of streams, lakes, reservoirs, bays and coastal waters. Care shall be exercised to preserve roadside vegetation beyond the limits of construction.
- Water pollution control work is intended to provide prevention, control, and abatement of water pollution to streams, waterways, and other bodies of water, and shall consist of constructing those facilities which may be shown on the plans, specified herein or in the special provisions, or directed by the Engineer.
- In order to provide effective and continuous control of water pollution it may be necessary for the Contractor to perform the contract work in small or multiple units, on an out of phase schedule, and with modified construction procedures. The

Contractor shall provide temporary water pollution control measures, including but not limited to, dikes, basins, ditches, and applying straw and seed, which become necessary as a result of the Contractor's operations. The Contractor shall coordinate water pollution control work with all other work done on the contract.

- Before starting any work on the project, the Contractor shall submit, for acceptance by the Engineer, a program to control water pollution effectively during construction of the project. The program shall show the schedule for the erosion control work included in the contract and for all water pollution control measures which the Contractor proposes to take in connection with construction of the project to minimize the effects of the operations upon adjacent streams and other bodies of water. The Contractor shall not perform any clearing and grubbing or earthwork on the project, other than that specifically authorized in writing by the Engineer, until the program has been accepted.

- If the measures being taken by the Contractor are inadequate to control water pollution effectively, the Engineer may direct the Contractor to revise the operations and the water pollution control program. The directions will be in writing and will specify the items of work for which the Contractor's water pollution control measures are inadequate. No further work shall be performed on those items until the water pollution control measures are adequate and, if also required, a revised water pollution control program has been accepted.

- The Engineer will notify the Contractor of the acceptance or rejection of any submitted or revised water pollution control program in not more than 5 working days.

- The State will not be liable to the Contractor for failure to accept all or any portion of an originally submitted or revised water pollution control program, nor for any delays to the work due to the Contractor's failure to submit an acceptable water pollution control program.

- The Contractor may request the Engineer to waive the requirement for submission of a written program for control of water pollution when the nature of the Contractor's operation is such that erosion is not likely to occur. Waiver of this requirement will not relieve the Contractor from responsibility for compliance with the other provisions of this section. Waiver of the requirement for a written program for control of water pollution will not preclude requiring submittal of a written program at a later time if the Engineer deems it necessary because of the effect of the Contractor's operations.

- Unless otherwise approved by the Engineer in writing, the Contractor shall not expose a total area of erodible earth material, which may cause water pollution, exceeding 70 000 m² for each separate location, operation, or spread of equipment before either temporary or permanent erosion control measures are accomplished.

- Where erosion which will cause water pollution is probable due to the nature of the material or the season of the year, the Contractor's operations shall be so scheduled that permanent erosion control features will be installed concurrently with or immediately following grading operations.

- Nothing in the terms of the contract nor in the provisions in this Section 5-1.01R shall relieve the Contractor of the responsibility for compliance with Sections 5650 and 12015 of the Fish and Game Code, or other applicable statutes relating to prevention or abatement of water pollution.

- When borrow material is obtained from other than commercially operated sources, erosion of the borrow site during and after completion of the work shall not result in water pollution. The material source shall be finished, where practicable, so that water will not collect or stand therein.

- The requirements of this section shall apply to all work performed under the contract and to all non-commercially operated borrow or disposal sites used for the project.

- The Contractor shall also conform to the following provisions:

1. Where working areas encroach on live streams, barriers adequate to prevent the flow of muddy water into streams shall be constructed and maintained between working areas and streams, and during construction of the barriers, muddying of streams shall be held to a minimum.
2. Removal of material from beneath a flowing stream shall not be commenced until adequate means, such as a bypass channel, are provided to carry the stream free from mud or silt around the removal operations.
3. Should the Contractor's operations require transportation of materials across live streams, the operations shall be conducted without muddying the stream. Mechanized equipment shall not be operated in the stream channels of the live streams except as may be necessary to construct crossings or barriers and fills at channel changes.
4. Water containing mud or silt from aggregate washing or other operations shall be treated by filtration, or retention in a settling pond, or ponds, adequate to prevent muddy water from entering live streams.
5. Oily or greasy substances originating from the Contractor's operations shall not be allowed to enter or be placed

where they will later enter a live stream.

6. Portland cement or fresh portland cement concrete shall not be allowed to enter flowing water of streams.
7. When operations are completed, the flow of streams shall be returned as nearly as possible to a meandering thread without creating possible future bank erosion, and settling pond sites shall be graded so they will drain and will blend in with the surrounding terrain.
8. Material derived from roadway work shall not be deposited in a live stream channel where it could be washed away by high stream flows.
9. Where there is possible migration of anadromous fish in streams affected by construction on the project, the Contractor shall conduct work operations so as to allow free passage of the migratory fish.

• Compliance with the requirements of this section shall in no way relieve the Contractor from the responsibility to comply with the other provisions of the contract, in particular the responsibility for damage and for preservation of property.

5-1.02 PROTECTION AND USE OF PROPERTY

- The Contractor shall be responsible for and provide and maintain all proper temporary walks, roads, guards, railings, lights, warning signs, and take precaution at all times to avoid injury or damage to any person or any property, and upon completion of the work, or at other times as directed, restore premises and adjacent property to a proper condition.
- The Contractor shall protect adjoining property and nearby buildings, including State buildings, State roads, and public streets or roads, from dust, dirt, debris, or other nuisance arising out of the Contractor's operations or storage practices, and, if ordered by the Engineer, the Contractor shall provide and install suitable safeguards, approved by the Engineer, to protect objects from damage. If any objects are injured or damaged by reason of the Contractor's operations, they shall be replaced or restored at the Contractor's expense. The facilities shall be replaced or restored to a condition as good as when the Contractor entered upon the work, or as good as required by the specifications accompanying the contract, if any of the objects are a part of the work being performed under the contract.
- If the Contractor damages any buildings, roads or other property which belong to the State, or any department or agency thereof, then the Engineer, at his option, may retain from the money due under the contract an amount sufficient to insure repair of the damage.
- The Engineer may make or cause to be made those temporary repairs that are necessary to restore to service any damaged highway facility. The cost of the repairs shall be borne by the Contractor and may be deducted from any moneys due or to become due to the Contractor under the contract.
- The fact that any underground facility is not shown upon the plans shall not relieve the Contractor of the responsibility of protecting underground improvements or facilities. It shall be the Contractor's responsibility, pursuant thereto, to ascertain the location of those underground improvements or facilities, which may be subject to damage by reason of the Contractor's operations.

5-1.03 (BLANK)

5-1.031 INDEMNIFICATION

• With the exception that this section shall in no event be construed to require indemnification by the Contractor to a greater extent than permitted by law, the Contractor shall defend, indemnify and save harmless the State, including its officers, directors, agents (excluding agents who are design professionals), and employees, and each of them (Indemnitees), from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity, of every kind and nature whatsoever (Claims), arising out of or in connection with the Contractor's performance of this contract for:

- A. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, State, Department, or any other contractor and;
- B. Damage to property of anyone including loss of use thereof;

caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

- Except as otherwise provided by law, the indemnification provisions above shall apply regardless of the existence or degree of fault of Indemnitees. The Contractor, however, shall not be obligated to indemnify Indemnitees for Claims arising from conduct delineated in Civil Code section 2782. Further, the Contractor's indemnity obligation shall not extend to Claims to the extent they arise from any defective or substandard condition of the roadway which existed at or prior to the time the Contractor commenced work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing Roadway facilities and the claim arises from the Contractor's failure to maintain. The Contractor's indemnity obligation shall extend to Claims arising after the work is completed and accepted only if these Claims are directly related to alleged acts or omissions of the Contractor which occurred during the course of the work. No inspection by the Department, its employees or agents shall be deemed a waiver by the Department of full compliance with the requirements of this section.

- The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determines that the Contractor is not liable to the claimant. The Contractor will respond within 30 days to the tender of any claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, so much of the money due the Contractor under and by virtue of the contract as shall reasonably be considered necessary by the Department, may be retained by the State until disposition has been made of the claim or suit for damages, or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

- With respect to third party claims against the Contractor, the Contractor waives any and all rights of any type to express or implied indemnity against the State, its directors, officers, employees, or agents (excluding agents who are design professionals).

5-1.032 INSURANCE

- Insurance shall conform to the following requirements:

5-1.032A Casualty Insurance

- The Contractor shall, at the Contractor's expense, procure and maintain insurance on all of its operations with companies acceptable to the Department as follows. All insurance shall be kept in full force and effect from the beginning of the work through final acceptance by the State. In addition, the Contractor shall maintain completed operations coverage with a carrier acceptable to the Department through the expiration of the patent deficiency in construction statute of repose set forth in Section 337.1 of the Code of Civil Procedure.

5-1.032A(1) Workers' Compensation and Employer's Liability Insurance

- Workers' Compensation insurance shall be provided as specified in Section 7-1.01A(6), "Workers' Compensation." Employer's Liability Insurance shall be provided in amounts not less than:

- (a) \$1,000,000 for each accident for bodily injury by accident.
- (b) \$1,000,000 policy limit for bodily injury by disease.
- (c) \$1,000,000 for each employee for bodily injury by disease.

- If there is an exposure of injury to the Contractors' employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act or under laws, regulations or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

5-1.032A(2) Liability Insurance

- The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability, and property damage liability for the limits of liability indicated below and including coverage for:

- (a) premises, operations and mobile equipment
- (b) products and completed operations
- (c) broad form property damage (including completed operations)
- (d) explosion, collapse and underground hazards
- (e) personal injury
- (f) contractual liability

5-1.032A(3) Liability Limits/Additional Insureds

- The limits of liability shall be at least:

Contract No. 07-4H9104

- (a) \$1,000,000 for each occurrence (combined single limit for bodily injury and property damage).
- (b) \$2,000,000 aggregate for products-completed operations.
- (c) \$2,000,000 general aggregate. This general aggregate limit shall apply separately to the Contractor's work under this Agreement.
- (d) \$5,000,000 umbrella or excess liability. For projects over \$25,000,000 only, an additional \$10,000,000 umbrella or excess liability (for a total of \$15,000,000). Umbrella or excess policy shall include products liability completed operations coverage and may be subject to \$5,000,000 or \$15,000,000 aggregate limits. Further, the umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted.

• The State and the Department, including their officers, directors, agents (excluding agents who are design professionals), and State employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for those additional insureds shall not extend to liability:

- (1) arising from any defective or substandard condition of the Roadway which existed at or prior to the time the Contractor commenced work, unless that condition has been changed by the work or the scope of the work requires the Contractor to maintain existing Roadway facilities and the claim arises from the Contractor's failure to maintain; or
- (2) for claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor which occurred during the course of the work; or
- (3) to the extent prohibited by Section 11580.04 of the Insurance Code.

• The policy shall stipulate that the insurance afforded the additional insureds shall apply as primary insurance. Any other insurance or self insurance maintained by the Department or State will be excess only and shall not be called upon to contribute with this insurance. Those additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO).

5-1.032B Automobile Liability Insurance

• The Contractor shall carry automobile liability insurance, including coverage for all owned, hired and non-owned automobiles. The primary limits of liability shall be not less than \$1,000,000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Section 5-1.032A(3), "Liability Limits/Additional Insureds," shall also apply to automobile liability.

5-1.032C Policy Forms, Endorsements and Certificates

• The Contractor's General Liability Insurance shall be provided under Commercial General Liability policy form no. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form no. CG0001.

• Evidence of insurance in a form acceptable to the Department, including the required "additional insured" endorsements, shall be furnished by the Contractor to the Department at or prior to the pre-construction conference. The evidence of insurance shall provide that there will be no cancellation, lapse, or reduction of coverage without thirty (30) days' prior written notice to the Department. Certificates of Insurance, as evidence of required insurance, for the General Liability, Auto Liability and Umbrella-Excess Liability policies shall set forth deductible amounts applicable to each policy and all exclusions which are added by endorsement to each policy. The Department may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Standard ISO form CG 0001 or similar exclusions will be allowed provided they are not inconsistent with the requirements of this section. Allowance of any additional exclusions is at the discretion of the Department. Regardless of the allowance of exclusions or deductions by the Department, the Contractor shall be responsible for any deductible amount and shall warrant that the coverage provided to the Department is consistent with the requirements of this section.

5-1.032D Enforcement

• The Department may take any steps as are necessary to assure Contractor's compliance with its obligations. Should any insurance policy lapse or be canceled during the contract period the Contractor shall, within thirty (30) days prior to the effective expiration or cancellation date, furnish the Department with evidence of renewal or replacement of the policy. Failure to continuously maintain insurance coverage as herein provided is a material breach of contract. In the event the

Contractor fails to maintain any insurance coverage required, the Department may, but is not required to, maintain this coverage and charge the expense to the Contractor or terminate this Agreement. The required insurance shall be subject to the approval of Department, but any acceptance of insurance certificates by the Department shall in no way limit or relieve the Contractor of the Contractor's duties and responsibilities under the Contract to indemnify, defend and hold harmless the State, its officers, agents, and employees. Insurance coverage in the minimum amounts set forth herein shall not be construed to relieve the Contractor for liability in excess of that coverage, nor shall it preclude the State from taking other actions as is available to it under any other provision of the contract or law. Failure of the Department to enforce in a timely manner any of the provisions of this section shall not act as a waiver to enforcement of any of these provisions at a later date.

5-1.032E Self-Insurance

- Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State of evidence of the Contractor's financial capacity to respond. Additionally, self-insurance programs or retentions must provide the State with at least the same protection from liability and defense of suits as would be afforded by first-dollar insurance.

5-1.032F Miscellaneous

- Nothing contained in the Contract is intended to make the public or any member thereof a third party beneficiary of the Insurance or Indemnity provisions of these General Conditions, nor is any term, condition or other provision of the Contract intended to establish a standard of care owed to the public or any member thereof.

5-1.04 OCCUPANCY BY THE DEPARTMENT PRIOR TO ACCEPTANCE

- The Department reserves the right to occupy all or any part of the project prior to completion of the entire contract, upon written order therefor. In that event, the Contractor will be relieved of responsibility for any injury or damage to that part as results from the Department's occupancy and use by the Department. If the Contractor carries insurance against damage to the premises or against liability to third persons covering the premises so used and occupied by the Department, and if the occupancy results in increased premiums for insurance, the Department will pay to the Contractor the added cost for insurance during the period of occupancy.

- This occupancy does not constitute acceptance by the Director either of the complete work or of any portion thereof, nor will it relieve the Contractor of full responsibility for correcting defective work or materials found at any time before the formal written acceptance of the entire contract by the Director or during the full guarantee period after project acceptance, as provided in Section 7-1.09, "Guarantee," of these General Conditions.

5-1.05 CONTRACTOR'S RESPONSIBILITY FOR THE WORK

- Except as otherwise provided herein, the Contractor shall have the charge and care of the work and shall bear the risk of injury or damage to any part of the work by the action of the elements or from any other cause whether arising from the execution or from the nonexecution of the work until the acceptance of the contract by the Director. The Contractor shall rebuild, repair, restore, and make good all injuries or damages to any portion of the work occasioned by any cause before its completion and acceptance, and shall bear the expense thereof. In case of suspension of work from any cause whatever, the Contractor shall be responsible for the work and shall also be responsible for all materials, and shall properly store them if necessary, and shall provide suitable drainage and erect temporary structures where necessary.

- The Contractor will be relieved of responsibility for any injury or damage to the work caused by the following:

- (1) An earthquake in excess of a magnitude of 3.5 on the Richter Scale or a tidal wave, when the effect of that event has been proclaimed a disaster or state of emergency by the Governor of the State of California or by the President of the United States, or was of such magnitude at the site of the work as to have been sufficient to have caused a proclamation of disaster or state of emergency, had it occurred in a populated area.
- (2) Occupancy and use by the Department or the public prior to the completion of the entire project.
- (3) Acts of the Federal Government or the public enemy.

5-1.06 RESPONSIBILITY FOR UTILITIES

- The Contractor shall be responsible for the cost for any and all work, expense or special precautions caused or required by the existence or proximity of utilities encountered in performing the work, including without limitation thereon, repair of any or all damage and all hand or exploratory excavation required. The Contractor is cautioned that the utilities may include communication cables or electrical cables which may be high voltage, and when working or excavating in the vicinity of any cables, or the ducts enclosing cables, the Contractor shall observe any special precautions required and the cost of these special precautions. Suitable warning signs, barricades, and safety devices shall be erected as necessary or required.

- However, if during the course of the work the Contractor encounters utility installations which are not shown or indicated on the plans or in the special provisions, or which are found in a location substantially different from that shown, and the utilities are not reasonably apparent from visual examination, then the Contractor shall promptly notify the Engineer in writing. Where necessary for the work of the contract, the Engineer shall issue a written order to the Contractor to make adjustment, rearrangement, repair, removal, alteration, or special handling of the utility, including repair of utility if damaged. The Contractor shall perform the work described in the written order, and compensation therefor will be made in conformance with the provisions in Section 3, "Changes in the Work," of these General Conditions, relating to changes in the work. Except for the items of cost specified in Section 3, "Changes in the Work," of these General Conditions, the Contractor shall receive no compensation for any other cost, damage, delay, interference, or hindrance to him due to the presence of these utilities. If the Contractor fails to give the notice specified above and thereafter acts without instructions from the Engineer, then the Contractor shall be liable for any or all damage to these utilities or other work of the contract which arises from the Contractor's operations subsequent to discovery thereof, and the Contractor shall repair and make good any damage at the Contractor's expense.

5-1.07 PROPERTY RIGHTS IN MATERIALS

- Nothing in the contract shall be construed as vesting in the Contractor any right of property in the materials used after they have been attached or affixed to the work or soil or after partial payment has been made as provided in Section 7-1.05, "Partial Payment," of these General Conditions for material delivered on the ground or stored subject to or under the control of the State and unused. These material shall become the property of the State of California upon being so attached or affixed or upon payment for materials delivered on the ground or stored subject to or under the control of the State and unused, as provided in Section 7-1.05, "Partial Payment," of these General Conditions.

5-1.08 LEGAL ACTIONS AGAINST THE DEPARTMENT

- If, pursuant to court order, the Department temporarily suspends performance of all or any portion of the work, an extension of time determined pursuant to the provisions in Section 6-1.08, "Liquidated Damages," of these General Conditions will be granted, and the Contractor shall not be entitled to any additional compensation because of the suspension.

5-1.09 NO PERSONAL LIABILITY

- Neither the Director, the Engineer, nor any other officer or authorized employee of the Department of Transportation shall be personally responsible for any liability arising under the contract.

5-1.10 PATENTS

- The Contractor shall assume all costs arising from the use of patented materials, equipment, devices, or processes used on or incorporated in the work, and agrees to indemnify and save harmless the State of California, the Director, the Engineer, and their duly authorized representatives, from all suits at law, or actions of every nature for, or on account of the use of any patented materials, equipment, devices, or processes.

5-1.11 PAYMENT OF TAXES

- The contract price paid for the work shall include full compensation for all taxes which the Contractor is required to pay, whether imposed by Federal, State or local government, including, without being limited to, Federal excise tax. No tax exemption certificate nor any document designed to exempt the Contractor from payment of any tax will be furnished to the Contractor by the Department, as to any tax on labor, services, materials, transportation, or any other items furnished pursuant to the contract.

5-1.12 COOPERATION

- Should construction be under way by State forces or other forces or by other contractors within or adjacent to the limits of the work or should work of any other nature be under way by other forces within or adjacent to those limits, the Contractor shall cooperate with all the other contractors or other forces to the end that any delay, interference or hindrance to their work will be avoided. The right is reserved to perform other or additional work at or near the site at any time, by the use of other forces.

SECTION 6

PROSECUTION AND PROGRESS

6-1.01 SUBLETTING AND SUBCONTRACTING

- The Contractor shall be responsible for all work performed under the contract. All persons engaged in the work will be considered as employees of the Contractor. The Contractor shall give personal attention to the fulfillment of the contract and shall keep the work under the Contractor's control. When any subcontractor fails to prosecute a portion of the work in a manner satisfactory to the Engineer, the Contractor shall remove that subcontractor immediately upon written request of the Engineer, and the subcontractor shall not again be employed on the work. Although the sections of the contract may be arranged according to various trades, or general grouping of the work, the Contractor is not obligated to sublet the work in the same manner. The State will not arbitrate disputes among subcontractors or between the Contractor and one or more subcontractors concerning responsibility for performing any part of the work.
- Subcontracts shall include provisions that the contract between the State and the Contractor is part of the subcontract, and that all terms and provisions of the contract are incorporated in the subcontract. Subcontracts shall also contain certification by the subcontractor that the subcontractor is experienced in and qualified to do, and knowledgeable about, the subcontracted work. Copies of subcontracts shall be available to the Engineer upon written request, and shall be provided to the Engineer at the time any litigation against the State concerning the project is filed.
- Pursuant to the provisions of Section 6109 of the Public Contract Code, the Contractor shall not perform work on a public works project with a subcontractor who is ineligible to perform work on the public works project pursuant to Section 1777.1 or 1777.7 of the Labor Code.
- The Contractor shall not substitute any person as subcontractor in place of a subcontractor listed on the Contractor's bid proposal without the written approval of the Engineer. Substitutions must be in conformance with the provisions of the "Subletting and Subcontracting Fair Practices Act" beginning with Section 4100 of the Public Contract Code. Violations of this Act by the Contractor may subject him to penalties which may include cancellation of contract, assessment of 10 percent of the subcontractor's bid, and disciplinary action by the Contractors' State License Board.

6-1.02 ASSIGNMENT

- The performance of the contract may not be assigned, except upon the written consent of the Director. Consent will not be given to any proposed assignment which would relieve the original Contractor or the Contractor's surety of their responsibilities under the contract nor will the Director consent to any assignment of a part of the work under the contract.
- The Contractor may assign moneys due or to become due the Contractor under the contract and the assignment will be recognized by the Department, if given proper notice thereof, to the extent permitted by law, but any assignment of moneys shall be subject to all proper set-offs in favor of the Department and to all deductions provided for in the contract and particularly all money withheld, whether assigned or not, shall be subject to being used by the Department for the completion of the work in the event that the Contractor should be in default therein.

6-1.03 BEGINNING OF WORK

- The Contractor shall begin work within 15 calendar days after receiving notice that the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department, and shall diligently prosecute the same to completion within the time limit provided in the special provisions.
- The Contractor shall notify the Engineer, in writing, of the Contractor's intent to begin work at least 72 hours before work is begun. The notice shall be delivered to the Office of the District Director of Transportation in the district in which the work is situated and shall specify the date the Contractor intends to start. If the project has more than one location of work, a separate notice shall be given for each location.
- Should the Contractor begin work in advance of receiving notice that the contract has been approved as above provided, any work performed by the Contractor in advance of the date of approval shall be considered as having been done by the Contractor at the Contractor's own risk and as a volunteer unless the contract is approved.
- The delivery to the State for execution and approval of the contract properly executed on behalf of the Contractor and surety and the minimum 72 hours advance written notice as required above shall constitute the Contractor's authority to enter upon the site of the work and to begin operations, subject to the Contractor's assumption of the risk of the disapproval of the contract, as above provided, and subject also to the following:

- (1) The Contractor shall, on commencing operations, take all precautions required for public safety and shall observe all the provisions in these General Conditions and the special provisions.
- (2) In the event of disapproval, the Contractor shall at the Contractor's expense do that work that is necessary to leave the site in a neat condition to the satisfaction of the Engineer.

- (3) All work done according to the contract prior to its approval, will, when the contract is approved, be considered authorized work and will be paid for as provided in the contract.
- (4) The Contractor shall not be entitled to any additional compensation or an extension of time for any delay, hindrance or interference caused by or attributable to commencement of work prior to the date on which the contract was approved by the Attorney General or the attorney appointed and authorized to represent the Department, except to the extent the delay, hindrance or interference would have been compensable hereunder had work been commenced on the date of the approval and the progress thereof been the same as that actually made.

6-1.04 PROGRESS SCHEDULE

- The Contractor shall submit to the Engineer a practicable progress schedule within 15 days of approval of the contract, and within 7 days of the Engineer's written request at any other time.
- The Contractor may furnish the schedule on a form of the Contractor's choice or, if requested, the Engineer will furnish a form for the Contractor's use. If the Engineer furnishes a form, the Engineer will also furnish to the Contractor, on request, on or before the last day of each month a copy of the form showing the status of work actually completed during the preceding estimate period.
- The schedule shall show the order in which the Contractor proposes to carry out the work, the dates on which the Contractor will start the several salient features of the work, and the contemplated dates for completing those salient features.
- The progress schedules submitted shall be consistent in all respects with the time and order of work requirements of the contract.
- Subsequent to the time that submittal of a progress schedule is required in conformance with these General Conditions, no progress payment will be made for any work until a satisfactory schedule has been submitted to the Engineer.

6-1.05 SCHEDULE OF VALUES

- The Contractor shall submit to the Engineer a schedule of values for each lump sum item. The sum of the items listed in the schedule of values shall equal the contract lump sum prices. Overhead and profit shall not be listed as separate items. The schedule of values shall be approved by the Engineer before any partial payment estimate is prepared.

6-1.06 TEMPORARY SUSPENSION OF WORK

- The Engineer shall have the authority to suspend the work wholly or in part, for any time period as the Engineer deems necessary, due to unsuitable weather, or to such other conditions as are considered unfavorable for the suitable prosecution of the work, or for any time period as the Engineer deems necessary due to the failure on the part of the Contractor to carry out orders given, or to perform any provision of the contract.
- The Contractor shall immediately comply with the written order of the Engineer to suspend the work wholly or in part. The suspended work shall be resumed when conditions are favorable and methods are corrected, as ordered or approved in writing by the Engineer.
- If the Engineer orders a suspension of all of the work or a portion of the work which is the current controlling operation or operations, due to unsuitable weather or to such other conditions as are considered unfavorable to the suitable prosecution of the work, the days on which the suspension is in effect shall not be considered working days as defined in Section 6-1.07, "Time of Completion," of these General Conditions. If a portion of work at the time of the suspension is not a current controlling operation or operations, but subsequently does become the current controlling operation or operations, the determination of working days will be made on the basis of the then current controlling operation or operations.
- If a suspension of work is ordered by the Engineer, due to the failure on the part of the Contractor to carry out orders given or to perform any provision of the contract, the days on which the suspension order is in effect shall be considered working days if those days are working days within the meaning of the definition set forth in Section 6-1.07, "Time of Completion," of these General Conditions.
- In the event of a suspension of work under any of the conditions set forth in this Section 6-1.06, the suspension of work shall not relieve the Contractor of the Contractor's legal responsibilities as set forth in these General Conditions.
- The Contractor shall have no claim for damage or compensation for any delay, interference or hindrance resulting from an ordered temporary suspension of the work.
- In addition to the requirements specified above, the following shall apply:

If the performance of all or any portion of the work is suspended or delayed by the Engineer in writing for an unreasonable period of time (not originally anticipated, customary, or inherent to the construction industry) and the Contractor believes that additional compensation or contract time or additional compensation and contract time is due as a result of the suspension or delay, the Contractor shall submit to the Engineer in writing a request for adjustment within 7 calendar days of receipt of the notice to resume work. The request shall set forth the reasons and support for the adjustment.

Upon receipt, the Engineer will evaluate the Contractor's request. If the Engineer agrees that the cost or time or cost and time required for the performance of the contract has increased as a result of the suspension and the suspension was caused by conditions beyond the control of and not the fault of the Contractor, the Contractor's suppliers, or subcontractors at any approved tier, and not caused by weather, the Engineer will make an adjustment (excluding profit) and modify the contract in writing accordingly. The Engineer will notify the Contractor of the Engineer's determination whether or not an adjustment of the contract is warranted.

No contract adjustment will be allowed unless the Contractor has submitted the request for adjustment within the time prescribed.

No contract adjustment will be allowed under the provisions specified in this section to the extent that performance would have been suspended or delayed by any other cause, or for which an adjustment is provided for or excluded under any term or condition of this contract.

6-1.07 TIME OF COMPLETION

- The Contractor shall complete all or any designated portion of the work called for under the contract in all parts and requirements within the time set forth in the special provisions.
- A working day is defined as any day, except Saturdays, Sundays and legal holidays and days on which the Contractor is specifically required by the special provisions to suspend construction operations, and except days on which the Contractor is prevented by inclement weather or conditions resulting immediately therefrom adverse to the current controlling operation or operations, as determined by the Engineer, from proceeding with at least 75 percent of the normal labor and equipment force engaged on the controlling operation or operations for at least 60 percent of the total daily time being currently spent on the controlling operation or operations.
- Should the Contractor prepare to begin work at the regular starting time in the morning of any day on which inclement weather, or the conditions resulting from the weather, or the condition of the work, prevents the work from beginning at the usual starting time and the crew is dismissed as a result thereof and the Contractor does not proceed with at least 75 percent of the normal labor and equipment force engaged in the current controlling operation or operations for at least 60 percent of the total daily time being currently spent on the controlling operation or operations, the Contractor will not be charged for a working day whether or not conditions should change thereafter during that day and the major portion of the day could be considered to be suitable for those construction operations.
- The current controlling operation or operations is to be construed to include any feature of the work which, if delayed, will delay the time of completion of the contract.
- Determination that a day is a nonworking day by reason of inclement weather or conditions resulting immediately therefrom shall be made and agreed upon during that day by conference between the Engineer and the Contractor. In the event of failure to agree, the Contractor will be allowed 15 days from the issuance of the weekly statement of working days in which to file a written protest setting forth in what respects the Contractor differs from the Engineer, otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The Engineer will furnish the Contractor a weekly statement showing the number of working days charged to the contract for the preceding week, the number of working days of time extensions being considered or approved, the number of working days originally specified for the completion of the contract and the number of working days remaining to complete the contract and the extended date for completion thereof, except when working days are not being charged in conformance with the provisions in Section 6-1.06, "Temporary Suspension of Work," of these General Conditions.

6-1.08 LIQUIDATED DAMAGES

- It is agreed by the parties to the contract that in case all the work called for under the contract in all parts and requirements is not finished or completed within the number of working days as set forth in the special provisions, damage will be sustained by the State of California, and that it is and will be impracticable and extremely difficult to ascertain and determine the actual damage which the State will sustain in the event of and by reason of the delay; and it is therefore agreed that the Contractor will pay to the State of California, the sum set forth in the special provisions per day for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed; and the Contractor agrees to pay the liquidated damages herein provided for, and further agrees that the Department may deduct the amount thereof from any moneys due or that may become due the Contractor under the contract.
- It is further agreed that in case the work called for under the contract is not finished and completed in all parts and requirements within the number of working days specified, the Director shall have the right to increase the number of working days or not, as the Director may deem best to serve the interest of the State, and if the Director decides to increase the number of working days, the Director shall further have the right to charge to the Contractor, the Contractor's heirs, assigns or sureties and to deduct from the final payment for the work all or any part, as the Director may deem proper, of the actual cost of engineering, inspection, superintendence, and other overhead expenses which are directly chargeable to the

contract, and which accrue during the period of the extension, except that cost of final surveys and preparation of final statement shall not be included in the charges.

- The Contractor will be granted an extension of time and will not be assessed with liquidated damages or the cost of engineering and inspection for any portion of the delay in completion of the work beyond the time named in the special provisions for the completion of the work caused by acts of God or of the public enemy, fire, floods, tsunamis, earthquakes, epidemics, quarantine restrictions, strikes, labor disputes, shortage of materials and freight embargoes, provided, that the Contractor shall notify the Engineer in writing of the causes of delay within 15 days from the beginning of that delay. The Engineer shall ascertain the facts and the extent of the delay, and the Engineer's findings thereon shall be final and conclusive.

- No extension of time will be granted for a delay caused by a shortage of materials unless the Contractor furnishes to the Engineer documentary proof that the Contractor has made every effort to obtain the materials from all known sources within reasonable reach of the work in a diligent and timely manner, and further proof in the form of supplementary progress schedules, as required in Section 6-1.04, "Progress Schedule," of these General Conditions that the inability to obtain the materials when originally planned, did in fact cause a delay in final completion of the entire work which could not be compensated for by revising the sequence of the Contractor's operations. The term "shortage of materials," as used in this section, shall apply only to materials, articles, parts or equipment which are standard items and are to be incorporated in the work. The term "shortage of materials," shall not apply to materials, parts, articles, or equipment which are processed, made, constructed, fabricated or manufactured to meet the specific requirements of the contract. Only the physical shortage of material will be considered under these provisions as a cause for extension of time. Delays in obtaining materials due to priority in filling orders will not constitute a shortage of materials.

- If the Contractor is delayed in completion of the work by reason of changes made under Section 3, "Changes in the Work," of these General Conditions or by any act of the Engineer or of the Department, not contemplated by the contract, an extension of time commensurate with the delay in completion of the work thus caused will be granted and the Contractor shall be relieved from any claim for liquidated damages, or engineering and inspection charges or other penalties for the period covered by that extension of time; provided that the Contractor shall notify the Engineer in writing of the causes of delay within 15 days from the beginning of the delay. The Engineer shall ascertain the facts and the extent of the delay, and the Engineer's findings thereon shall be final and conclusive.

- Except as provided in Public Contract Code Section 7102, the Contractor shall have no claim for damage or compensation for any delay or hindrance whether or not contemplated by the contract.

- It is the intention of the above provisions that the Contractor shall not be relieved of liability for liquidated damages or engineering and inspection charges for any period of delay in completion of the work in excess of that expressly provided for in this Section 6-1.08.

6-1.09 TERMINATION

6-1.09A Termination Of Contract - "Convenience Of State"

- The Department reserves the right to terminate the contract at any time if the Director determines that to do so would be in the best interest of the State.

- Termination of the contract and the total compensation payable to the Contractor in the event of termination shall be governed by the following:

- (1) The Engineer will issue the Contractor a written notice signed by the Director, specifying that the contract is to be terminated. Upon receipt of that written notice and, except as otherwise directed in writing by the Engineer, the Contractor shall:
 - (a) Stop all work under the contract except that specifically directed to be completed prior to acceptance.
 - (b) Perform work the Engineer deems necessary to secure the project for termination.
 - (c) Remove equipment from the site of the work.
 - (d) Take the required action as is necessary to protect materials from damage.
 - (e) Notify all subcontractors and suppliers that the contract is being terminated and that their contracts or orders are not to be further performed unless otherwise authorized in writing by the Engineer.
 - (f) Provide the Engineer with an inventory list of all materials previously produced, purchased or ordered from suppliers for use in the work and not yet used in the work, including its storage location, and any other information as the Engineer may request.
 - (g) Dispose of materials not yet used in the work as directed by the Engineer. It shall be the Contractor's responsibility to provide the State with good title to all materials purchased by the State hereunder, including

materials for which partial payment has been made as provided in Section 7-1.05, "Partial Payments," of these General Conditions and with bills of sale or other documents of title for the materials.

- (h) Subject to the prior written approval of the Engineer, settle all outstanding liabilities and all claims arising out of subcontracts or orders for materials terminated hereunder. To the extent directed by the Engineer, the Contractor shall assign to the Department all the right, title and interest of the Contractor under subcontracts or orders for materials terminated hereunder.
 - (i) Furnish the Engineer with the documentation required to be furnished by the Contractor under the provisions of the contract including, on projects as to which Federal funds are involved, all documentation required under the Federal requirements included in the contract.
 - (j) Take other actions as the Engineer may direct.
- (2) Acceptance of the contract as hereinafter specified shall not relieve the Contractor of responsibility for damage to materials except as follows:

The Contractor's responsibility for damage to materials for which partial payment has been made as provided in Section 7-1.05, "Partial Payments," of these General Conditions and for materials furnished by the State for use in the work and unused shall terminate when the Engineer certifies that the materials have been stored in the manner and at the locations the Engineer has directed.

The Contractor's responsibility for damage to materials purchased by the State subsequent to the issuance of the notice that the contract is to be terminated shall terminate when title and delivery of those materials has been taken by the State.

When the Engineer determines that the Contractor has completed the work under the contract directed to be completed prior to termination and all other work as may have been ordered to secure the project for termination, the Engineer will recommend that the Director formally accept the contract, and immediately upon and after the acceptance by the Director, the Contractor will not be required to perform any further work thereon and shall be relieved of contractual responsibilities for injury to persons or damage to property which occurs after the formal acceptance of the project by the Director.

- (3) The total compensation to be paid to the Contractor shall be determined by the Engineer on the basis of the following:
- (a) The reasonable cost to the Contractor, without profit, for all work performed under the contract, including mobilization, demobilization and work done to secure the project for termination.
When in the opinion of the Engineer the cost of the work is excessively high due to costs incurred to remedy or replace defective or rejected work, the reasonable cost to be allowed will be the estimated reasonable cost of performing that work in compliance with the requirements of the plans and special provisions and the excessive actual cost shall be disallowed.
 - (b) A reasonable allowance for profit on the cost of work performed as determined under Subsection (a), provided the Contractor establishes to the satisfaction of the Engineer that it is reasonably probable that the Contractor would have made a profit had the contract been completed and provided further, that the profit allowed shall in no event exceed 4 percent of the cost.
 - (c) The reasonable cost to the Contractor of handling material returned to the vendor, delivered to the Department or otherwise disposed of as directed by the Engineer.
 - (d) A reasonable allowance for the Contractor's administrative costs in determining the amount payable due to termination of the contract.

All records of the Contractor and subcontractors, necessary to determine compensation in conformance with the provisions of this Section shall be open to inspection or audit by representatives of the Department at all times after issuance of the notice that the contract is to be terminated and for a period of 3 years, and these records shall be retained for that period.

After acceptance of the work by the Director, the Engineer may make payments on the basis of interim estimates pending issuance of the Final Statement, when in the Engineer's opinion the amount thus paid, together with all amounts previously paid or allowed, will not result in total compensation in excess of that to which the Contractor will be entitled. All payments, including payment upon the Final Statement, shall be subject to deduction for prior payments and amounts, if any, to be kept or retained under the provisions of the contract.

- The provisions of this Section shall be included in all subcontracts.

6-1.09B Termination Of Control - "Default Of Contractor"

- Failure to supply an adequate working force, or material of proper quality, or failure to comply with Section 10262 of the State Contract Act, or in any other respect to prosecute the work with the diligence and force specified by the contract, is grounds for termination of the Contractor's control over the work and for taking over the work by the State. The procedures for termination, completion of the work, and the rights and obligations of the parties are provided for in the State Contract Act (Public Contract Code Sections 10253-10260).
- If the Contractor's control of the work is terminated or the Contractor abandons the work and the contract work is completed in conformance with the provisions in Section 10255 of the State Contract Act, any dispute concerning the amount to be paid by the State to the Contractor or the Contractor's surety or to be paid to the State by the Contractor or the Contractor's surety, under the provisions in Section 10258 of the State Contract Act, shall be subject to arbitration in conformance with the provisions in Section 7-1.10, "Arbitration," of these General Conditions. The surety shall be bound by the arbitration award and is entitled to participate in the arbitration proceedings.

SECTION 7

ACCEPTANCE AND PAYMENT

7-1.01 ACCEPTANCE

- The contract will be accepted in writing by the Director when the whole shall have been completed in all respects in conformance with the provisions of the contract to the full satisfaction of the Department.

7-1.02 SCOPE OF PAYMENT

- The Contractor shall accept the compensation provided in the contract as full payment for furnishing all labor, materials, tools, equipment, and incidentals necessary to the completed work and for performing all work contemplated and embraced under the contract; also for loss or damage arising from the nature of the work, or from the action of the elements, or from any unforeseen difficulties which may be encountered during the prosecution of the work until the acceptance by the Director and for all risks of every description connected with the prosecution of the work, also for all expenses incurred in consequence of the suspension or discontinuance of the work as provided in the contract; and for completing the work according to the contract. Neither the payment of any estimate nor of any retained percentage shall relieve the Contractor of any obligation to make good any defective work or material.
- No compensation will be made in any case for loss of anticipated profits.

7-1.03 NOTICE OF POTENTIAL CLAIM

- The Contractor shall not be entitled to the payment of any additional compensation for any act, or failure to act, by the Engineer, including failure or refusal to issue a change order, or for the happening of any event, thing, occurrence, or other cause, unless the Contractor shall have given the Engineer due written notice of potential claim as hereinafter specified. Compliance with this Section 7-1.03 shall not be a prerequisite as to matters within the scope of the protest provisions in Section 3, "Changes in the Work," or Section 6-1.07, "Time of Completion," or the notice provisions in Section 2-1.045, "Differing Site Conditions," or Section 6-1.08, "Liquidated Damages," or Section 5-1.06, "Responsibility for Utilities," of these General Conditions.
- The written notice of potential claim shall be submitted to the Engineer prior to the time that the Contractor performs the work giving rise to the potential claim for additional compensation, if based on an act or failure to act by the Engineer, or in all other cases within 15 days after the happening of the event, thing, occurrence, or other cause, giving rise to the potential claim.
- The written notice of potential claim shall be submitted on Form CEM-6201 furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650 - 12655. The notice shall set forth the reasons for which the Contractor believes additional compensation will or may be due and the nature of the costs involved. Unless the amount of the potential claim has been stated in the written notice, the Contractor shall, within 15 days of submitting the notice, furnish an estimate of the cost of the affected work and impacts, if any, on project completion. The estimate of costs may be changed or updated by the Contractor when conditions have changed. When the affected work is completed, the Contractor shall submit substantiation of the Contractor's actual costs. Failure to do so shall be sufficient cause for denial of any claim subsequently filed on the basis of that notice of potential claim.
- It is the intention of this Section 7-1.03 that differences between the parties arising under and by virtue of the contract be brought to the attention of the Engineer at the earliest possible time in order that those matters may be settled, if possible, or other appropriate action promptly taken. The Contractor hereby agrees that the Contractor shall have no right to additional compensation for any claim that may be based on any act, failure to act, event, thing or occurrence for which no written notice of potential claim as herein required was filed.
- Should the Contractor, in connection with or subsequent to the assertion of a potential claim, request inspection and copying of documents or records in the possession of the Department that pertain to the potential claim, the Contractor's records of the project, as deemed by the Department to be pertinent to the potential claim, shall be made available to the Department for inspection and copying.

7-1.04 STOP NOTICES

- The State of California, by and through the Department or other appropriate State office or officers, may at its option and at any time retain out of any amounts due the Contractor, sums sufficient to cover claims, filed pursuant to Section 3179 et seq of the Civil Code.
- Stop notice information may be obtained from the Departmental Disbursing Office at 1801 30th Street, East Building, Sacramento, California.

7-1.05 PARTIAL PAYMENTS

- The Department, once in each month upon request of the Contractor for partial payments, shall cause an estimate in

writing to be made by the Engineer. The estimate shall include the total amount of work done and acceptable materials furnished to the time of the estimate, and the value thereof. The acceptable materials shall include materials that are furnished and delivered to the work site and are not incorporated in the work.

- The Department shall retain 10 percent of the estimated value of the work done and 10 percent of the value of materials so estimated to have been furnished and delivered and not incorporated in the work as aforesaid as part security for the fulfillment of the contract by the Contractor, except that at any time after 20 percent of the work has been completed, if the Engineer finds that satisfactory progress is being made, the Department may reduce the total amount being retained from payment pursuant to the above requirements to 5 percent of the total estimated value of the work and materials and may also reduce the amount retained from any of the remaining partial payments to 5 percent of the estimated value of the work and materials. In addition, on any partial payment made after 95 percent of the work has been completed, the Department may reduce the amount withheld from payment pursuant to the requirements of this Section 7-1.05, to such lesser amount as the Department determines is adequate security for the fulfillment of the balance of the work and other requirements of the contract, but in no event will that amount be reduced to less than 125 percent of the estimated value of the work yet to be completed as determined by the Engineer. The reduction will only be made upon the written request of the Contractor and shall be approved in writing by the surety on the Performance Bond and by the surety on the Payment Bond. The approval of the surety shall be submitted to the Disbursing Officer of the Department; the signature of the person executing the approval for the surety shall be properly acknowledged and the power of attorney authorizing the person to give that consent must either accompany the document or be on file with the Department.

- The Department shall pay monthly to the Contractor, while carrying on the work, the balance not retained, as aforesaid, after deducting therefrom all previous payments and all sums to be kept or retained under the provisions of the contract. No monthly estimate or payment shall be required to be made when, in the judgment of the Engineer, the work is not proceeding in conformance with the provisions of the contract.

- No monthly estimate or payment shall be construed to be an acceptance of any defective work or improper materials.

- Attention is directed to the prohibitions and penalties pertaining to unlicensed contractors as provided in Business and Professions Code Sections 7028.15(a) and 7031.

7-1.06 PAYMENT OF WITHHELD FUNDS

- Attention is directed to Section 7-1.05, "Partial Payments," of these General Conditions and in particular to the retention provisions of Section 7-1.05, of these General Conditions.

- Upon the Contractor's request, pursuant to Public Contract Code Section 10263, the Department will make payment of funds withheld from progress payments to ensure performance of the contract if the Contractor deposits in escrow with the State Treasurer, or with a bank acceptable to the Department, securities equivalent to the amount withheld. The Contractor shall be beneficial owner of any securities substituted for moneys withheld and shall receive any interest thereon. Upon satisfactory completion of the contract, the securities shall be returned to the Contractor.

- Alternatively, upon the Contractor's request, the Department will make payment of retentions earned directly to the escrow agent. The Contractor may direct the investment of the payments into securities and the Contractor shall receive the interest earned on the investments upon the same terms provided for securities deposited by the Contractor. Upon satisfactory completion of the contract, the Contractor shall receive from the escrow agent all securities, interest, and payments received by the escrow agent from the Department, pursuant to the terms in Section 10263 of the Public Contract Code.

- Alternatively, and subject to the approval of the Department, the payment of retentions earned may be deposited directly with a person licensed under Division 6 (commencing with Section 17000) of the Financial Code as the escrow agent. Upon written request of an escrow agent that has not been approved by the Department under subdivision (c) of Section 10263 of the Public Contract Code, the Department will provide written notice to that escrow agent within 10 business days of receipt of the request indicating the reason or reasons for not approving that escrow agent. The payments will be deposited in a trust account with a Federally chartered bank or savings association within 24 hours of receipt by the escrow agent. The Contractor shall not place any retentions with the escrow agent in excess of the coverage provided to that escrow agent pursuant to subdivision (b) of Section 17314 of the Financial Code. In all respects not inconsistent with subdivision (c) of Section 10263 of the Public Contract Code, the remaining provisions of Section 10263 of the Public Contract Code shall apply to escrow agents acting pursuant to subdivision (c) of Section 10263 of the Public Contract Code.

- Securities eligible for investment shall include those listed in Section 16430 of the Government Code, bank or savings and loan certificates of deposit, interest-bearing demand deposit accounts, standby letters of credit, or any other security mutually agreed to by the Contractor and the Department.

- The escrow agreement used pursuant to this Section 7-1.06 shall be substantially similar to the "Escrow Agreement for Security Deposits In Lieu of Retention" in Section 10263 of the Public Contract Code, deemed as incorporated herein by reference.

- The Contractor shall obtain the written consent of the surety to the agreement.

7-1.07 FINAL PAYMENT AND CLAIMS

- After acceptance of the work by the Director, the Department will make a final monthly payment pending approval of the final statement. The final monthly payment will be the balance found to be due after deduction of all previous payments, all amounts to be kept or retained under the provisions of the contract, and such further amounts as the Engineer determined to be necessary pending approval of the final statement. The Engineer will promptly submit to the Contractor a final statement of the sum due the Contractor under the contract. The statement shall take into account the contract price, as adjusted by any change order; amounts already paid; and sums to be withheld for incomplete work, liquidated damages, and for any other cause under the contract. The Contractor shall submit written approval of the final statement or submit a written statement of all claims arising under or by virtue of the contract so that the Engineer receives the written approval or statement of claims no later than close of business of the thirtieth day after receiving the final statement of the sum due the Contractor. If the thirtieth day falls on a Saturday, Sunday or legal holiday, then receipt of the written approval or statement of claims by the Engineer shall not be later than the close of business of the next business day. The approval of that statement or the failure to file a claim within the specified 30 day period shall constitute a waiver by the Contractor of any additional right to compensation under or by reason of the contract and the payment so made by the State shall thereupon become a complete statement between the State and the Contractor.
- To constitute the filing of a claim, the Contractor shall set forth in writing the basis for the claim and the amount of money for which demand is made and shall submit the same to the Engineer. No demand by the Contractor shall be recognized as a claim by the State unless it is filed in conformance with this paragraph.
- Claims filed by the Contractor shall be in sufficient detail to enable the Engineer to ascertain the basis and amount of those claims. If additional information or details are required by the Engineer to determine the basis and amount of the claims, the Contractor shall furnish additional information or details so that the information or details are received by the Engineer no later than the fifteenth day after receipt of the written request from the Engineer. If the fifteenth day falls on a Saturday, Sunday or legal holiday, then receipt of the information or details by the Engineer shall not be later than close of business of the next business day. Failure to submit the information and details to the Engineer within the time specified will be sufficient cause for denying the claim.
- The Contractor shall keep full and complete records of the costs and additional time incurred for any work for which a claim for additional compensation is made. The Engineer or any designated claim investigator or auditor shall have access to those records and any other records as may be required by the Engineer to determine the facts or contentions involved in the claims. Failure to permit access to those records shall be sufficient cause for denying the claims.
- Claims submitted by the Contractor shall be accompanied by a notarized certificate containing the following language:

Under the penalty of law for perjury or falsification and with specific reference to the California False Claims Act, Government Code Section 12650 et. seq., the undersigned,

_____,
 (name)
 _____ of
 (title)
 _____,
 (company)

hereby certifies that the claim for the additional compensation and time, if any, made herein for the work on this contract is a true statement of the actual costs incurred and time sought, and is fully documented and supported under the contract between parties.

Dated _____

/s/ _____

Subscribed and sworn before me this _____ day

of _____.

Contract No. 07-4H9104

- Failure to submit the notarized certificate will be sufficient cause for denying the claim.
- Any claim for overhead type expenses or costs, in addition to being certified as stated above, shall be supported by an audit report of an independent Certified Public Accountant. Any claim for overhead shall also be subject to audit by the State at its discretion.
- Any costs or expenses incurred by the State in reviewing or auditing any claims that are not supported by the Contractor's cost accounting or other records shall be deemed to be damages incurred by the State within the meaning of the California False Claims Act.
- The District Director of the District which administers the contract will make the final determination of any claims which remain in dispute after completion of claim review by the Engineer. A board or person designated by the District Director will review those claims and make a written recommendation thereon to the District Director. The Contractor may meet with the review board or person to make a presentation in support of those claims.
- Upon final determination of the claims, the Engineer will then make and issue the Engineer's final statement in writing and within 30 days thereafter the State will pay the entire sum, if any, found due thereon. That final statement shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Section 7-1.08, "Clerical Errors," of these General Conditions.

7-1.08 CLERICAL ERRORS

- Notwithstanding the provisions in Section 7-1.07, "Final Payment And Claims," of these General Conditions, for a period of 3 years after acceptance of the work, all estimates and payments made pursuant to Section 7-1.07, including the final statement and payment, shall be subject to correction and adjustment for clerical errors in the calculations involved in the determination of quantities and payments. The Contractor and the Department agree to pay to the other any sum due under the provisions of this Section 7-1.08, provided, however, if the total sum to be paid is less than \$200, no payment shall be made.

7-1.09 GUARANTEE

- The Contractor hereby unconditionally guarantees that the mechanical and electrical equipment and related components in the building work will be done in conformance with the requirements of the contract, and further guarantees the same to be and remain free of defects in workmanship and materials for a period of 6 months from the date of acceptance of the contract. The Contractor hereby agrees to repair or replace any and all mechanical and electrical equipment and related components in the building work that may prove to be not in conformance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.
- A portion of the performance bond for the contract in a sum equal to one half the value of the mechanical and electrical equipment and related components in the building work, shall remain in full force and effect during the guarantee period. The value of those mechanical and electrical equipment and related components shall be the value determined in conformance with the requirements specified in Section 6-1.05, "Schedule of Values" of the General Conditions.
- The Contractor further agrees that, within 10 calendar days after being notified in writing by the Department of any mechanical and electrical equipment and related components in the building work not in conformance with the requirements of the contract or any defects in the mechanical and electrical equipment and related components in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event the Contractor fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

7-1.10 ARBITRATION

- Sections 10240-10240.13, inclusive of the Public Contract Code provides for the resolution of contract claims by arbitration.
- Claims (demands for monetary compensation or damages) arising under or related to performance of the contract shall be resolved by arbitration unless the Department and the Contractor agree in writing, after the claim has arisen, to waive arbitration and to have the claim litigated in a court of competent jurisdiction. Arbitration shall be pursuant to Public Contract Code Sections 10240-10240.13, inclusive, and applicable regulations (see Subchapter 3 [Sections 301-382, inclusive] of Chapter 2 of Title 1 of the California Code of Regulations). The arbitration decision shall be decided under and

in conformance with the law of this State, supported by substantial evidence and, in writing, contain the basis for the decision, findings of fact, and conclusions of law.

- Arbitration shall be initiated by a Complaint in Arbitration made in compliance with the requirements of those regulations. A Complaint in Arbitration by the Contractor shall be made not later than 90 days after the date of service in person or by mail on the Contractor of the final written decision by the Department on the claim.

-

**STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION**

SPECIAL PROVISIONS

Annexed to Contract No. 07-4H9104

DIVISION 0 BIDDING AND CONTRACT REQUIREMENTS

0.01 INSTRUCTIONS TO BIDDERS AND GENERAL CONDITIONS

The work embraced herein shall conform to the provisions in the Instructions to Bidders and General Conditions for Building Construction of the Department of Transportation, dated January, 2002, a single publication attached hereto and referred to herein as "Instructions to Bidders" and "General Conditions", and the following special provisions.

In case of conflict between the Instructions to Bidders or the General Conditions and these special provisions, the special provisions shall take precedence over and be used in lieu of the conflicting portions.

0.02 PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder's attention is directed to the provisions in Section 1, "Proposal Requirements and Conditions," of the Instructions to Bidders, and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 1-1.05, "Required Listing of Proposed Subcontractors," of the Instructions to Bidders, each proposal shall have listed therein the name and address of each DVBE subcontractor to be used for credit in meeting the goal, and to whom the bidder proposes to directly subcontract portions of the work. The list of subcontractors shall also set forth the portion of work that will be performed by each subcontractor listed. A sheet for listing the subcontractors is included in the Proposal.

The Bidder's Bond form mentioned in the last paragraph in Section 1-1.07, "Proposal Guaranty," of the Instructions to Bidders will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

0.024 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) in contracts.

It is the policy of the Department that Disabled Veteran Business Enterprise (DVBE) shall have the maximum opportunity to participate in the performance of contracts financed solely with state funds. The Contractor shall ensure that DVBEs have the maximum opportunity to participate in the performance of this contract and shall take all necessary and reasonable steps for this assurance. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts. Failure to carry out the requirements of this paragraph shall constitute a breach of contract and may result in termination of this contract or other remedy the Department may deem appropriate.

Bidder's attention is directed to the following:

- A. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business and Disabled Veteran Business Enterprise Certification, Department of General Services.
- B. A DVBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, or vendor of material or supplies.
- C. Credit for DVBE prime contractors will be 100 percent.
- D. A DVBE joint venture partner must be responsible for a clearly defined portion of the work to be performed. Responsibility means actually performing, managing and supervising that portion of the work with its own forces. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks and profits of the joint venture. The DVBE joint venturer must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Division 0.026, "Submission of DVBE Information," elsewhere in these special provisions.

- E. A DVBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. Credit for DVBE vendors of materials or supplies is limited to 60 percent of the amount to be paid to the vendor for the material unless the vendor manufactures or substantially alters the goods.
- G. Credit for trucking by DVBEs will be as follows:
 - 1. One hundred percent of the amount to be paid when a DVBE trucker will perform the trucking with his/her own trucks, tractors and employees.
 - 2. Twenty percent of the amount to be paid to DVBE trucking brokers who do not have a "certified roster."
 - 3. One hundred percent of the amount to be paid to DVBE trucking brokers who have signed agreements that all trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that all trucks are owned by DVBEs, and a signed statement on the "certified roster" that indicates that 100 percent of revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."
 - 4. Twenty percent of the amount to be paid to trucking brokers who are not a DVBE but who have signed agreements with DVBE truckers assuring that at least 20 percent of the trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that at least 20 percent of the number of trucks are owned by DVBE truckers, and a signed statement on the "certified roster" that indicates that at least 20 percent of the revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."

The "certified roster" referred to herein shall conform to the requirements in Division 0.026, "Submission Of DVBE Information," elsewhere in these special provisions.

- H. DVBEs and DVBE joint venture partners must be certified DVBEs as determined by the Department of General Services, Office of Small Business and Disabled Veteran Business Enterprise Certification, 707 Third Street, West Sacramento, CA 95605, on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
- I. Noncompliance by the Contractor with these requirements constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

0.025 DVBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disabled Veteran Business Enterprise (DVBE) participation for this project:

Disabled Veteran Business Enterprise (DVBE): 3 percent.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation.

The Office of Small Business and Disabled Veteran Business Enterprise Certification, Department of General Services, may be contacted at (800) 559-5529 or (916) 375-4940 or visit their internet web site at <http://www.pd.dgs.ca.gov/smbus/default.htm> for program information and certification status. The Department's Business Enterprise Program may also be contacted through their internet web site at <http://www.dot.ca.gov/hq/bep/> or at (866) 810-6346 or (916) 324-1700.

0.026 SUBMISSION OF DVBE INFORMATION

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DVBEs and to select those portions of the work or material needs consistent with the available DVBEs to meet the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DVBE information sent by

U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that good faith efforts to meet the DVBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their adequate good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of DVBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DVBE transaction, and a written confirmation from the DVBE that it is participating in the contract. A copy of the DVBE's quote will serve as written confirmation that the DVBE is participating in the contract. When 100 percent of a portion of the work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work. The work that a DVBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DVBE subcontractors, suppliers and trucking companies will count toward the goal.

If credit for trucking by a DVBE trucking broker is shown on the bidder's information as 100 percent of the revenue to be paid by the broker is to be paid to DVBE truckers, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that all the trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification numbers. The roster must indicate that all revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

If credit for trucking by a trucking broker who is not a DVBE is shown in the bidder's information, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that at least 20 percent of the broker's trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification number. The roster must indicate that at least 20 percent of the revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

A bidder shall be deemed to have made good faith efforts upon submittal, within time limits specified by the Department, of documentary evidence that all of the following actions were taken:

- A. Contact was made with the Office of Small Business and Disabled Veteran Business Enterprise Certification, Department of General Services or their web site at <http://www.pd.dgs.ca.gov/smbus/default.htm> to identify Disabled Veteran Business Enterprises.
- B. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
- C. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
- D. Available Disabled Veteran Business Enterprises were considered.

0.027 SMALL BUSINESS PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

Attention is also directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq and Title 2, California Code of Regulations, Section 1896, et seq.

Bidders who wish to be classified as a Small Business under the provisions of those laws and regulations, shall be certified as Small Business by the Department of General Services, Office of Small Business and Disabled Veteran Business Enterprise Certification, 707 Third Street, West Sacramento, CA 95605.

To request Small Business Preference, bidders shall fill out and sign the Request for Small Business Preference form in the Proposal and shall attach a copy of their Office of Small Business and Disabled Veteran Business Enterprise Certification (OSDC) small business certification letter to the form. The bidder's signature on the Request for Small Business Preference certifies, under penalty of perjury, that the bidder is certified as Small Business at the time of bid opening and further certifies, under penalty of perjury, that under the following conditions, at least 50 percent of the subcontractors to be utilized on the project are either certified Small Business or have applied for Small Business certification by bid opening date and are subsequently granted Small Business certification.

The conditions requiring the aforementioned 50 percent level of subcontracting by Small Business subcontractors apply

if:

- A. The lowest responsible bid for the project exceeds \$100,000; and
- B. The project work to be performed requires a Class A or a Class B contractor's license; and
- C. Two or more subcontractors will be used.

If the above conditions apply and Small Business Preference is granted in the award of the contract, the 50 percent Small Business subcontractor utilization level shall be maintained throughout the life of the contract.

0.028 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- A. Has its principal place of business in California.
- B. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- C. Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

0.03 AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 2, "Award and Execution of Contract," of the Instructions to Bidders and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DVBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

The contract shall be executed by the successful bidder and shall be returned, together with the contract bonds, to the Department so that it is received within 10 days, not including Saturdays, Sundays and legal holidays, after the bidder has received the contract for execution. Failure to do so shall be just cause for forfeiture of the proposal guaranty. The executed contract documents shall be delivered to the following address: Department of Transportation MS 43, Attn: Office Engineer, 1727 30th Street, Sacramento, CA 95816.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business Preference" of these special provisions. Any bidder who is certified as a Small Business by the Department of General Services, Office of Small Business and Disabled Veteran Business Enterprise Certification, will be allowed a preference in the award of this contract, if it be awarded, under the following conditions:

- A. The apparent low bidder is not certified as a Small Business, or has not filled out and signed the Request for Small Business Preference included with the bid documents and attached a copy of their Office of Small Business and Disabled Veteran Business Enterprise Certification small business certification letter to the form; and
- B. The bidder filled out and signed the Request for Small Business Preference form included with the bid documents and attached a copy of their Office of Small Business and Disabled Veteran Business Enterprise Certification small business certification letter to the form.

The small business preference will be a reduction in the bid submitted by the small business contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the small business contractor becoming the low bidder, then the contract will be awarded to the small business contractor on the basis of the actual bid of the small business contractor notwithstanding the reduced bid price used for bid comparison purposes.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over nonsmall business bidders in that the application of the "California company" preference for which nonsmall business bidders may be eligible shall not result in the denial of the award to a small business bidder.

0.04 BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 6-1.03, "Beginning of Work," Section 6-1.07, "Time of Completion," and Section 6-1.08, "Liquidated Damages," of the General Conditions and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **160 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$300 per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

0.052 DIFFERING SITE CONDITIONS

Attention is directed to Section 2-1.045, "Differing Site Conditions," of the General Conditions.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 7-1.03, "Notice of Potential Claim," of the General Conditions and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

0.053 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final statement, ordered changes in the work

Contract No. 07-4H9104

payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final statements shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid ordered changes in work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed bill for ordered changes in the work. To be properly submitted, the bill must be submitted within 7 days of the performance of the ordered change in the work and in conformance with the provisions in Section 3, "Changes in the Work," and Section 7-1.05, "Partial Payments," of the General Conditions. An undisputed ordered change in the work bill not submitted within 7 days of performance of the ordered change in the work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and ordered change in the work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of that claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

0.054 FINAL PAYMENT AND CLAIMS

Attention is directed to Section 7-1.07, "Final Payment and Claims," of the General Conditions.

If the Contractor files a timely written statement of claims in response to the proposed final estimate, the District that administers the contract will submit a claim position letter to the Contractor by hand delivery or deposit in the U.S. mail within 135 days of acceptance of the contract. The claim position letter will delineate the District's position on the Contractor's claims. If the Contractor disagrees with the claim position letter, the Contractor shall submit a written notification of its disagreement to be received by the District not later than 15 days after the Contractor's receipt of the claim position letter. The written notification of disagreement shall set forth the basis for the Contractor's disagreement and be submitted to the office designated in the claim position letter. The Contractor's failure to provide a timely, written notification of disagreement shall constitute the Contractor's acceptance and agreement with the determinations provided in the claim position letter and with final payment pursuant to the claim position letter.

If the Contractor files a timely notification of disagreement with the District claim position letter, the board of review designated by the District Director to review claims that remain in dispute will meet with the Contractor within 45 days after receipt by the District of the notification of disagreement. Attendance by the Contractor at the board of review meeting shall be mandatory.

If the District fails to submit a claim position letter to the Contractor within 135 days after the acceptance of the contract and the Contractor has claims that remain in dispute, the Contractor may request a meeting with the board of review designated by the District Director to review claims that remain in dispute. The Contractor's request for a meeting shall identify the claims that remain in dispute. If the Contractor files a request for a meeting, the board of review will meet with the Contractor within 45 days after the District receives the request for the meeting. Attendance by the Contractor at the District Director's board of review meeting shall be mandatory.

Failure of the Contractor to file a timely written statement of claims in response to the proposed final estimate, or to file a timely notification of disagreement with the District claim position letter, or to attend the District Director's board of review meeting shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract and shall be a bar to arbitration in conformance with the requirements in Section 10240.2 of the California Public Contract Code.

0.055 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If performance of the Contractor's current controlling operation is delayed in the area, and the delay could not be avoided by the judicious handling of forces, equipment, and plant, an extension of time determined in conformance with the provisions in Section 6-1.08, "Liquidated Damages," of the General Conditions will be granted. Compensation for the delay will be made only for the Contractor's actual losses due to idle time of equipment, necessary payments for idle time of workers, and cost of extra moving of equipment, in conformance with the provisions in Section 3-1.01E, "Allowable Costs for Changes," of the General Conditions, except that no markups will be added.

0.067 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product must also operate accurately in the manner in which it was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 4-1.04, "Certificates of Compliance," of the General Conditions for all automated devices furnished for the project.

0.07 SUBCONTRACTOR AND DVBE RECORDS

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (S) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer.

0.075 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS

The DVBEs listed by the Contractor in response to the provisions in Division 0.026, "Submission of DVBE Information," and Division 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to utilize other forces or sources of materials may be requested for the following reasons:

- A. The listed DVBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when the written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of the subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DVBE becomes bankrupt or insolvent.
- C. The listed DVBE fails or refuses to perform the subcontract or furnish the listed materials.
- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DVBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. The listed DVBE subcontractor is not licensed pursuant to the Contractor's License Law.
- G. It would be in the best interest of the State.

The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

0.077 SUBCONTRACTING

Attention is directed to the provisions in Section 6-1.01, "Subletting and Subcontracting," of the General Conditions, and Division 0.02, "Proposal Requirements and Conditions," Division 0.026, "Submission of DVBE Information," and Division 0.030, "Award and Execution of Contract," of these special provisions.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is

available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The DVBE information furnished under Division 0.026, "Submission of DVBE Information," of these special provisions is in addition to the subcontractor information required to be furnished in Section 1-1.05, "Required Listing of Proposed Subcontractors," of the Instructions to Bidders and Section 6-1.01, "Subletting and Subcontracting," of the General Conditions.

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in highway contracts that are State funded. As a part of this requirement:

- A. No substitution of a DVBE subcontractor shall be made at any time without the written consent of the Department, and
- B. If a DVBE subcontractor is unable to perform successfully and is to be replaced, the Contractor shall make good faith efforts to replace the original DVBE subcontractor with another DVBE subcontractor.

The provisions in Division 0.024, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to DVBE substitutions after award of the contract.

0.082 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

0.10 GUARANTEE

Section 7-1.09, "Guarantee," of the General Conditions is amended to read:

7-1.09 GUARANTEE.—The Contractor hereby unconditionally guarantees that the work will be done in conformance with the requirements of the contract, and further guarantees the work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required by the special provisions. The Contractor hereby agrees to repair or replace any and all work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in conformance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

Contract bonds shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any work not in conformance with the requirements of the contract or any defects in the work, the Contractor shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event the Contractor fails to comply, the Contractor does hereby authorize the Department to proceed to have the work done at the Contractor's expense and the Contractor shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

12/21/02 100% specification fast track 1 week. E-Mail PS&E specs to Dist 07 PE, John Holzhauser. Instructions to Thi and Barbara Brown requesting formal Estimate from Joe T. prior to transmittal to Programming. Circulation set to Barbara.

1/08/03 Incorporated mech, elec, and arch changes and distributed hard copy circulation set.

1/22/03 Insert final mech spec, edits to earthwork, fax PSE paperwork to Brenda Robson, Dist 03 OE (Originally sent to Dist 07 OE on Dec 24, 02), E-mail final spec version to Brenda.

DIVISION 1. GENERAL REQUIREMENTS

1.01 SCOPE

The building work described herein and as shown on the plans shall conform to the requirements of the General Conditions and these special provisions.

The building work to be done consists, in general, of fabricating, transporting, and installing a modular office including utilities hook-up at the Conejo Westbound Weigh Station in Tehama County. The work shall include such other items or details, not mentioned above, that are required by the plans, General Conditions, or these special provisions to be performed, placed, constructed or installed.

1.02 FIRST ORDER OF WORK

Attention is directed to "Water Pollution Control" of these special provisions regarding the submittal and approval of the Storm Water Pollution Prevention Plan prior to performing work having potential to cause water pollution.

1.03 AREAS FOR CONTRACTOR'S USE

No area is available within the contract limits for the exclusive use of the Contractor. The Contractor shall arrange with the Engineer for areas to store equipment and materials within the work area.

1.04 COOPERATION

Attention is directed to Sections 5-1.06, "Responsibility for Utilities," and 5-1.12, "Cooperation," of the General Conditions and these special provisions.

Weigh Station operations will be in progress adjacent to the contract limits during the working period for this contract except when the modular building sections are delivered to the site which will necessitate temporary Weigh Station closure. The Contractor shall notify the Engineer 10 days in advance of modular building delivery to ensure closure activities can be coordinated with the CHP and the public.

The Contractor shall comply with all security policies and normal working hours of the State concerning the Conejo Weigh Station.

The Contractor shall plan his work to minimize interference with State forces and the public. Interruptions to any services for the purpose of making or breaking a connection shall be made only after consultation with and for such time periods as directed by the Engineer.

1.05 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the General Conditions and these special provisions, and as directed by the Engineer.

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the building work shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

1.06 SUBMITTALS

Shop drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 2-1.04, "Shop Drawings, Descriptive Data, Samples, and Alternatives," of the General Conditions and these special provisions.

Unless otherwise permitted in writing by the Engineer and except submittals for "Alternatives" in conformance with the provisions of said Section 2-1.04 of the General Conditions, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 2-1.01, "Authority of Engineer," of the General Conditions. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Division of Structure Design, Documents Unit, Fourth Floor, Mail Station 9-4/4I, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252.

Contract No. 07-4H9104

1.07 SCHEDULE OF VALUES

The Contractor shall prepare and submit to the Engineer for approval 2 copies of a Schedule of Values within 15 working days of approval of the contract. The Engineer shall be allowed 15 working days for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete the review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 6-1.08, "Liquidated Damages," of the General Conditions.

The Schedule of Values shall cover each lump sum item for building work and shall be accurately divided into sections representing the cost of each separate building or structure. Any site work that is not part of a separate building or structure shall be included under a specific section as General Work and not included in the building or structure cost. Indirect costs and general condition items are to be listed as a separate line item of work. The sections representing each building or structure must be identified as to the building or structure they represent and be broken down to show the corresponding value of each craft, trade or other significant portion of the work. A sub-total for each section shall be provided.

The Schedule of Values shall be approved by the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead and profit shall not be listed as separate items, but shall be appropriately distributed across all line items of cost.

1.08 OBSTRUCTIONS

Attention is directed to Sections 5-1.02, "Protection and Use of Property," 5-1.03, "Responsibility for Damage," and 5-1.06, "Responsibility for Utilities," of the General Conditions and these special provisions.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 5 working days prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include but are not limited to the following:

Underground Service Alert
Northern California (USA)
Telephone: 1(800)642-2444

Underground Service Alert
Southern California (USA)
Telephone: 1(800)422-4133

South Shore Utility
Coordinating Council (DIGS)
Telephone: 1(800)541-3447

Western Utilities
Underground Alert, Inc.
Telephone: 1(800)424-3447

1.09 PRESERVATION OF PROPERTY

Attention is directed to Sections 5-1.02, "Protection and Use of Property," 5-1.03, "Responsibility for Damage," 5-1.05, "Contractor's Responsibility for the Work," and 5-1.06, "Responsibility for Utilities," of the General Conditions.

Operations shall be conducted in such a manner that existing facilities, surfacing, installations, and utilities which are to remain in place will not be damaged. Temporary surfacing, facilities, utilities and installations shall also be protected until they are no longer required. The Contractor, at his expense shall furnish and install piling, sheet piling, cribbing, bulkheads, shores, or whatever means may be necessary to adequately support material carrying such facilities, or to support the facilities themselves and shall maintain such support until they are no longer needed.

1.10 TEMPORARY CONTROLS

GENERAL.--

The Contractor shall provide storm water controls such as earthen embankments and similar barriers in and around excavations and subgrade construction, sufficient to prevent flooding by runoff of storm water from heavy rains.

1.11 PUBLIC SAFETY

It is the Contractor's responsibility to provide for the safety of traffic and the public during construction.

Whenever the Contractor's operations create a condition hazardous to traffic or to the public, the Contractor shall, at the Contractor's expense and without cost to the State, furnish, erect and maintain such fences, temporary railing (Type K), barricades, lights, signs and other devices and take such other protective measures as are necessary to prevent accidents or damage or injury to the public.

Fences, temporary railing (Type K), barricades, lights, signs, and other devices furnished, erected and maintained by the Contractor, at the Contractor's expense, are in addition to any construction area traffic control devices which are specified elsewhere in these special provisions.

The Contractor shall also furnish such flaggers as are necessary to give adequate warning to traffic or to the public of any dangerous conditions to be encountered. Full compensation for flaggers for public safety shall be considered as included in the contract lump sum price paid for building work and no separate payment will be made therefor.

Signs, lights, flags, and other warning and safety devices and their use shall conform to the requirements set forth in the current MANUAL OF TRAFFIC CONTROLS, published by the Department. Signs or other protective devices furnished and erected by the Contractor at the Contractor's expense, as above provided, shall not obscure the visibility of, nor conflict in intent, meaning and function of either existing signs, lights and traffic control devices or any construction area signs and traffic control devices for which furnishing of, or payment for, is provided elsewhere in these special provisions. Signs furnished and erected by the Contractor at the Contractor's expense shall be approved by the Engineer as to size, wording and location.

The installation of general roadway illumination shall not relieve the Contractor of his responsibility for furnishing and maintaining any of the protective facilities herein before specified.

Construction equipment shall enter and leave the highway via existing ramps and crossovers and shall move in the direction of public traffic. All movements of workmen and construction equipment on or across lanes open to public traffic shall be performed in a manner that will not endanger public traffic.

When leaving a work area and entering a roadway carrying public traffic, the Contractor's equipment, whether empty or loaded, shall in all cases yield to public traffic.

In addition to any other measures taken by the Contractor pursuant to the provisions of this division, "Public Safety," the Contractor shall install temporary railing (Type K) between any lane carrying public traffic and any excavation, obstacle, or storage area when the following conditions exist:

- A. Excavations.--The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - 2. Excavations less than 0.3-m deep.
 - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.--The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.--Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this Division "Public Safety" and in the Division entitled, "Public Safety," of these special provisions, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash

cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in, "Temporary Railing (Type K)," of these special provisions. Temporary railing (Type K), conforming to the details shown on the Department's 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to the Department's 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this division shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

No material or equipment shall be stored where it will interfere with the free and safe passage of public traffic, and at the end of each day's work and at other times when construction operations are suspended for any reason, the Contractor shall remove all equipment and other obstructions from that portion of the roadway open for use by public traffic.

Temporary facilities which the Contractor uses to perform the work shall not be installed or placed where they will interfere with the free and safe passage of public traffic.

Temporary facilities which could be a hazard to public safety if improperly designed shall comply with design requirements specified in the contract for such facilities or, if none are specified, with standard design criteria or codes appropriate for the facility involved. Working drawings for such temporary facilities shall be prepared and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California, and shall be submitted to the Engineer for approval. The submittals shall designate thereon the standard design criteria or codes used. Installation of such temporary facilities shall not start until the Engineer has reviewed and approved the drawings.

Should the Contractor appear to be neglectful or negligent in furnishing warning devices and taking protective measures as specified herein, the Engineer may direct attention to the existence of a hazard and the necessary warning devices shall be furnished and installed and protective measures taken by the Contractor at the Contractor's expense. Should the Engineer point out the inadequacy of warning devices and protective measures, such action on the part of the Engineer shall not relieve the Contractor from responsibility for public safety or abrogate his obligation to furnish and pay for these devices and measures.

PAYMENT

Except as provided in these special provisions, full compensation for public safety shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

1.12 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 5-1.01R, "Water Pollution," of the General Conditions and these special provisions.

This project lies within the boundaries of the Los Angeles Regional Water Quality Control Board (RWQCB).

The State Water Resources Control Board (SWRCB) has issued a permit to the Department which governs storm water and non-storm water discharges from its properties, facilities and activities. The Department's Permit is entitled: "Order No. 99-06-DWQ, NPDES No. CAS000003, National Pollutant Discharge Elimination System (NPDES) Permit, Storm Water Permit and Waste Discharge Requirements (WDRs) for the State of California, Department of Transportation Properties, Facilities, and Activities." Copies of the Department's Permit are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254, and may also be obtained from the SWRCB Internet website at: <http://www.swrcb.ca.gov/stormwtr/caltrans.html>.

Contract No. 07-4H9104

The Department's Permit references and incorporates by reference the current Statewide General Permit issued by the SWRCB entitled "Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Associated with Construction Activity," which regulates discharges of storm water and non-storm water from construction activities disturbing 2 or more hectares of soil in a common plan of development. Sampling and analysis requirements as specified in SWRCB Resolution No. 2001-46 are added to the Statewide General Permit. Copies of the Statewide General Permit and modifications thereto are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254 and may also be obtained from the SWRCB Internet website at: <http://www.swrcb.ca.gov/stormwtr/construction.html>.

The NPDES permit that regulate this project, as referenced above, are hereafter collectively referred to as the "Permits."

This project shall conform to the Permits and modifications thereto. The Contractor shall maintain copies of the Permits at the premises and shall make the Permits available during construction.

The Permits require the preparation of a Storm Water Pollution Prevention Plan (SWPPP). The SWPPP shall be prepared in conformance with the requirements of the Permits, the Department's "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual," and the Department's "Construction Site Best Management Practices (BMPs) Manual," including addenda issued up to and including the date of advertisement of the project. These manuals are hereinafter referred to, respectively, as the "Preparation Manual" and the "Construction Site BMPs Manual," and collectively, as the "Manuals." Copies of the Manuals may be obtained from the Department of Transportation, Materiel Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520, and may also be obtained from the Department's Internet website at: <http://www.dot.ca.gov/hq/construc/stormwater.html>.

The Contractor shall know and fully comply with applicable provisions of the Permits and all modifications thereto, the Manuals, and Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from both the premises and areas of disturbance outside the premises during construction. Attention is directed to Sections 5-1.01, "Laws to be Observed," 5-1.031, Indemnification," and 5-1.032, "Insurance," of the General Conditions.

The Permits shall apply to storm water and certain permitted non-storm water discharges from areas outside the premises which are directly related to construction activities for this contract including, but not limited to, material borrow areas, staging areas, storage yards and access roads. The Contractor shall comply with the Permits and the Manuals for those areas and shall implement, inspect and maintain the required water pollution control practices. Installing, inspecting and maintaining water pollution control practices on areas outside the premises not specifically arranged and provided for by the Department for the execution of this contract, will not be paid for.

The Contractor shall be responsible for penalties assessed or levied on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in this division, "Water Pollution Control," including, but not limited to, compliance with the applicable provisions of the Permits, the Manuals, and Federal, State and local regulations and requirements as set forth therein.

Penalties as used in this division, "Water Pollution Control," shall include fines, penalties and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of the Permits, the Manuals, or applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

RETENTION OF FUNDS

Notwithstanding any other remedies authorized by law, the Department may retain money due the Contractor under the contract, in an amount determined by the Department, up to and including the entire amount of Penalties proposed, assessed, or levied as a result of the Contractor's violation of the Permits, the Manuals, or Federal or State law, regulations or requirements. Funds may be retained by the Department until final disposition has been made as to the Penalties. The Contractor shall remain liable for the full amount of Penalties until such time as they are finally resolved with the entity seeking the Penalties.

Retention of funds for failure to conform to the provisions in this division, "Water Pollution Control," shall be in addition to the other retention amounts required by the contract. The amounts retained for the Contractor's failure to conform to provisions in this division will be released for payment on the next monthly estimate for partial payment following the date when an approved SWPPP has been implemented and maintained, and when water pollution has been adequately controlled, as determined by the Engineer.

When a regulatory agency identifies a failure to comply with the Permits and modifications thereto, the Manuals, or other Federal, State or local requirements, the Department may retain money due the Contractor, subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 7-1.05, "Partial Payments," of the General Conditions.
- C. If the Department has retained funds, and it is subsequently determined that the State is not subject to the entire amount of the Costs and Liabilities assessed or proposed in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained for the period of the retention. The interest rate payable shall be 6 percent per annum.

During the first estimate period that the Contractor fails to conform to the provisions in this division, "Water Pollution Control," the Department may retain an amount equal to 25 percent of the estimated value of the contract work performed.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the premises or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions or proposed fines by regulatory agencies to the requesting regulatory agency.

STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS

As part of the water pollution control work, a Storm Water Pollution Prevention Plan (SWPPP) is required for this contract. The SWPPP shall conform to the provisions in Section 5-1.01R, "Water Pollution," of the General Conditions, the requirements in the Manuals, the requirements of the Permits, and these special provisions. Upon the Engineer's approval of the SWPPP, the SWPPP shall be considered to fulfill the provisions in Section 5-1.01R, "Water Pollution," of the General Conditions for development and submittal of a Water Pollution Control Program.

No work having potential to cause water pollution, shall be performed until the SWPPP has been approved by the Engineer. Approval shall not constitute a finding that the SWPPP complies with applicable requirements of the Permits, the Manuals and applicable Federal, State and local laws, regulations, and requirements.

The Contractor shall designate a Water Pollution Control Manager. The Water Pollution Control Manager shall be responsible for the preparation of the SWPPP and required modifications or amendments, and shall be responsible for the implementation and adequate functioning of the various water pollution control practices employed. The Contractor may designate different Water Pollution Control Managers to prepare the SWPPP and to implement the water pollution control practices. The Water Pollution Control Manager(s) shall serve as the primary contact for issues related to the SWPPP or its implementation. The Contractor shall submit to the Engineer a statement of qualifications, describing the training, previous work history and expertise of the individual selected by the Contractor to serve as Water Pollution Control Manager(s). The Water Pollution Control Manager(s) shall have a minimum of 24 hours of formal storm water management training or certification as a Certified Professional in Erosion and Sediment Control (CPESC). The Engineer will reject the Contractor's submission of a Water Pollution Control Manager if the submitted qualifications are deemed to be inadequate.

Within 20 working days after the approval of the contract, the Contractor shall submit 3 copies of the draft SWPPP to the Engineer. The Engineer will have 5 working days to review the SWPPP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the SWPPP within 5 working days of receipt of the Engineer's comments. The Engineer will have 5 working days to review the revisions. Upon the Engineer's approval of the SWPPP, 3 approved copies of the SWPPP, incorporating the required changes, shall be submitted to the Engineer. In order to allow construction activities to proceed, the Engineer may conditionally approve the SWPPP while minor revisions are being completed. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for resulting losses, and an extension of time will be granted, as provided in Section 6-1.08, "Liquidated Damages," of the General Conditions.

The SWPPP shall apply to the areas within or outside of the premises that are directly related to construction including, but not limited to, material borrow areas, staging areas, storage yards, and access roads.

The SWPPP shall incorporate water pollution control practices in the following categories:

- A. Soil stabilization.
- B. Sediment control.
- C. Wind erosion control.
- D. Tracking control.
- E. Non-storm water management.
- F. Waste management and materials pollution control.

The Contractor shall develop a Water Pollution Control Schedule that describes the timing of grading or other work activities that could affect water pollution. The Water Pollution Control Schedule shall be updated by the Contractor to reflect changes in the Contractor's operations that would affect the necessary implementation of water pollution control practices.

The Contractor shall complete the "Construction Site BMPs Consideration Checklist" presented in the Preparation Manual and shall incorporate water pollution control practices into the SWPPP. Water pollution control practices include the "Minimum Requirements" and other Contractor-selected water pollution control practices from the "Construction Site BMPs Consideration Checklist" and the "Project-Specific Minimum Requirements" identified in the Water Pollution Control Cost Break-Down of this division.

The SWPPP shall include, but not be limited to, the items described in the Manuals, Permits and related information contained in the contract documents.

The Contractor shall prepare an amendment to the SWPPP when there is a change in construction activities or operations which may affect the discharge of pollutants to surface waters, ground waters, municipal storm drain systems, or when the Contractor's activities or operations violate a condition of the Permits, or when directed by the Engineer. Amendments shall identify additional water pollution control practices or revised operations, including those areas or operations not identified in the initially approved SWPPP. Amendments to the SWPPP shall be prepared and submitted for review and approval within a time approved by the Engineer, but in no case longer than the time specified for the initial submittal and review of the SWPPP. The Contractor shall keep one copy of the approved SWPPP and approved amendments at the premises. The SWPPP shall be made available upon request by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests by the public shall be directed to the Engineer.

COST BREAK-DOWN

The Contractor shall include a Water Pollution Control Cost Break-Down in the SWPPP which itemizes the cost for water pollution control work shown in the SWPPP. The Contractor shall use the Water Pollution Control Cost Break-Down provided in this division as the basis for the cost break-down submitted with the SWPPP. The Contractor shall use the Water Pollution Control Cost Break-Down to identify items, quantities and values for water pollution control work. The Contractor shall be responsible for the accuracy of the SWPPP quantities and values used in the cost break-down submitted with the SWPPP. Partial payment for water pollution control will not be made until the Water Pollution Control Cost Break-Down is approved by the Engineer.

Line items indicated in the Water Pollution Control Cost Break-Down in this division with a specified Estimated Quantity shall be considered "Project-Specific Minimum Requirements." The Contractor shall incorporate Project-Specific Minimum Requirements with Contractor-designated quantities and values into the Water Pollution Control Cost Break-Down submitted with the SWPPP.

Line items indicated in the Water Pollution Control Cost Break-Down in this division without a specified Estimated Quantity shall be considered by the Contractor for selection to meet the applicable "Minimum Requirements" as defined in the Manuals, or for other water pollution control work as identified in the "Construction Site BMPs Consideration Checklist" presented in the Preparation Manual. In the Water Pollution Control Cost Break-Down submitted with the SWPPP, the Contractor shall list only those water pollution control practices selected for the project, including quantities and values required to complete the work for those items.

The sum of the amounts for the work listed in the Water Pollution Control Cost Break-Down shall be equal to the cost shown for water pollution control in the cost break-down for building work. Overhead and profit shall be included in the individual items listed in the Water Pollution Control Cost Break-Down.

WATER POLLUTION CONTROL COST BREAK-DOWN

Contract No. 07-4H9104

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
SS-3	Hydraulic Mulch	M2			
SS-4	Hydroseeding	M2			
SS-5	Soil Binders	M2			
SS-6	Straw Mulch	M2			
SS-7	Geotextiles, Plastic Covers & Erosion Control Blankets/Mats	M2			
SS-8	Wood Mulching	M2			
SS-9	Earth Dikes/Drainage Swales & Lined Ditches	M			
SS-10	Outlet Protection/Velocity Dissipation Devices	EA			
SS-11	Slope Drains	EA			
SC-1	Silt Fence	M			
SC-2	Desilting Basin	EA			
SC-3	Sediment Trap	EA			
SC-4	Check Dam	EA			
SC-5	Fiber Rolls	M			
SC-6	Gravel Bag Berm	M			
SC-7	Street Sweeping and Vacuuming	LS			
SC-8	Sandbag Barrier	M			
SC-9	Straw Bale Barrier	M			
SC-10	Storm Drain Inlet Protection	EA			
WE-1	Wind Erosion Control	LS			
TC-1	Stabilized Construction Entrance/Exit	EA			
TC-2	Stabilized Construction Roadway	EA			
TC-3	Entrance/Outlet Tire Wash	EA			
NS-1	Water Conservation Practices	LS			
NS-2	Dewatering Operations	EA			
NS-3	Paving and Grinding Operations	LS			
NS-4	Temporary Stream Crossing	EA			

Contract No. 07-4H9104

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
NS-5	Clear Water Diversion	EA			
NS-6	Illicit Connection/Illegal Discharge Detection and Reporting	LS			
NS-7	Potable Water/Irrigation	LS			
NS-8	Vehicle and Equipment Cleaning	LS			
NS-9	Vehicle and Equipment Fueling	LS			
NS-10	Vehicle and Equipment Maintenance	LS			
WM-1	Material Delivery and Storage	LS			
WM-2	Material Use	LS			
WM-3	Stockpile Management	LS			
WM-4	Spill Prevention and Control	LS			
WM-5	Solid Waste Management	LS			
WM-6	Hazardous Waste Management	LS			
WM-7	Contaminated Soil Management	LS			
WM-8	Concrete Waste Management	LS			
WM-9	Sanitary/Septic Waste Management	LS			
WM-10	Liquid Waste Management	LS			
	Prepare Storm Water Pollution Prevention Plan	LS			

TOTAL _____

Adjustments in the quantities listed in the approved Water Pollution Control Cost Break-Down shall be made when required to address amendments to the SWPPP, except when the adjusted items are paid for in conformance with the provisions in Section 3, "Changes," of the General Conditions.

No adjustment in compensation will be made for work completed as shown on the approved SWPPP. No adjustment in compensation will be made for ordered changes to correct SWPPP work resulting from the Contractor's own operations or from the Contractor's negligence.

The approved cost break-down will be used to determine partial payments during the progress of the work and as the basis for calculating the adjustment in compensation for increases or decreases of quantities ordered by the Engineer. When an ordered change increases or decreases the quantities of an approved cost break-down item, the adjustment in compensation will be determined in conformance with the provisions in Section 3, "Changes," of the General Conditions. If an ordered change requires a new item which is not on the approved cost break-down, the adjustment in compensation will be determined in conformance with the provisions in Section 3, "Changes," of the General Conditions.

If requested by the Contractor and approved by the Engineer, changes to the water pollution control practices listed in the approved cost break-down, including addition of new water pollution control practices, will be allowed. Changes shall be included in the approved amendment of the SWPPP. If the requested changes result in a net cost increase, an adjustment in compensation will be made. The net cost increase to the lump sum item Building Work will be paid for in conformance with the provisions in Section 3, "Changes," of the General Conditions.

SWPPP IMPLEMENTATION

Unless otherwise specified, upon approval of the SWPPP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, maintaining, removing, and disposing of the water pollution control practices specified in the SWPPP and in the amendments. Unless otherwise directed by the Engineer, the Contractor's responsibility for SWPPP implementation shall continue throughout temporary suspensions of work ordered in conformance with the provisions in Section 6-1.06, "Temporary Suspension of Work," of the General Conditions. Requirements for installation, construction, inspection, maintenance, removal, and disposal of water pollution control practices shall conform to the requirements in the Manuals and these special provisions.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved SWPPP or amendments, the deficiency shall be corrected immediately unless requested by the Contractor and approved by the Engineer in writing, but shall be corrected prior to the onset of precipitation. If the Contractor fails to correct the identified deficiency by the date agreed or prior to the onset of precipitation, the project shall be in nonconformance with this division, "Water Pollution Control." Attention is directed to Section 2-1.01, "Authority of Engineer," of the General Conditions, and to "Retention of Funds" of this division for possible nonconformance penalties.

If the Contractor fails to conform to the provisions of this division, "Water Pollution Control," the Engineer may order the suspension of construction operations until the project complies with the requirements of this division.

Implementation of water pollution control practices may vary by season. The Construction Site BMPs Manual and these special provisions shall be followed for control practice selection of year-round, rainy season and non-rainy season water pollution control practices.

Year-Round Implementation Requirements

The Contractor shall have a year-round program for implementing, inspecting and maintaining water pollution control practices for wind erosion control, tracking control, non-storm water management, and waste management and materials pollution control.

The National Weather Service weather forecast shall be monitored and used by the Contractor on a daily basis. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted, the necessary water pollution control practices shall be deployed prior to the onset of the precipitation.

Disturbed soil areas shall be considered active whenever the soil disturbing activities have occurred, continue to occur or will occur during the ensuing 21 days. Non-active areas shall be protected as prescribed in the Construction Site BMPs Manual within 14 days of cessation of soil disturbing activities or prior to the onset of precipitation, whichever occurs first.

Rainy Season Implementation Requirements

Soil stabilization and sediment control practices conforming to the requirements of these special provisions shall be provided throughout the rainy season, defined as between October 1 and May 1.

An implementation schedule of required soil stabilization and sediment control practices for disturbed soil areas shall be completed no later than 20 days prior to the beginning of each rainy season. The implementation schedule shall identify the

soil stabilization and sediment control practices and the dates when the implementation will be 25 percent, 50 percent and 100 percent complete, respectively. For construction activities beginning during the rainy season, the Contractor shall implement applicable soil stabilization and sediment control practices.

Throughout the defined rainy season, the active disturbed soil area of the premises shall be not more than 1.9 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active disturbed soil area limit. Soil stabilization and sediment control materials shall be maintained on site sufficient to protect disturbed soil areas. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to deploy the water pollution control practices required to protect disturbed soil areas prior to the onset of precipitation.

Non-Rainy Season Implementation Requirements

The non-rainy season shall be defined as days outside the defined rainy season. The Contractor's attention is directed to the Construction Site BMPs Manual for soil stabilization and sediment control implementation requirements on disturbed soil areas during the non-rainy season. Disturbed soil areas within the project shall be protected in conformance with the requirements in the Construction Site BMPs Manual with an effective combination of soil stabilization and sediment control.

MAINTENANCE

To ensure the proper implementation and functioning of water pollution control practices, the Contractor shall regularly inspect and maintain the construction site for the water pollution control practices identified in the SWPPP. The construction site shall be inspected by the Contractor as follows:

- A. Prior to a forecast storm.
- B. After a precipitation event which causes site runoff.
- C. At 24 hour intervals during extended precipitation events.
- D. Routinely, a minimum of once every two weeks outside of the defined rainy season.
- E. Routinely, a minimum of once every week during the defined rainy season.

The Contractor shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. One copy of each site inspection record shall be submitted to the Engineer within 24 hours of completing the inspection.

REPORTING REQUIREMENTS

Report of Discharges, Notices or Orders

If the Contractor identifies discharges into surface waters or drainage systems in a manner causing, or potentially causing, a condition of pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge event, notice or order. The report shall include the following information:

- A. The date, time, location, nature of the operation, and type of discharge, including the cause or nature of the notice or order.
- B. The water pollution control practices deployed before the discharge event, or prior to receiving the notice or order.
- C. The date of deployment and type of water pollution control practices deployed after the discharge event, or after receiving the notice or order, including additional measures installed or planned to reduce or prevent reoccurrence.
- D. An implementation and maintenance schedule for affected water pollution control practices.

Report of First-Time Non-Storm Water Discharge

The Contractor shall notify the Engineer at least 3 days in advance of first-time non-storm water discharge events, excluding exempted discharges. The Contractor shall notify the Engineer of the operations causing non-storm water discharges and shall obtain field approval for first-time non-storm water discharges. Non-storm water discharges shall be monitored at first-time occurrences and routinely thereafter.

Annual Certifications

By June 15 of each year, the Contractor shall complete and submit an Annual Certification of Compliance, as contained

Contract No. 07-4H9104

in the Preparation Manual, to the Engineer.

PART 4.--PAYMENT

General.--Except as provided herein, full compensation for water pollution control shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

Attention is directed to Section 7-1.05, "Partial Payment," and Section 7-1.07, "Final Payment and Claims," of the General Conditions. Payments for prepare storm water pollution prevention plan will be made as follows:

- A. After the SWPPP has been approved by the Engineer, 75 percent of the cost shown in the Water Pollution Control Cost Break-Down for prepare storm water pollution prevention plan will be included in the monthly partial payment estimate.
- B. After acceptance of the contract in conformance with the provisions in Section 7-1.07, "Final Payment and Claims," of the General Conditions, payment for the remaining 25 percent of the cost shown in the Water Pollution Control Cost Break-Down for prepare storm water pollution prevention plan will be made.

For items identified on the approved Water Pollution Control Cost Break-Down, the cost of maintaining the temporary water pollution control practices shall be divided equally by the State and the Contractor as follows:

Soil Stabilization

Temporary water pollution control practices except:

SS-1 Scheduling

SS-2 Preservation of Existing Vegetation

Sediment Control

Temporary water pollution control practices except:

SC-7 Street Sweeping and Vacuuming

Wind Erosion Control

No sharing of maintenance costs will be allowed.

Tracking Control

TC-1 Stabilized Construction Entrance/Exit.

Non-Storm Water Management

No sharing of maintenance costs will be allowed.

Waste Management & Materials Pollution Control

No sharing of maintenance costs will be allowed.

The division of cost will be made by determining the cost of maintaining water pollution control practices in conformance with the provisions in Section 3, "Changes," of the General Conditions and paying to the Contractor one-half of that cost. Cleanup, repair, removal, disposal, improper installation, and replacement of water pollution control practices damaged by the Contractor's negligence, shall not be considered as included in the cost for performing maintenance.

The provisions for sharing maintenance costs shall not relieve the Contractor from the responsibility for providing appropriate maintenance on items with no shared maintenance costs.

Full compensation for non-shared maintenance costs of water pollution control practices, as specified in this division, "Water Pollution Control," shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

1.13 UTILITY CONNECTION

The Contractor shall make all arrangements and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions

Contract No. 07-4H9104

which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 45 days before service connections are required.

The costs incurred by the Contractor for the extension of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as an ordered change as provided in Section 3, "Changes in the Work," of the General Conditions.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

1.14 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in "Cooperation" of these special provisions.

The Contractor, at his own expense, shall obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

1.15 SANITARY FACILITIES

State sanitary facilities will be available for use by the Contractor's employees, during normal State working hours. Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

1.16 REFERENCES

Attention is directed to Section 1-1.26, "Abbreviations," of the General Conditions

When reference is made to the Uniform Building Code (UBC) on the plans or in the special provisions, it shall be the 1997 Uniform Building Code as amended by the 1998 Title 24 California Building Standards Code.

1.17 PROJECT RECORD DRAWINGS

The Contractor shall prepare and maintain one set of project record drawings, using an unaltered set of original project plans, to clearly show all as-constructed information for the project. As a minimum, the information to be shown shall include 1) any plan clarifications or change orders, 2) locations of any underground utilities, or 3) the location, size, type, and manufacturer of all major products or components selected by the Contractor for use in the work.

All markings shall be placed on the project record drawings using red ink or red pencil. Original figures shall not be eradicated nor written over and superseded material shall be neatly lined out. Additional drawings shall be submitted if the required information cannot be clearly shown on the original set of project plans. The additional drawings shall be not less than 279 mm x 432 mm in size and shall have the contract number on each sheet. The Contractor shall sign and date each sheet of the project record drawings to verify that all as-constructed information shown on the drawings is correct.

The Contractor shall periodically review the set of project record drawings with the Engineer during the progress of the work to assure that all changes and other required information are being recorded.

Before completion of the work, the Contractor shall request a review of the project record drawings to determine the completeness and adequacy of them. If the project record drawings are unacceptable, the Contractor shall inspect, measure, and survey the project as necessary to record the required additional information.

The set of completed project record drawings shall be delivered to the Engineer prior to acceptance of the contract.

1.18 FIELD ENGINEERING

This section specifies administrative and procedural requirements for field engineering services to be performed by the Contractor.

Lines and grades.--Such stakes or marks will be set by the Engineer as he determines to be necessary to establish the lines and grades required for the completion of the work shown on the plans and as specified in these special provisions. In general, these will consist of the primary vertical and horizontal control points.

Stakes and marks set by the Engineer shall be carefully preserved by the Contractor. In case such stakes and marks are destroyed or damaged they will be replaced at the Engineer's earliest convenience. The Contractor will be charged for the cost of necessary replacement or restoration of such stakes and marks which in the judgment of the Engineer were carelessly or willfully destroyed or damaged by the Contractor's operations. This charge will be deducted from any moneys due or to become due the Contractor.

All other stakes or marks required to establish the lines and grades required for the completion of the work shall be the responsibility of the Contractor.

Existing utilities and equipment.--The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, the Contractor shall investigate and verify the existence and location of underground utilities and other construction.

Prior to construction, the Contractor shall verify the location and invert elevation at points of connection of sanitary and septic sewers, storm sewer, and water or fire service piping.

Surveys for layout and performance.--The Contractor shall perform all surveys for layout and performance, reduce field notes, and make all necessary calculations and drawings necessary to carry out the work.

The Contractor shall locate and layout site improvements, and other work requiring field engineering services, including pavements, stakes for grading, fill and topsoil placement, utility slopes and invert elevations by instrumentation and similar appropriate means.

Batter boards shall be located and laid out for structures, building foundations, column grids and locations, floor levels and, control lines and levels required for mechanical and electrical work.

Survey accuracy and tolerances.--The tolerances generally applicable in setting survey stakes for foundations, slabs, and underground work shall not exceed the following:

Survey Stakes or Markers	Tolerance
Rough grading or excavation	30 mm
Trimming or preparation of subgrade for roadways	15 mm
Roadway surfacing, steel or concrete pipe	6 mm
Structures or building construction	3 mm

Such tolerance shall not supersede stricter tolerances required by the plans or special provisions, and shall not otherwise relieve the Contractor of responsibility for measurements in compliance therein.

1.19 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following requirements:

Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.

Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish all information necessary as required to the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision shall be final.

When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, a list of substitutions to be made shall be submitted for approval.

The following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325M	
METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR REINFORCEMENT	
METRIC BAR DESIGNATION NUMBER AS SHOWN ON THE PLANS	IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

SUBSTITUTION TABLE FOR WELDED PLAIN WIRE REINFORCEMENT, ASTM DESIGNATION: A 185	
	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF: (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449	
DIAMETER	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL			
UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED (GALVANIZED) SHEETS	
METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT US STANDARD GAGE inch	METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT GALVANIZED SHEET GAGE inch
7.94	0.3125		
6.07	0.2391		
5.69	0.2242		
5.31	0.2092		
4.94	0.1943		
4.55	0.1793		
4.18	0.1644	4.270	0.1681
3.80	0.1495	3.891	0.1532
3.42	0.1345	3.510	0.1382
3.04	0.1196	3.132	0.1233
2.66	0.1046	2.753	0.1084
2.28	0.0897	2.372	0.0934
1.90	0.0747	1.994	0.0785
1.71	0.0673	1.803	0.0710
1.52	0.0598	1.613	0.0635
1.37	0.0538	1.461	0.0575
1.21	0.0478	1.311	0.0516
1.06	0.0418	1.158	0.0456
0.91	0.0359	1.006 or 1.016	0.0396
0.84	0.0329	0.930	0.0366
0.76	0.0299	0.853	0.0336
0.68	0.0269	0.777	0.0306
0.61	0.0239	0.701	0.0276
0.53	0.0209	0.627	0.0247
0.45	0.0179	0.551	0.0217
0.42	0.0164	0.513	0.0202
0.38	0.0149	0.475	0.0187

CONVERSION TABLE FOR WIRE		
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT USA STEEL WIRE THICKNESS	GAGE NO.
mm	inch	
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR COMMON NAILS				
NAIL SIZE	METRIC		ENGLISH	
	mm		inch	
	Length	Diameter	Length	Diameter
8d	63.5	3.33	2 1/2	0.131
10d	76.2	3.76	3	0.148
16d	88.9	4.11	3 1/2	0.162

CONVERSION TABLE FOR LUMBER	
METRIC NOMINAL SURFACE DRY SIZE	EQUIVALENT NOMINAL SURFACE DRY U S SIZE
mm	inch
51	2
102	4
152	6
203	8
254	10
305	12

CONVERSION TABLE FOR PLYWOOD	
METRIC mm	ENGLISH inch
6.4	1/4
7.9	5/16
9.5	3/8
11.1	7/16
11.9	15/32
12.7	1/2
15.1	19/32
15.9	5/8
18.3	23/32
19.1	3/4
22.2	7/8
25.4	1
28.6	1 1/8

CONVERSION TABLE FOR INSULATION R-VALUE	
METRIC (K m ² /W)	ENGLISH (HR FT ² F/BTU)
0.5	3
0.7	4
1.4	8
1.9	11
2.3	13
2.5	14
3.3	19
5.3	30

CONVERSION TABLE FOR VAPOR TRANSMISSION RATING	
METRIC (Perm-m)	ENGLISH (perm-inch)
0.29	0.02

CONVERSION TABLE FOR LOW PRESSURE	
METRIC (Pa)	ENGLISH (Inches of Water Column)
30	0.125
60	0.25
90	0.375
120	0.50
150	0.60
155	0.625
175	0.70
185	0.75
200	0.80
250	1.00
310	1.25

CONVERSION TABLE FOR PRESSURE	
METRIC (kPa)	ENGLISH (psi)
10	1.5
210	30
280	40
350	50
690	100
860	125
1040	150
1100	160
1210	175
1380	200
1730	250
2070	300
2170	315
2410	350
2590	375
2760	400
4830	700
5170	750
5520	800
13800	2000
17200	2500
20700	3000
27600	4000
34500	5000
137900	20000

CONVERSION TABLE FOR MIL THICKNESS	
METRIC (mm)	ENGLISH (inch/1000)
0.10	4
0.13	5
0.15	6
0.50	20
0.75	30
1.00	40

CONVERSION TABLE FOR HVAC DUCTING.	
METRIC (mm)	ENGLISH (inch)
100	4
125	5
150	6
175	7
200	8
225	9
250	10
300	12
360	14
410	16
460	18
510	20
560	22
610	24
660	26
710	28
760	30

CONVERSION TABLE FOR MECHANICAL PIPING		
METRIC (GSP, PVC, BSP, DUCTILE IRON)	METRIC (mm)	ENGLISH (inch)
NPS 1/2	15	1/2
NPS 3/4	20	3/4
NPS 1	25	1
NPS 1 1/4	32	1 1/4
NPS 1 1/2	40	1 1/2
NPS 2	50	2
NPS 2 1/2	65	2 1/2
NPS 3	75	3
NPS 4	100	4
NPS 6	150	6

CONVERSION TABLE FOR LUBRICATION PIPING TUBING WALL THICKNESS	
METRIC (mm)	ENGLISH (inch)
2.1	0.083
0.9	0.035

CONVERSION TABLE FOR HOSE/TUBING SIZES O. D.	
METRIC (mm)	ENGLISH (inch)
6	1/4
10	3/8
13	1/2
16	5/8
19	3/4
22	7/8
25	1

CONVERSION TABLE FOR DRUM SIZES			
METRIC		ENGLISH	
L	kg	gallons	pounds
205	180	55	400
60	55	16	120
19	16	5	35

CONVERSION TABLE FOR POWER	
METRIC (kW)	ENGLISH (HP)
0.037	1/20
0.075	1/10
0.18	1/4
0.25	1/3
0.37	1/2
0.55	3/4
0.75	1
1.1	1 1/2
1.5	2
2.2	3
3.7	5
5.5	7 1/2
7.5	10
11	15
15	20
18.5	25
22	30
30	40
37	50
45	60
55	75
75	100
90	120
110	150

CONVERSION TABLE FOR IMPELLER BALANCE		
SYNCHRONOUS RPM	METRIC (g mm/kg)	ENGLISH (ounce- inch/pound)
720	94	0.059
900	73	0.046
1200	54	0.034
1800	41	0.026
3600	17	0.011

CONVERSION TABLE FOR ELECTRICAL CONDUIT	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
16	1/2
21	3/4
27	1
35	1 1/4
41	1 1/2
53	2
103	4

DIVISION 2. SITEWORK

2.01 EARTHWORK FOR BUILDING WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of structure excavation and structure backfill. Structure excavation shall include excavation for footings, foundations, walls, slabs, tanks, drywells, manholes, oil/water separators, clarifiers, and trenches. Structure backfill shall include backfilling under slabs; backfilling under and around footings; backfilling for walls, backfilling for pipes and conduits; backfilling holes resulting from removal of existing facilities. In addition to structure excavation and structure backfill, earthwork for building work shall include any other earthwork, not mentioned, but necessary to complete the building work.

Attention is directed to the requirements of "Field Engineering" in Division 1, "General Requirements," of these special provisions.

QUALITY ASSURANCE.--

Samples.--Samples of sand, pea gravel, or crushed stone, weighing not less than 11 kg, shall be submitted to the Engineer at the jobsite for approval.

SITE CONDITIONS.--

Existing underground piping and conduit.--The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 1.5 meters, or, if no elevations are indicated and the piping or conduit is more than 0.9 meter below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as an ordered change in accordance with the requirements specified in Section 3, "Changes in the Work," of the General Conditions.

Existing surfaced or planted areas.--Existing surfaced or planted areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein.

Restoration materials shall be equal to or better than the original materials. Surfacing shall be replaced to match the material thickness, grades, and finish of the adjacent surrounding surfaces.

PART 2.- PRODUCTS

BACKFILL MATERIALS.--

Structure backfill.--

Structure and trench backfill shall be free of organic and other deleterious material and shall be suitable for the required compaction. Gravel without sand matrix shall not be used except as free draining granular material beneath slabs and footings.

Select backfill.--

Select backfill shall conform to the requirements specified under "Aggregate Base," elsewhere in this Division 2.

Sand.--

Sand shall be clean, washed sand, free from clay or organic material graded such that 100 percent passes the 6 mm sieve, 90 percent to 100 percent passes the 4.75 mm sieve and not more than 5 percent passes the 75 μ m sieve size.

Pea gravel (naturally rounded).--

Pea gravel (naturally rounded) shall be clean, washed, dry density of not less than 1522 kg/m³, free from clay or organic material and shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
19 mm	100
13 mm	90-100
9.5 mm	40-70
4.75 mm	0-15
2.36 mm	0-3

Pea gravel shall conform to the following requirements:

Test	California Test No.	Test Requirements
Durability Index	229	35 Min.

Crushed stone.--

Crushed stone shall be clean, washed, dry density of not less than 1522 kg/m³, crushed stone or crushed gravel with an angular particle size not less than 3 mm or more than 13 mm.

Sieve or Screen Size	Percentage Passing
13 mm	100
9.5 mm	85-100
4.75 mm	10-30
2.36 mm	0-3

Crushed stone shall conform to the following requirements:

Test	California Test No.	Test Requirements
Durability Index	229	35 Min.

PART 3.- EXECUTION

PREPARATION & RESTORATION.--

Sawcutting.--Prior to excavation or trenching, existing surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than 25 mm.

Restoration.--Surfacing shall be replaced to match the thickness, grades and finish of the adjacent surrounding surfaces.

STRUCTURE EXCAVATION.--

General.--Unless otherwise noted, all excavation for building work shall be classified as structure excavation.

Footing excavation.--The bottom of excavations shall not be disturbed. The contractor shall excavate by hand to the final grade. The bottom of concrete footings shall be poured against undisturbed material. Unless otherwise noted, compaction of the bottom of footing excavation is not required unless the material is disturbed. The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as an ordered change in accordance with the requirements in Section 3, "Changes in the Work," of the General Conditions.

Excavate to the elevations and dimensions within a tolerance of ± 12 mm. Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

At locations and to the limits shown on the plans, material below the bottom of the foundation or footing shall be removed and replaced with select backfill in accordance with the placing and compacting requirements for backfill.

Excavation for pipes and conduits.--Pipes or conduits in the same trench shall have a minimum clear distance between pipes or conduits of 150 mm. Pipes or conduits shall have not less than 0.75 meter of cover from top of pipes or conduits to finished grade unless otherwise shown on the plans or specified.

Trenching shall be of sufficient depth to permit placing a minimum depth of 100 mm of compacted sand under all pipes and conduits.

Excavation adjacent to trees shall be performed by hand methods where necessary to avoid injury to trees and roots. Roots 50 mm in diameter and larger shall be protected with heavy burlap. Roots smaller than 50 mm in diameter adjacent to trees shall be hand trimmed. Cuts through roots 13 mm in diameter and larger shall be sealed with tree trimmers' asphaltic emulsion. If trenches remain open more than 24 hours, the side of the trench adjacent to the tree shall be shaded with burlap and kept damp. Materials shall not be stockpiled within the drip line of trees.

Dewatering.--Excavations shall be kept clear of standing water. Water shall be removed by pumping if necessary. Water removed from excavation shall be carried away from the building site and disposed of in a manner that will not harm State or adjacent property.

STRUCTURE BACKFILLING.--

Contract No. 07-4H9104

General.--Unless otherwise noted, all backfill for building work shall be classified as structure backfill. Backfill shall be placed and compacted in horizontal layers, not more than 150 mm thick prior to compaction, and to the lines and grades shown on the plans or to original ground.

Structure backfill.--After structures are in place and forms are removed, wood and other debris shall be removed from excavations before placing structure backfill.

Select backfill.--At the locations and to the limits shown on the plans, materials below the bottom of footings or foundations shall be removed and replaced with select backfill material in accordance with the placing requirements of structure backfill.

Backfilling pipes and conduits.--Backfill placed under pipe and conduits shall be compacted sand, 100 mm minimum depth. Backfill material placed to a level 150 mm above tops of pipes and conduits shall be sand or fine earth and particles shall not exceed 13 mm in greatest dimension. For wrapped, coated, or plastic pipe or conduits, sand shall be used for backfill. Backfill material placed higher than 150 mm above tops of pipes or conduits shall consist of material free of stones or lumps exceeding 100 mm in greatest dimension except:

- (a) The top 300 mm of backfill under roads, walks or paving shall consist of aggregate base material.
- (b) The top 150 mm of backfill in planted areas shall consist of topsoil.

Unless otherwise shown on the plans, pipe under roads, with less than 0.75 m of cover over the top of pipe, shall be backfilled with concrete to a level 100 mm above the top of pipe. Concrete for backfill shall be commercial quality concrete containing not less than 350 kg/m³ of cement.

COMPACTION.--

General.--Relative compaction shall be determined in accordance with California Test 216 or 231.

Unless otherwise noted below, all backfill shall be compacted to a minimum relative compaction of 90 percent.

Unless approved in writing by the Engineer, compaction by jetting or ponding will not be permitted.

Compact original ground.--Original ground surface under fill with surfacing of concrete and asphalt concrete shall be compacted to a relative compaction of not less than 95 percent for a minimum depth of 150 mm.

Subgrade preparation.--Preparation of subgrade material for placing aggregate base, surfacing, or slabs thereon shall include fine grading, compaction, reworking as necessary. The upper 150 mm of the subgrade shall have the same compaction as the fill to be placed over it.

The prism of backfill directly underneath the building foundation and sloping downward at 1:1 shall be compacted to 95 percent.

Structure backfill.--Structure backfill shall be compacted to not less than 95 percent relative compaction.

Select backfill.--Select backfill shall be compacted to not less than 95 percent relative compaction.

A relative compaction of not less than 95 percent shall be obtained for a minimum depth of 150 mm below the bottom of the excavation before placing select backfill.

Trench backfill.--Trench backfill placed beneath slabs or paved areas shall be compacted to a relative compaction of not less than 95 percent.

DISPOSAL.--

Surplus material.--Surplus material from the excavation shall be disposed of away from the premises.

FIELD QUALITY CONTROL.--

Inspection.--When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

Testing.--The State will conduct compaction tests during the backfilling and compacting operations.

2.02 AGGREGATE BASE

PART 1.-GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, spreading and compacting aggregate base in accordance with the details shown on the plans and these special provisions.

PART 2.-PRODUCTS

Aggregate base.--

Aggregate base shall be commercial quality aggregates consisting of broken stone; crushed gravel; natural, clean, rough-surfaced gravel and sand; or a combination thereof.

Aggregate base shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
25 mm	100
19 mm	90 - 100
4.75 mm	35 - 60
600 µm	10 - 30
75 µm	2 - 9

Aggregate base shall also conform to the following quality requirements:

Tests	California Test No.	Test Requirements
Durability Index	229	35 Min.
Resistance (R-Value)	301	78 Min.
Sand Equivalent	217	22 Min.

PART 3.-EXECUTION

SPREADING AND COMPACTING.--

Spreading.--Aggregate base shall be placed and compacted to the lines and grades shown on the plans.

Spreading and compacting shall be performed by methods that will produce a uniform base, free from pockets of coarse or fine material.

Compaction.--Relative compaction of each layer of compacted base material shall be not less than 95 percent, as determined by California Test 216 or 231.

2.03 GUARD POSTS

PART 1.- GENERAL

Scope.--This work shall consist of constructing steel guard posts in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Steel posts.--

Steel posts for guard posts shall be ASTM Designation: A 53/A 53M, standard weight (Schedule 80), unless another weight is indicated. .

Concrete.--

Concrete for guard posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--The length and diameter of the guard posts shall conform to the details shown on the plans.

Guard posts shall be placed in holes excavated to the depth and cross section shown on the plans, and shall be installed plumb.

Guard posts shall be anchored in place with concrete footings. Guard posts shall be centered and aligned in holes 75 mm above bottom of excavation. Concrete shall be placed and vibrated or tamped for consolidation. Guard posts shall be supported and braced in position until concrete has cured.

Guard posts shall be filled solidly with concrete, mounding top surface to shed water.

Painting.--Guard posts shall be prepared, primed and painted with:

2 prime coats: red oxide ferrous metal primer

2 finish coats: alkyd, exterior enamel, semi-gloss

Color shall be as indicated on the plans.

DIVISION 3. THRU 4. (NOT USED)

DIVISION 5. METALS

5.01 BUILDING MISCELLANEOUS METAL

PART 1.- GENERAL

Scope.--This work consists of fabricating, furnishing and installing building miscellaneous metal in accordance with the details shown on the plans and these special provisions.

Including but not limited to the following: Steel ramp, stair, platform, handrail, and guardrail with screening including all anchors, fastenings, hardware, accessories and other supplementary parts necessary to complete the work.

REFERENCES.--

Codes and standards.--Welding of steel shall be in accordance with American Welding Society (AWS) D 1.1, "Structural Welding Code-Steel" and D 1.3, "Structural Welding Code-Sheet Steel."

SUBMITTALS.--

Product data.--Submit manufacturer's specifications, anchor details and installation instructions for products used in miscellaneous metal fabrications.

Shop drawings.--Shop drawings of fabricated items shall be submitted for approval.

QUALITY ASSURANCE.--

Shop assembly.--Preassemble items in shop to the greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark all units for reassembly and installation.

Inspection and tests.--Materials and fabrication procedures shall be subject to inspection and tests by the Engineer, in mill, shop and field. Such tests will not relieve the Contractor of responsibility of providing materials and fabrication procedures in compliance with specified requirements.

PART 2.- PRODUCTS

MATERIALS.--

Steel bars, plates and hot-rolled shapes.--

Steel bars, plates and hot-rolled shapes shall conform to ASTM Designation: A 36/A 36M.

Galvanized sheet steel.--

Galvanized sheet steel shall conform to ASTM Designation: A 446M having a minimum yield strength of 228 MPa. Galvanizing shall be G60.

Checkered floor plates shall be commercial quality steel with standard raised pattern.

Pipe.--

Pipe shall be commercial quality standard steel pipe.

Steel tubing.--

Steel tubing shall conform to ASTM Designation: A 500, Grade B, or A 501.

Bolts, studs, threaded rods, nuts and washers.--

Bolts, studs, threaded rods, and nuts for general application shall conform to ASTM Designation: A 307. Washers shall be commercial quality.

Fittings.--

Brackets, bolt, threaded studs, nuts, washers, and other fittings for railings and handrailings shall be commercial quality pipe and fittings.

Expansion anchors.--

Expansion anchors shall be ICBO approved for the purpose intended, integral stud type anchor or internally threaded type with independent stud, hex nut and washer.

Powder driven anchors.--

Powder driven anchors shall be plated, spring steel alloy drive pin or threaded stud type anchors for use in concrete or steel. Spring steel shall conform to ASTM Designation: A 227M, Class 1. The diameter, length and type of shank and the number and type of washer shall be as recommended by the manufacturer for the types and thickness of material being anchored or fastened.

Resin capsule anchors.--

Stud anchors for resin capsule anchors shall conform to ASTM Designation: A 307 threaded steel rod with hex nut and washer and sealed glass capsule or cartridge containing an adhesive composed of unsaturated polyester resin and benzol peroxide coated quartz sand. Resin capsule shall be Hilti; Molly; or equal.

Mortar.--

Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

FABRICATION.--

Workmanship and finish.--Workmanship and finish shall be equal to the best general practice in modern shops.

Miscellaneous metal shall be clean and free from loose mill scale, flake rust and rust pitting, and shall be well formed and finished to shape and size with sharp lines and angles. Bends from shearing or punching shall be straightened.

The thickness of metal and details of assembly and support shall give ample strength and stiffness.

Built-up parts shall be true to line and without sharp bends, twists and kinks. Exposed ends and edges of metal shall be milled or ground smooth, with corners slightly rounded.

Joints exposed to the weather shall be made up to exclude water.

Galvanizing.--Items indicated on the plans to be galvanized shall be hot-dip galvanized after fabrication. The weight of galvanized coating shall be at least 460 grams per square meter of surface area, except drainage grates shall have at least 610 grams per square meter of surface area.

Painting.--Building miscellaneous metal items not galvanized shall be cleaned and prime painted prior to erection in accordance with the requirements specified for steel and other ferrous metals under "Painting" in Division 9, "Finishes," of these special provisions.

Loose bearing and leveling plates.--Loose bearing and leveling plates shall be furnished for steel items bearing on masonry or concrete construction, made flat, free from warps or twists, and of required thickness and bearing area. Plates shall be drilled to receive anchor bolts. Galvanize after fabrication.

Steel pipe railings and handrailings.--Pipe handrailing shall consist of handrailing elements supported by metal brackets (wall type) or handrailing elements supported by tubular steel posts (post type).

Ends of railing pipe shall be closed, except for a 3 mm diameter weep hole at the low point.

All corners on railings shall be rounded. Simple and compound curves shall be formed by bending pipe in jigs to produce uniform curvature; maintain cylindrical cross-section of pipe throughout the bend without buckling, twisting or otherwise deforming exposed surfaces of the pipe.

Wall brackets, end closures, flanges, miscellaneous fitting and anchors shall be provided for interconnections of pipe and attachment of railings and handrails to other work. Inserts and other anchorage devices shall be furnished for connecting railings and handrails to concrete or masonry.

Steel railing shall be galvanized after fabrication. After galvanizing, all elements of the railing shall be free of fins, abrasions, rough or sharp edges, and other surface defects and shall not be kinked, twisted or bent.

PART 3.- EXECUTION

GENERAL.--

Anchorage.--Anchorage devices and fasteners shall be provided for securing miscellaneous metal in-place construction; including threaded fasteners for concrete and masonry inserts, toggle bolts, through bolts, lag bolts, wood screws and other connectors.

Cutting, drilling and fitting shall be performed as required for installation of miscellaneous metal fabrications. Work is to set accurately in location, alignment and elevation, plumb, level, true and free of rack, measured from established lines and levels.

Loose leveling and bearing plates.--Plates shall be set on wedges or other adjustable devices. Anchor bolts shall be wrench tightened after the plates have been positioned and plumbed. Mortar shall be packed solidly between bearing surfaces and plates to ensure that no voids remain.

Steel pipe railings and handrailings.--Railings shall be adjusted prior to anchoring to ensure matching alignment at abutting joints. Secure posts and railing ends to building construction as shown on the plans.

Powder driven anchors.--Powder driven anchors shall be installed with low velocity powder actuated equipment in accordance with the manufacturer's instructions and State and Federal OSHA regulations.

Resin capsule anchors.--Resin capsule anchors shall be installed in accordance with the manufacturer's instructions.

DAMAGED SURFACES.--

General.--Galvanized surfaces that are abraded or damaged at any time after the application of the zinc coating shall be repaired by thoroughly wire brushing the damaged areas and removing all loose and cracked coating, after which the clean areas shall be painted with 2 applications of unthinned zinc-rich primer (organic vehicle type). Aerosol cans shall not be used.

DIVISION 13. SPECIAL CONSTRUCTION

13.01 MODULAR BUILDING

PART 1. GENERAL

Scope.—This work, in general consists of fabricating, transporting and installing commercial quality prefabricated modular buildings complete with finishes, mechanical, electrical, equipment, casework, and appliances. Modular buildings shall be furnished and installed in accordance with the details shown on the plans and these special provisions.

Related sections.—

Mechanical and plumbing systems shall conform to the requirements specified in Division 15 "Mechanical."

Electrical systems shall conform to the requirements specified in Division 16 "Electrical."

DEFINITIONS.--

Manufacturer.—A company regularly engaged in the design, factory fabrication, transport, and field assembly of modular building systems. In this section of the specifications, the term manufacturer and Contractor have been used synonymously.

SYSTEM DESCRIPTION.--

General.—The modular building system shall be a product of a recognized modular buildings manufacturer. Modular buildings shall have vertical walls and slope roofs. Roof slope shall be as indicated. Building dimensions of the units shall be standard with the manufacturer and not less than those indicated, but exceeding the indicated dimensions only by the amount of the closest standard size thereto. Each module shall be physically joined in the plant to ensure unit connections result in flush interior and exterior surfaces to receive finishes. Modules shall be braced and transported in a stand-up position meeting DOT safety code requirements for commercial coaches. Modules shall be designed with a minimum amount of interconnecting elements for accurate and easy field assembly at the Work site. The modules shall form a complete useable facility, including utilities hook-up, free from materials or workmanship defects.

Design requirements.—

General.—Methods shall conform to the California Building Standards Code (1998 edition) and applicable codes relating to Fire, Safety, Electrical, and Mechanical as they apply to the requirements of this project.

Occupancy	B Office
Construction Type	V-N
Sprinklers	None

Roof Live Loads	146.5 Kg/M ²
Floor Live Loads	610.3 Kg/M ²
Wind Load	128.75 K/Hour, Exposure C
Seismic Zone	4

SUBMITTALS.—

Shop drawings.—Shop drawings shall be submitted for approval in accordance with the General Requirements. Shop drawings shall consist of catalog cuts, design and erection drawings, shop painting and finishing specifications, instruction manuals, and other data as necessary to clearly describe design, materials, sizes, layouts, construction details, fasteners, erection, and anchoring. For all modules designs, except those programmed on a computer, the shop drawings shall be accompanied by engineering design calculations for structural and covering components. For computer programmed designs, shop drawings shall be accompanied by stress values and a certificate, signed by a registered Civil or Structural Engineer registered in the State of California, stating the design criteria and procedures have been used and attesting to the adequacy and accuracy of the design. The Engineer's original signature shall be submitted with expiration date of the registration

Contract No. 07-4H9104

shown. Copies will not be accepted.

Shop drawings shall have plan check approvals for fire safety, and building code compliance.

Color samples.—Standard color pallets for all interior finish materials and exterior cladding shall be submitted for approval to the Architect per shop submittal procedure.

Qualification Data.—The Contractor shall submit modular building manufacturer's qualifications to demonstrate their capabilities and experience. A list shall be included of completed projects with project names and addresses of architects and owners.

Closeout submittals.—The Contractor shall submit two complete packages of the building O&M instructions for appliances, mechanical and electrical equipment, including warranties and guaranties to the Engineer prior to acceptance of the contract.

QUALITY ASSURANCE.—

Qualifications.—Modules shall be the product of a recognized modular building manufacturer with a minimum of five years experience in the fabrication and erection of modular units comparable to the modules in this project and with a record of successful in-service performance.

The modular building manufacturer shall be a member of the Modular Building Institute (MBI).

Regulatory requirements.-- Each module shall meet design and performance requirements for intended use, fabrication, transportation, and installation. The standards listed below shall form a part of this specification to the extent they apply to the contract work:

California Health and Safety Code; Division 13, Part 2.

California Code of Regulations; Department of Housing and Community Development's regulations in Title 25, Chapter 3.

Americans with Disabilities Act 1990; reference latest edition of Americans with Disabilities Act Accessibility Guidelines (ADAGG).

California Building Standards Code (1998 CBSC).

California Department of Transportation Regulations; California Vehicle Codes for transport of commercial coaches.

Inspections.-- The modular building shall be made available for inspection in the plant by the Engineer during all stages of fabrication prior to delivery to the site.

DELIVERY, STORAGE, AND HANDLING

General.—Materials shall be delivered to the site in a dry and undamaged condition and stored out of contact with the ground.

WARRANTY.—The Contractor shall furnish the membrane sheet manufacturer's 5 year warranty for the modular building system, including structural elements, exterior cladding, flashings, and finishes defects caused by poor workmanship. The warranty shall run directly to the Department.

The warranty shall state that: When within the warranty period the modular building system becomes non-watertight, splits, tears, or separates at the seams because of defective materials and workmanship, the repair or replacement of defective materials and correction of defective workmanship shall be the responsibility of the building manufacturer; When the manufacturer or the manufacturer's approved applicator fail to perform repairs within 72 hours of notification, emergency repairs performed by others will not void the warranty. Damage to the modular building system caused by sustained winds having a velocity of 90 kilometers per hour or less is covered by the warranty.

PROJECT/SITE CONDITIONS

Existing conditions.—The modules shall be set on existing level asphalt paving. The Contractor shall coordinate installation of modules with the requirements of the required utilities work, fixed deck, and State operations of the Weigh Station in section "Cooperation" in Division 1, "General Requirements."

Weather Limitations.—Installation shall proceed only when weather conditions permit roof and wall panel installation to be performed according to manufacturer's written instructions and warranty requirements.

0.

Field Measurements.—The Contractor shall verify modular building system foundations by field measurements before fabrication and indicate measurements on shop drawings.

PART 2. PRODUCTS.--

BUILDING COMPONENTS.—

General.—The size and weight of the modular units shall permit easy handling in the field; and the maximum size and weight of any component shall be suitable for transportation by commercial carrier. Building shall be pre-assembled. Where a duplication of items exists between the manufacturer's standard items and these special provisions, the item of higher quality shall be furnished. See below for approved manufacturers.

Manufacturers.--

1. Pacific Mobile Offices
2. Mobile Modular Management Corporation
3. Meehleis Modular Buildings, Inc.
4. G.E. Capital Modular Space
5. Approved equal.

Framing and Structural members.--

General.--

Steel.—Steel 3 mm or more in thickness shall conform to ASTM Designation A 36, A 572, or A 588. Uncoated steel less than 3 mm in thickness shall conform to ASTM Designation A 570, A606, or A 607. Galvanized steel shall conform to ASTM Designation A 446, G 90 coating 0.045 minimum thickness. Shop connections for steel shall conform to AISC publication, "Specification for the Design, Fabrication, and Erection of Structural Steel for Buildings," or the AISI publication, "Specification for the Design of Cold-Formed Steel," as applicable. Erection bolts and anchor bolts shall be of standard sizes and types. Holes for the bolts shall be made in the shop, prior to assembly of structural members in the field.

Framing lumber.—Lumber shall be manufactured to comply with PS 20, "American Softwood Lumber Standard," and with applicable grading rules of inspection. Softwood lumber shall be quality grade stamped or shall be accompanied by a certificate of inspection. Inspection certificates or grade stamps shall indicate compliance with the grading requirements of WWSA, WCLIB, RIS, or other approved lumber inspection agencies. All lumber used shall be nominal sized and dressed S4S unless otherwise specified in these special provisions. Framing lumber shall be solid stock lumber, Douglas Fir-Larch, and the grades indicated under WCLIB or WWSA rules. Moisture content shall not exceed 19 percent and shall be grade stamped "S-Dry."

Framing system.—The following structural framing requirements shall be integrated into the modular building design and may be exceeded with higher quality materials at the option of the manufacturer at no additional cost to the Department:

Floor.—All steel welded construction for the specified loadings.

Sub-floor.—30 mm tongue and groove OSB screwed to steel floor joists.

Exterior walls.—2 x 6 wood construction for the specified loadings.

Interior walls.—2 x 4 wood construction for the specified loadings.

Roof framing.—3/12 slope with 2 x 8 wood construction for the specified loadings.

Wall and roof sheathing.--

Roof sheathing.—Sheathing shall meet design and building code requirements.

Exterior wall sheathing.—Sheathing shall meet design and building code requirements.

Roof covering and wall covering.—Base metal shall be cold formed, 0.71 mm (24-gage), galvanized sheet steel conforming to ASTM Designation: A 653/A 653M, Grade 33 [230] with G90 [Z275] coating, except where a higher strength is required for performance, extra smooth; or cold formed aluminum-zinc alloy-coated, commercial quality, sheet steel conforming to ASTM Designation: A 792/A 792M, Grade 40 [275] with AZ55 [AZM 165], coating extra smooth. Metal roofing and siding system shall be a standing seam system with standing seams a minimum of 45 mm high and spaced not less than 305 mm nor more than 455 mm on center.

Finish shall be the manufacturer's standard Kynar coating with a baked on primer (0.005 mm) and a finish coat of 0.02 mm nominal for a total dry film thickness of approximately 0.025 mm nominal.

Accessories.—Flashings, trim, metal closure strips, caps, and similar metal accessories shall be not less than the minimum thickness specified for covering. Accessories shall be compatible with the system furnished. Exposed metal accessories shall have factory finish to match the building finish. Molded closure strips shall be bituminous-saturated fiber, closed-cell or synthetic rubber or neoprene, or polyvinyl chloride pre-molded to match configuration of the covering and shall not absorb or retain water.

Fasteners.—Fasteners for wall and roof panels shall be zinc-coated steel, aluminum, corrosion resisting steel, or nylon capped steel, type and size as required to meet performance requirements. Fasteners for accessories shall be manufacturer's standard. Aluminum or corrosion resisting steel fasteners shall be used only with aluminum sheets. Exposed roof fasteners shall be gasketed or have gasketed washers on the exterior side of the covering to waterproof the fastener penetration. Washer material shall be compatible with the covering; have a minimum diameter of 10 mm for structural connections; equally durable elastomeric material approximately 3 mm thick. When wall covering is factory color finished, exposed wall fasteners shall be color finished or provided with plastic color caps to match covering. Non-penetrating fastener system using concealed clips shall be the manufacturer's standard for the system provided.

Doors.—

Exterior doors.—Frames shall be hollow metal 16 gauge steel, fully mitered and welded with sufficient wall and floor anchorage for commercial use. Frames shall be shop primed and then painted. Door construction shall be 18 gauge galvanized steel with zinc coating, flush with no face seams; SDI Grade III, extra heavy duty with 16 gauge steel end channels spot welded in place and reinforced for surface mounted door closures, lock assemblies, and hinges. Door panels shall be reinforced, stiffened, and insulated. Door panels shall be shop primed and then painted. Exterior shall be constructed with vision panels with wire glass. The Contractor shall provide locksets, deadbolts, hinges and door closures, weather stripping, and any necessary weather protective hardware necessary for a weather tight installation. Exterior door size shall be .915 x 2030 x 44 mm. Provide heavy duty screen doors at exterior door locations. Exterior door thresholds shall be equipped with ADA and BHMA certified saddle strips.

Interior doors.—Frames shall be hollow metal, fully mitered and welded with sufficient wall and floor anchorage for commercial use. Frames shall be shop primed and then painted. Door construction shall be solid core flush panel, paint grade. The Contractor shall provide cylindrical lever set/privacy locks except as otherwise noted on the plans. Interior door size shall be .915 x 2030 x 44 mm.

Exterior windows.—windows shall be commercial grade aluminum frame horizontal sliding with anodized finish and integral insect screen. Glazing shall be double pane with Low-E coating. Unless otherwise noted, window size shall be 1525 mm W 1065 mm H.

INSULATION.—

General.—As a minimum, THE Contractor shall provide and install building insulation for the following:

Exterior walls: R-19 resistance rating

Floor: R-19 resistance rating

Roof: R-30 resistance rating

Interior walls: R-11 resistance rating

FINISHES.--

Wall and ceiling finishes.--

Walls.--Unless otherwise indicated, all interior walls shall be 16 mm vinyl faced gypsum board conforming to ASTM Designation: C 36/C 36M. Restrooms, and shower room, shall be finished with water-resistant gypsum backing board substrate (ASTM Designation: C 630/C 630M) and full height 3 mm fiber reinforced plastic panels (FRP).

Ceilings.--

Acoustical panels.--Acoustical panels shall be factory produced, lay-in panels, 610 mm x 1219 mm x 16 mm thick with non-directional natural fissured surface texture and factory applied, off-white, vinyl latex finish. Panels shall conform to ASTM E 1264 Type III, form 2. Noise Reduction Coefficient (NRC) shall be minimum 0.65. Panels shall have a flame spread rating not exceeding 25. Restroom panels shall be washable.

Suspension system.--Suspension system shall be galvanized steel, tee shaped main runners and cross runners and wall molding angles or channels conforming to ASTM Designation: C 635, intermediate duty or heavy duty. Runners shall have exposed flanges approximately one inch wide and positive interlocks between main runners and cross runners. Wall moldings shall have a 19 mm wide exposed face. Runners and moldings shall be bonderized and shall have a flat off-white color, factory painted finish unless otherwise indicated. Assembly devices, splices, intersection connectors and expansion devices shall be as recommended by the suspension system manufacturer. The ceiling shall be leveled to within 3 mm in 3.6 m.

Flooring.--

Offices.--Offices (3 rooms) shall be carpet with pad. Padding shall conform to requirements of CCC Class III, extra-heavy traffic. Carpet shall be third generation nylon, continuous filament yarn with a woven polypropylene backing. Yarn shall be solution dyed. Carpet constructions shall be textured loop, 3 mm gage minimum, pile height shall be between 4 mm and 6 mm with a yarn weight of not less than 950 g/m². Carpet shall be permanently anti-static.

All other rooms, including Training Room, Lunch Room, Restrooms and Shower Room.--Flooring shall be sheet vinyl floor covering with fibrous backing conforming with ASTM Designation: F 1303. Thickness shall be a minimum of 2.4 mm. Sheet vinyl shall be "No Wax," and installed with cove base in restroom and shower room locations.

Base.--Unless otherwise indicated, floor base shall be 4 inch rubber base.

Exterior entrance.--The Contractor shall provide and install outdoor carpet at connector entry.

CASEWORK.--

Laminate clad cabinets.--Cabinets shall be manufactured and installed in accordance with the Manual of Millwork of the Woodwork Institute of California (WIC) requirements for custom grade. Laminate clad cabinets shall be custom grade, flush overlay construction. Laminate cladding shall be high pressure decorative laminate complying with NEMA LD 3. Horizontal and vertical surfaces other than tops shall conform to GP-50 (1.27 mm nominal thickness). Post-formed surfaces shall conform to PF-42 (1.07 mm nominal thickness). Exposed face framing to be solid stock custom quality hardwood. Doors and drawer faces to be solid stock custom quality hardwood frames with 6 mm custom quality hardwood inset panels. Hardware shall be heavy duty chrome self-closing hinges, metal pulls and metal sliding drawer mechanisms. Finish for exposed wood and plywood shall be 2 coats of clear water based satin polyurethane over one application of sanding sealer. Countertops shall have integral rolled front edges and integral 4" high, rolled back splashes. Provide 18 inches of clearance between top of base cabinet and bottom of wall cabinet.

ACCESSORIES.--

Window covering.--Window covering shall be metal horizontal mini-blinds for all windows.

FIXTURES/EQUIPMENT.--

General.—Unless otherwise indicated, kitchen and bathroom fixtures shall be selected from the modular building manufacturer's standard products for commercial use. Fixtures and hardware shall be designed and installed to conform to ADA requirements. Materials composition and finish shall be stainless steel. Fixtures shall be surface mounted with sufficient backing.

Mop holder	heavy gage stainless steel, 3 heads, spring loaded
Robe hooks	4 each, 1370 mm AFF
Fold-down bench	Hardwood, located in changing room
Toilet Partitions	Enamel steel
Toilet paper holders, soap dispensers, combination paper towel dispensers/receptacles,	As required to meet minimum code requirements
Grab bars	As required to meet minimum code requirements
Bathroom lavatories	porcelain, to be set in 1830 mm long counter top
Water closets	White porcelain, tank type (See Mechanical Section, Div 15)
Mirrors	1525 mm L, centered over lavatories
Plumbing Fixtures	See Division 15, "Mechanical"
Locker room wood benches	factory fabricated hardwood laminated seats, with steel pedestal assembly, secured to floor and bench
Shower room steel lockers	460 mm W x 610 mm D x 1830 mm H, sloped top, standard factory fabricated steel units with metal base, hat shelf, rod, door vents, and non-breakable handle with provision for a padlock, gray enamel

KITCHEN APPLIANCES.--

General.—The modular building manufacturer shall provide and install kitchen appliances in locations indicated. Place units in final locations after finishes have been completed in each area. The Contractor shall verify that clearances are adequate to properly operate equipment.

Electric range	760 mm freestanding electric range with four-burner cooktop and oven with broiler, listed by UL; self cleaning with broiler function, white porcelain-enamel finish. Manufacturers shall be Hot Point; Magic Chef; GE, or equal.
Exhaust hood	Wall-mounted, under cabinet exhaust hood, listed by UL, 4-speed with integral light, removable stainless steel filters, quiet fan system. Finish shall be white porcelain-enamel.
Upright refrigerator	Free standing, side-by-side, 2 door, no frost type, UL listed, 120-volt AC, single phase, 60 HZ, with freezer compartment and automatic ice maker, and 2 vegetable/fruit pans, nominal 0.59 cubic meter capacity, 3 interior shelves with 2 adjustable, door shelves, polystyrene inner cabinet liner. Manufacturers shall be GE; Hot Point; Amana, or equal. Finish shall be white enamel.
Garbage disposal	0.37kW

MISCELLANEOUS MATERIALS.--

Fire extinguishers.—The Contractor shall provide and install surface mounted fire extinguishers as required by code, located as shown on plans. Rating shall be UL Listed, 1A; 10BC; C.

Signage.—Signage shall be provided by the manufacturer as indicated on the plans.

Perimeter skirt.—The foundation skirt shall be 4.8 mm thick cementitious hard board, or equal. Skirting shall come with a 20 year warranty. Where skirting and siding meet, a weather tight, continuous, galvanized metal closure piece shall be provided. All required framing for skirting shall be made from hot-dipped galvanized metal shapes, either welded together or mechanically fastened using galvanized attachments. Two metal access panels shall be provided; one into each half of the building.

Smoke detectors.—The manufacturer shall provide and install standard smoke detectors in compliance with the building code.

PART 3. EXECUTION.--

EXAMINATION.—The Contractor shall examine the building site and make all necessary preparations necessary to set the modules in place prior to delivery to the site.

DELIVERY AND INSTALLATION.—A certified trailer mover shall transport the modules to the site. Moving permits from the State Department of Housing and Community Development shall be obtained and submitted to the Engineer in advance. Installation of the modular building shall be in strict accordance with manufacturer's printed installation instructions. Coordination shall be made with access and use of the project site as specified in Division 1, "General Requirements," of these Special Provisions.

The temporary hitch and wheel/axle assemblies shall remain the property of the State.

FIELD QUALITY CONTROL.—The Manufacturer shall provide a field services representative/s to oversight delivery, structural erection, and finish work in the field.

DEMONSTRATION.—Upon completion of mechanical work and pre-test requirements, or at such time prior to completion as determined by the Engineer, the Contractor shall operate and test installed mechanical systems for at least 3 consecutive 8-hour days to demonstrate satisfactory overall operation.

DIVISION 14. (NOT USED)
DIVISION 15. MECHANICAL

15.01 MECHANICAL WORK

GENERAL.--

Scope.--This work shall consist of performing mechanical work in accordance with the details shown on the plans and these special provisions.

Mechanical work shall include furnishing all labor, materials, equipment and services required for providing heating, ventilating, air conditioning, and plumbing distribution systems.

Earthwork, foundations, sheet metal, painting, electrical, and such other work incidental and necessary to the proper installation and operation of the mechanical work shall be in accordance with the requirements specified for similar type work elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of pipes, ducts, etc., and location of equipment is to be governed by structural conditions and obstructions. Equipment requiring maintenance and inspection is to be readily accessible.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for plumbing fixtures, and component layout shall be included where applicable.

Manufacturer's descriptive data shall be submitted for the following:

- Heat Pump
- Back-up Heat
- Exhaust Fan

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Operation and maintenance manuals shall be submitted for the following equipment:

- Heat Pump
- Back-up Heat
- Exhaust Fan

QUALITY ASSURANCE.--

Codes and standards.--Mechanical work, including equipment, materials and installation, shall conform to the California Building Standards Code, Title 24, and to the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS).

WARRANTY.--

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

15.02 PIPE, FITTINGS AND VALVES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing pipes, fittings and valves in accordance with the details shown on the plans and these special provisions. Pipe, fittings and valves shall include such plumbing and piping accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the plumbing and piping systems.

All piping insulation and associated material shall be in accordance with the requirements specified under "Mechanical Insulation," elsewhere in this Division 15.

The pipe sizes shown on the plans are nominal pipe size. No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

The pipe and fitting classes and material descriptions shall be as specified herein. No change in class or description shall be permitted without written permission from the Engineer.

QUALITY ASSURANCE.--

Codes and standards.--Pipe, fittings and valves shall be installed in accordance with the requirements in the latest edition of the Uniform Plumbing Code, the manufacturer's recommendations and the requirements specified herein.

PART 2.- PRODUCTS

MATERIALS.--

PIPE AND FITTINGS --

Class	Description
--------------	--------------------

A1.--

Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with 1040 kPa galvanized malleable iron banded screwed fittings and galvanized steel couplings. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

A2.--

Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with black cast iron recessed drainage fittings. For rainwater leaders, neoprene-gasket compression couplings, Smith Blair, Dresser, or equal, may be used. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

C1.--

Hub and plain end cast iron soil pipe with neoprene gaskets conforming to Cast Iron Soil Pipe Institute's Standard 301. Pipe, fittings and gaskets shall be of one manufacturer.

C2.--

Hubless cast iron soil pipe with neoprene gaskets, corrugated stainless steel shields and stainless steel clamps conforming to Cast Iron Soil Pipe Institute's Standard 301. Joint materials shall be furnished by pipe manufacturer.

H1.--

Type DWV hard copper tubing conforming to ASTM Designation: B 306, with DWV drainage fittings, stop type couplings and threaded adapters.

H3.--

Type L hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

P1.--

Polyvinyl chloride (PVC) gravity sewer plastic pipe and fittings conforming to ASTM Designation: D 3034, Standard Dimension Ratio (SDR) 35, with integral bell and bell and spigot rubber gasketed joints or conforming to ASTM Designation: D2665 with solvent welded fittings. Rubber gaskets shall conform to ASTM Designation: F 477. Stainless steel clamps with rubber boots shall not be used.

P2.--

Polyvinyl chloride (PVC) plastic pipe and fittings conforming to ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa working pressure at 23°C, National Sanitation Foundation approved. Pipe shall have bell ends conforming to ASTM Designation: D 3139 with triple edge rubber sealing ring. For pipe sizes 50 mm diameter and smaller, plain end pipe with solvent welded fittings ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa may be used.

P3.--

Polyvinyl chloride (PVC) standard weight pipe and fittings, Schedule 40, conforming to ASTM Designation: D 1785. Pipe shall meet or exceed requirements of National Sanitation Foundation Standard No. 14. Pipe shall have bell ends conforming to ASTM Designation: D 2672. For pipe sizes 75 mm and smaller, plain end pipe with solvent welded fittings conforming to ASTM Designation: D 2241, may be used.

Unions (for steel pipe).--

Unions (for steel pipe) shall be 1730 kPa, threaded malleable iron, ground joint, brass to iron seat, galvanized or black to match piping.

Unions (for copper or brass pipe).--

Unions (for copper or brass pipe) shall be 1040 kPa cast bronze, ground joint, bronze to bronze seat with silver brazing threadless ends or 860 kPa cast brass, ground joint, brass to brass seat with threaded ends.

Insulating union.--

Insulating union or flange as applicable shall be suitable for the service on which used. Connections shall be constructed such that the 2 pipes being connected are completely insulated from each other with no metal to metal contact. Insulating couplings shall not be used. Insulating union shall be F. H. Maloney; Central Plastics; EPCO; or equal.

Insulating connection (to hot water tanks).--

Insulating connection (to hot water tanks) shall be 150 mm minimum, flexible copper tubing with dielectric union at each end and designed to withstand a pressure of 1040 kPa and a temperature of 93°C.

VALVES.--

Ball valve.--

Ball valve shall be two piece, minimum 2760 kPa WOG, bronze body and chrome plated or brass ball with full size port.

FAUCET AND HYDRANTS.--

Hose faucet.--

Hose faucet shall be compression type, angle pattern, wall flange at exterior locations, tee handle, 20 mm female thread with hose end, rough chrome or nickel plated finish for locations inside building, rough brass finish for others. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Nibco, No. 63VB; Chicago, No. 13T; or equal.

CLEANOUTS.--

Cleanout to grade.--

Cleanout to grade shall be cast iron ferrule type. Plug shall be countersunk brass or bronze with tapered threads.

MISCELLANEOUS ITEMS.--

Water hammer arrestor.--

Water hammer arrestor shall be stainless steel body with bellows or piston. Arrestor compression chambers shall be pneumatically charged. Water hammer arrestors shall be tested and certified in accordance with the Plumbing and Drainage Institute Standard: PDI-WH201 and sized as shown on the plans.

Access door.--

Access door shall be 1.52 mm prime coated steel, face mounting square frame, minimum 300 mm x 300 mm door with concealed hinge and screwdriver latch.

Compression stop (exposed).--

Compression stop (exposed) shall be metal full free waterway, angle type, ground joint union, non-rising stem, molded rubber seat and wheel handle.

Pipe wrapping tape and primer.--

Pipe wrapping tape shall be pressure sensitive polyvinyl chloride or pressure sensitive polyethylene tape having nominal thickness of 0.50 mm.

Pipe wrapping primer shall be compatible with the pipe wrapping tape used.

Floor, wall, and ceiling plates.--

Floor, wall, and ceiling plates shall be chromium plated steel or plastic plates having screw or spring clamping devices and concealed hinges. Plates shall be sized to completely cover the hole.

Valve box.--

Valve box shall be precast high density concrete with polyethylene face and cast iron traffic rated cover marked "WATER," "GAS" or "CO-SS" as applicable. Extension shall be provided as required. Valve box shall be Christy, B3; Brooks Products Company, 3TL; Frazer, 3; or equal.

PART 3.- EXECUTION**INSTALLATION.--****INSTALLATION OF PIPES AND FITTINGS.--**

Pipe and fittings.--Pipe and fittings shall be installed in accordance with the following designated uses:

Designated Use	Pipe and Fitting Class
Domestic water (CW and HW) in buildings	H3
Domestic water underground within 1.5 m of the building	A1 or H2
Domestic water underground 1.5 m beyond the building	P2, P3, P4, A1 or H2
Sanitary drain piping above ground in building	H1, C1, or C2
Sanitary drain and vent piping underground within 1.5 m of the building	C1 or C2
Sanitary vent piping above ground in building	A2, H1, C1, or C2
Sanitary drain pipe, 1.5 m beyond the building	C1, C2, or P1

Installing piping.--Water piping shall be installed generally level, free of traps and bends, and arranged to conform to the building requirements.

Piping installed underground shall be tested as specified elsewhere in these special provisions before backfilling.

Public use areas, offices, rest rooms, locker rooms, crew rooms, training rooms, storage rooms in office areas, hallway type rooms, and similar type use areas shall have concealed piping.

Where pipes pass through exterior walls, a clear space around pipe shall be provided. Space shall be caulked water tight with silicone caulk.

Underground copper pipe shall have brazed joints. Underground plastic pipe shall be buried with No. 14 solid bare copper wire. Wire ends at pipe ends shall be brought up 200 mm and looped around pipe.

Exposed supply and drain piping in rest rooms shall be chrome finished.

Forty-five degree bends shall be used where offsets are required in venting. Vent pipe headers shall be sloped to eliminate any water or condensation.

Vent piping shall extend a minimum of 200 mm above the roof.

Horizontal sanitary sewer pipe inside buildings shall be installed on a uniform grade of not less than 2 percent unless shown otherwise on the plans.

Drainage pipe shall be run as straight as possible and shall have easy bends with long turns.

Cutting pipe.--All pipe shall be cut straight and true and the ends shall be reamed to the full inside diameter of the pipe after cutting.

Damaged pipe.--Pipe that is cracked, bent or otherwise damaged shall be removed from the work.

Pipe joints and connections.--Joints in threaded steel pipe shall be made with teflon tape or a pipe joint compound that is nonhardening and noncorrosive, placed on the pipe and not in the fittings.

The use of thread cement or caulking on threaded joints will not be permitted. Threaded joints shall be made tight. Long screw or other packed joints will not be permitted. Any leaky joints shall be remade with new material.

Exposed polished or enameled connections to fixtures or equipment shall be made with special care, showing no tool marks or threads.

Cleaning and closing pipe.--The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Securing pipe.--Pipe in the buildings shall be held in place by iron hangers, supports, pipe rests, anchors, sway braces, guides or other special hangers. Material for hangers and supports shall be compatible with the piping or neoprene isolators shall be used. Allowances shall be made for expansion and contraction. Steel pipe shall have hangers or supports every 3 m. Copper pipe 25 mm or smaller shall have hangers or supports every 2 m and sizes larger than 25 mm shall have hangers or supports every 3 m. Plastic pipe shall have hangers or supports every 1 m. Cast iron soil pipe with neoprene gaskets shall be supported at each joint. Vertical pipes shall be supported with clamps or straps. Horizontal and vertical piping shall be securely supported and braced to prevent swaying, sagging or flexing of joints.

Wrapping and coating steel pipe.--Steel pipe buried in the ground shall be wrapped or shall be plastic coated as specified herein:

1. Wrapped steel pipe shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
2. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids with approved wrapping machines and experienced operators to provide not less than 1.00 mm thickness.
3. Plastic coating on steel pipe shall be factory applied. Coating imperfections and damage shall be repaired to the satisfaction of the Engineer.
4. Field joints, fittings and valves for wrapped and plastic coated steel pipe shall be covered to provide continuous protection by puttying and double wrapping with 0.50 mm thick tape. Wrapping at joints shall extend a minimum of 150 mm over the adjacent pipe covering. Width of tape for wrapping fittings shall not exceed 50 mm. Adequate tension shall be applied so tape will conform closely to contours of fittings. Putty tape insulation compounds approved by the Engineer shall be used to fill voids and provide a smooth even surface for the application of the tape wrap.

Wrapped or coated pipe, fittings, and filed joints shall be approved by the Engineer after assembly. Piping shall be placed on temporary blocks to allow for inspection. Deficiencies shall be repaired to the satisfaction of the Engineer before backfilling or closing in.

Thrust blocks.--Thrust blocks shall be formed by pouring concrete between pipe and trench wall. Thrust blocks shall be sized and so placed as to take all thrusts created by maximum internal water pressure.

Plastic pipe underground shall be provided with thrust blocks and clamps at changes in direction of piping, connections or branches from mains 50 mm and larger, and all capped connections.

Union.--Unions shall be installed where shown and at each threaded or soldered connection to equipment and tanks. Unions shall be located so piping can be easily disconnected for removal of equipment or tanks. Unions shall be omitted at compression stops.

Insulating union and insulating connection.--Insulating union and insulating connection shall be provided where shown and at the following locations:

1. In metallic water, service connections into each. Insulating connections shall be installed on the exterior of the building, above ground and after shut-off valve.
2. At points of connections of copper or steel water pipes to steel domestic water heaters .

Bonding at insulating connections.--Interior water piping and other interior piping that may be electrically energized and are connected with insulating connections shall be bonded in accordance with the California Electrical Code. Bonding shall all be coordinated with electrical work.

Compression stop.--Each fixture, including hose faucets, shall be equipped with a compression stop installed on water supply pipes to permit repairs without shutting off water mains. Ball valves may be installed where shown on the plans or otherwise permitted by the Engineer.

INSTALLATION OF VALVES.--

Exterior valves.--Exterior valves located underground shall be installed in a valve box marked "Water." Extensions shall be provided as required.

INSTALLATION OF FAUCET.--

Hose faucet .--Faucet shall be installed with outlets 0.5 m above finished grade.

INSTALLATION OF CLEANOUTS.--

Cleanouts.--A concrete pad 0.5 m long and 100 mm thick shall be placed across the full width of trench under cleanout Wye or 1/8 bend. Cast iron soil pipe (C1 or C2) and fittings shall be used from Wye to surface. Required clearance around cleanouts shall be maintained.

Cleanout risers outside of a building installed in a surface other than concrete shall terminate in a cleanout to grade. Cleanout to grade shall terminate in a valve box with cover marked "CO-SS". Top of box shall be set flush with finished grade. Cleanout plug shall be 100 mm below grade and shall be located in the box to provide sufficient room for rodding.

INSTALLATION OF MISCELLANEOUS ITEMS.--

Water hammer arrestor.--Water hammer arrestor shall be installed so that they are vertical and accessible for replacement. Water hammer arrestor shall be installed with access door when in walls or there is no access to ceiling crawl spaces. Access door location shall be where shown on the plans or as approved by the Engineer.

Flushing completed systems.--All completed systems shall be flushed and blown out.

Chlorination.--The Contractor shall flush and chlorinate all domestic water piping and fixtures.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping at completion of roughing in, before backfilling, and at other times as directed by the Engineer.

The system shall be tested as a single unit, or in sections as approved by the Engineer. The Contractor shall furnish necessary materials, test pumps, instruments and labor and notify the Engineer at least 3 working days in advance of testing. After testing, the Contractor shall repair all leaks and retest to determine that leaks have been stopped. Surplus water shall be disposed of after testing as directed by the Engineer.

The Contractor shall take precautions to prevent joints from drawing while pipes and appurtenances are being tested. The Contractor shall repair damage to pipes and appurtenances or to other structures resulting from or caused by tests.

General tests.--All piping shall be tested after assembly and prior to backfill, pipe wrapping, connecting fixtures, wrapping joints and covering the pipe. Systems shall show no loss in pressure or visible leaks.

The Contractor shall test systems according to the following schedule for a period of not less than 4 hours:

Test Schedule		
Piping System	Test Pressure	Test Media
Sanitary sewer and vent	3.0 m head	Water
Water	860 kPa	Water

During testing of water systems, valves shall be closed and pipeline filled with water. Provisions shall be made for release of air.

Sanitary sewers shall be cleared of obstructions before testing for leakage. The pipe shall be proved clear of obstructions by pulling an appropriate size inflatable plug through the pipe. The plug shall be moved slowly through the pipe with a tag line. The Contractor shall remove or repair any obstructions or irregularities.

Sanitary sewer pipes beyond 1.5 m perpendicular to the building shall be tested for leakage for a period of not less than 4 hours by filling with water to an elevation of 1.2 m above average invert of sewer or to top of manholes where less than 1.2 m deep. The system shall show no visible leaks. The sewer may be tested in sections with testing water progressively passed down the sewer as feasible. Water shall be released at a rate that will not create water hammer or surge in plugged sections of sewer.

15.03 MECHANICAL INSULATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing mechanical insulation in accordance with the details shown on the plans and these special provisions.

Piping insulation shall be installed on all domestic hot water piping, above grade, in non-conditioned spaces.

P-trap, hot water supply pipes and angle valves for lavatories and sinks, except in janitor closets or similar enclosed spaces, shall be insulated.

Duct insulation shall be installed on all rigid ductwork installed in concealed non-conditioned spaces.

Duct liner shall be installed in all rectangular ductwork installed in exposed non-conditioned spaces and in exterior locations.

QUALITY ASSURANCE.--

Codes and standards.--Mechanical insulation shall conform to California State Energy Commission regulations and, where applicable, shall meet American Society of Testing and Materials (ASTM) standards.

All materials shall bear the label of the Underwriters Laboratory (UL) or other approved testing laboratory indicating that the materials proposed for use conform to the required fire hazard ratings.

Pipe safety insulation shall conform to Section 1504(b) of Title 24, Part 5, California Plumbing Code.

PART 2.- PRODUCTS

MATERIAL.--

General.--All pipe insulation and wrapping material, including adhesives and jackets, located within buildings shall be certified to have a composite flame spread rating of not more than 25 and smoke development rating of not more than 450 when tested in accordance with ASTM Designation: E 84.

Duct insulation and wrapping material, including adhesives and jackets, located within buildings shall be certified to have a composite flame spread of not more than 25 and smoke development rating of not more than 50 when tested in accordance with ASTM Designation: E 84.

PVC jacket.--

PCV jacket shall be rated for a service temperature of 80°C. PVC jacket shall include covers specifically designed to cover pipe fittings.

Alternative pipe insulation.--

Alternative pipe insulation shall be closed cell, elastomeric material in a flexible tubular form. Insulation shall have a service temperature range between -40°C and 93°C, a minimum vapor transmission rating of 0.29 Perm-m, and a minimum thermal resistance of $R-0.5 \text{ K}\cdot\text{m}^2/\text{W}$.

Pipe safety insulation.--

Pipe safety insulation for P-traps, hot water supply pipes and angle valves shall be molded closed cell vinyl or closed cell foam with exterior vinyl surface. Pipe safety insulation shall be configured to protect against contact.

External duct insulation.--

External duct insulation shall be 38 mm thick, 0.5 kg density glass-fiber blanket type. Material and coatings shall be fire resistive and shall be approved by the State Fire Marshal. External duct insulation shall be Fiberglas, Type PF-336; Ultralite, No. 100; Pittsburgh Plate Glass, Superfine; Johns-Manville, Microlite; Silvercote, Silvercel; or equal.

PART 3.- EXECUTION

INSTALLATION.--

General.--Insulation materials shall be neatly installed with smooth and even surfaces, jackets drawn tight and smoothly cemented down.

Insulation material shall not be installed until all pipes or surfaces to be covered are tested for leaks, cleaned and dried, and foreign materials, such as rust, have been removed.

Piping insulation.--Piping insulation shall be in accordance with the following, except that unions, unless integral with valves, and flexible connections shall not be insulated.

- a. Where insulation butts against flanges or is discontinued, insulation shall be tapered to pipe to allow for covering jacket to completely seal off end of insulation.

Insulation shall be extended on the valve bodies up to the valve bonnet.

Extend insulation continuous through pipe hangers and pipe sleeves. At hangers where pipe is supported, provide an insulated protection shield.

- b. Jacket flap shall be sealed down with factory applied self-sealing lap. Seams shall be lapped not less than 40 mm. Jacket shall be secured with aluminum bands installed at 300 mm centers.

Alternate pipe insulation, where used, shall be installed on hot water piping before connections are made or the insulation may be slit lengthwise, applied to pipe and sealed with adhesive.

Pipe safety insulation.--Pipe safety insulation shall be installed in accordance with the manufacturer's recommendations.

Duct insulation.--Ragged edges shall be repaired or taped. Coverings shall be neatly finished at joints and edges. Each joint shall have a 50 mm minimum lap.

Where transitions are made between externally covered ducts and lined ducts, the lined duct shall be overlapped 200 mm with external covering.

Insulation shall be flush with but not cover control devices, damper controls or access doors.

Before insulation is wrapped around concealed ducts, an adhesive shall be spot applied at a maximum of 100 mm centers on each side of the ducts to prevent sagging of the insulation. Insulation shall be wrapped entirely around the ducts and shall be wired securely in place with No. 16 copper clad wire, metal bands at least 10 mm wide or plastic ties. Supports shall be spaced a maximum of 300 mm on centers. Metal bands shall be installed with the use of a banding machine. Seams in the insulation shall be taped.

The finished insulation covering shall be even and level and shall not contain humps.

15.04 PLUMBING FIXTURES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing plumbing fixtures in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

General.--Plumbing fixtures shall be white in color and shall meet the following requirements:

Water closet seat.--

Water closet seat for disabled access shall be white colored, solid plastic, open front, 50 mm high seat assembly, elongated type and equipped with check hinges that support seat in open position. Double seat is not acceptable.

Urinal (disabled accessible).--

Urinal shall be vitreous china, wall hung, siphon jet or washout, top spud, integral shields, spreader and trap, with 380 mm maximum extension from wall. Urinal and valve shall meet Americans with Disabilities Accessibility Act Guidelines (ADAAG) Flush Valve shall be Exposed, diaphragm type, chrome plated, with oscillating handle, integral control stop, adjustable tail piece and vacuum breaker suitable for use with top spud urinals:-

Lavatory (counter mounted).--

Lavatory shall be self-rimming vitreous china, integral perforated grid drain, drilled for 102 mm centers, nominal bowl size 254 mm x 457 mm, with single extra long lever mixing faucet. Lavatory shall be equipped with temperature controls to limit the hot water supply to 43°C. Lavatory shall be equipped with a flow limiting device that limits the flow rate of hot water to no more than 2 liters per minute. Trap shall be 32 mm chromium plated brass exposed bent tube adjustable 1.37 mm (17-gage) minimum thickness-

Mop sink.--**Kitchen sink.—**

Kitchen sink shall be double compartment, self rimming, 18 gauge, type 304 nickel bearing stainless steel, 3 4 – hole, 100 mm center faucet stainless steel seamlessly drawn, strainer, Satin finish with standard 38 mm drain, High rise faucet assembly,

Water heater (electric).--

Water heater shall be minimum capacity as shown on plans, designed for minimum 860 kPa, interlocking (non-simultaneous) or single element, glass lined, and equipped with magnesium anodes, cold water drop tube, high temperature energy shut-off device, valved drain, high density $R-1.4 \text{ K} \cdot \text{m}^2/\text{W}$ minimum foam insulation and finished with a steel jacket with baked enamel finish. Water heater shall meet the requirements of the California Energy Commission.

Water heater shall be equipped with an ASME labeled, tank mounted, pressure and temperature relief valve sized for maximum input.

PART 3.- EXECUTION**INSTALLATION.--**

General.--All finish for exposed metal on any fixture, including wall flanges, bolts, nuts and washer, shall be polished chrome plated.

Fixtures shall be sealed to wall or floor with silicone caulk bead.

All exposed metal surfaces on fixture supports shall be enameled to harmonize with fixtures.

Wall mounted fixtures shall be installed on concealed chair carriers designed to support weight of fixture from the floor, made for the specific fixture to be supported and for the particular installation conditions.

All fixtures, including showers, shall be provided with accessible metal stop valves.

Hot water supply, trap and tailpiece on lavatories shall be wrapped with insulating material.

Flush valves for fixtures designated on the plans as disabled accessible shall be installed so that the valve handle is on

the widest side of the toilet space.

FIXTURE MOUNTING HEIGHTS.--

General.--Unless otherwise noted, fixtures shall be mounted at the heights shown on the plans.

Mop sink.--Mop sink double faucet shall be mounted on wall above sink back with spout outlet face one meter above the floor.

Water heater.--Water heater shall be installed with seismic restraints, inlet ball valve and insulating connections, and 20 mm pressure and temperature relief drain pipe.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping in accordance with the requirements specified elsewhere in these special provisions.

All installed fixtures shall be tested for proper operation after all plumbing work has been completed.

15.05 WHEELCHAIR ACCESSIBLE SHOWER UNIT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing a wheelchair accessible shower unit and fittings in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, installation instructions and color palette shall be submitted for approval. The color will be selected from the manufacturer's standard product line by the Engineer after approval of the contract.

QUALITY ASSURANCE.--

Codes and standards.--Shower units shall conform to the requirements of the California State Accessibility Standards contained in the California Building Standards Code, Title 24.

PART 2.- PRODUCTS

Shower stall.--

Shower stall shall be single unit, single piece construction with clear interior dimensions of 1065 mm wide, 1220 mm deep, with an entrance width of 915 mm, and no obstruction at the threshold. Shower stall shall be fabricated from gel-coated fiberglass or acrylic with a Class I Flame Spread. Shower unit shall be reinforced to accommodate the grab bars and seat.

Shower unit shall have a threshold or recessed drop, a maximum of 13 mm in height, sloped at an angle not exceeding 45 degrees from the horizontal. The floor shall be slip-resistant, sloping a maximum of 4 percent to a drain located near the rear wall.

Shower unit shall be provided with the following fittings and accessories: stainless steel corner grab bar and folding teakwood or woodgrain phenolic wheelchair transfer seat, each capable of resisting 1112 N of lateral, vertical and tensile load, stainless steel soap dish, chromium plated or stainless steel curtain rod, chromium plated steel hand-held shower head with ball joint, chromium plated 1525 mm long flexible shower spray hose, chromium plated fixed shower head, chromium plated metal outlet drain with removable strainer, chromium plated single lever control thermostatic mixing valve with control cartridge with no metal to metal wearing surface, a lever operated shower head selector, and vinyl shower curtain with corrosion resistant hooks.

PART 3.- EXECUTION

INSTALLATION.--

General.--Shower shall be installed with the manufacturer's instructions. All joints shall be sealed and caulked watertight.

15.06 HEATING, VENTILATING AND AIR CONDITIONING EQUIPMENT AND SYSTEMS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing, installing and testing heating, ventilating and air conditioning (HVAC) equipment and systems in accordance with the details shown on the plans and these special provisions.

The performance rating and electric service of the HVAC equipment shall be as shown on the plans.

Temperature controls.--Thermostats, and other sensor type control devices required for this work shall be furnished and installed by the supplier of the heating, ventilating and air conditioning equipment. All temperature control wiring shall be furnished and installed in accordance with the requirements specified in Division 16, "Electrical," of these special provisions.

Codes and standards.--Equipment and systems shall conform to California State Energy Commission Regulations and, where applicable, shall be American Refrigeration Institute (ARI), American Gas Association (AGA), Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA), and Air Movement and Control Association (AMCA) approved for performance ratings and application shown on the plans.

Any appliance for which there is a California standard established in the Appliance Efficiency Standards may be installed only if the manufacturer has certified to the Commission, as specified in those regulations, that the appliance complies with the applicable standards for that appliance. Space conditioning equipment may be installed only if the manufacturer has certified that the equipment meets or exceeds all applicable efficiency requirements listed in the Energy Efficiency Standards.

PART 2.- PRODUCTS

HEATING AND COOLING UNITS.--

Combination heating/cooling unit Heat pump ().--

Combination heating/cooling unit Heat pump shall be standard, commercial quality, single package, wall mounted unit with weatherproof acoustically lined cabinet. The cabinet shall have convenient access panels and a baked-on enamel finish. The roof curb shall be insulated and shall be supplied by the unit manufacturer.

Unit shall be specially designed for continuous compressor operation in the heating mode and shall be protected by a suction-tube accumulator.

Motors shall have integral thermal overload protection.

Electric resistance heater shall be supplied by the heat pump manufacturer, factory installed and shall be pre-wired for convenient hookup.

FANS AND VENTILATORS.--

Exhaust fan (ceiling mounted).--

Exhaust fan shall be ceiling mounted, AMCA certified and shall be equipped with grille, backdraft damper and metal housing. Exhaust fan motor shall have integral thermal overload protection.

HVAC CONTROLS.--

Thermostat (office only).--

Thermostat shall be 24-volt, 7-day programmable, multi-stage, 3-stage heat/2-stage cool, heat pump thermostat. Thermostat shall be auto-changeover type, and have full temperature range setback capacity.

AUXILIARY HVAC COMPONENTS.--

Unless specified herein, all components shall be sized and have the characteristics as shown on the plans.

Spiral duct.--

Spiral duct shall be prefabricated type.

Duct supports.--

Duct supports shall be hot-dip galvanized steel.

Flexible ductwork.--

Flexible ductwork shall be UL 181, Class 1 air duct rated and shall meet the requirements of NFPA 90-A. Duct shall have steel helix wire, flexible insulation, minimum thermal resistance of $R-0.7$ ($m^2 \cdot K/W$), and flame resistant vapor barrier. Inner and outer surfaces shall be non-metallic. Outer surface shall be Copolymer or Mylar, factory applied. (A maximum of 1500 mm at each diffuser and register.)

Flexible connection.--

Flexible connection shall be prefabricated type and shall be commercial quality flexible glass fabric coated on both sides with neoprene or hypalon.

Ceiling diffuser (for suspended ceilings).--

Ceiling diffuser for suspended ceilings shall be 610 mm square. Diffuser shall be steel with oven baked-on enamel bone white dull finish or extruded aluminum, perforated face hinged for easy access, and shall be fitted with fully adjustable air pattern controllers, a removable core, and a standard flanged frame.

Return register (for suspended ceilings).--

Return register for suspended ceilings shall be 610 mm square, steel or extruded aluminum, perforated face hinged for easy access.

Combination smoke and fire damper.--

Combination smoke and fire damper shall be approved or listed by the State Fire Marshal. Damper assembly shall be 1 1/2 hour fire rated under UL Standard 555 and be a Leakage Rated Damper for use in smoke control systems meeting the requirements of the latest version of UL 555S. Combination smoke and fire damper shall be equipped with a fusible link rated at 74°C, have a 115-volt shaded pole motor actuator and an approved smoke detector. Bearings shall be stainless steel sleeve turning in an extruded hole in the frame. Damper and actuator shall be supplied as a single entity which meets all applicable UL Standards. Damper shall have all galvanized steel parts. Damper shall be installed at the locations shown on the plans.

Balance damper.--

Balance damper shall be butterfly type, 1.52 mm (16-gage) minimum galvanized steel blade, end bearings with steel shaft and locking and indicator operator. Balance damper shall be Ventlock, Young, Anemostat, or equal.

Air filter (for HVAC units).--

Air filter shall be permanent metal viscous impingement type, constructed of aluminum or galvanized steel, 50 mm minimum thickness and be approved for Class 2 use. Filter shall have a minimum efficiency rating of 50 percent as determined when tested in accordance with ASHRAE Test Standard 52. Filter shall be mounted in 1.52 mm (16-gage) galvanized steel holding frames. Two cans of recharging adhesive shall be provided with the filter and shall be nearly odorless, have a high flash point, rapid wetting characteristics, dye tracer and be water soluble. Filter shall be Airspan, Type AF, Eco-Air Products, Inc., Type HIA; Snyder General, Type AAF; or approved equal.

Vents and flues (for heaters).--

Vents and flues for heaters shall be approved Type B or approved plastic vents for condensing furnaces.

Refrigerant and condensate drain piping.--

Refrigerant and condensate drain piping shall be rigid, Type L copper tubing with brazed solder fittings. The suction line shall be insulated, with vapor barrier and shall be weatherproofed for exterior installation. Factory sealed tubing shall not be used.

PART 3.- EXECUTION**INSTALLATION.--**

Ventilators--Exhaust ducts connected to exhaust fans shall be routed as shown on the plans and shall terminate in a weatherproof cap. Duct sizes shall be as recommended by the manufacturer.

Condensate drains.--Heat pumps shall be provided with condensate drain trap and piping. Air gap shall be installed where required by code. Interior condensate drain piping shall be insulated with foam insulation.

Mounting heights.--Thermostats and time switches shall be installed as shown on the plans.

Each thermostat shall be insulated from the outside walls, and shall be provided with an aluminum radiation shield above the thermostat.

Air outlets.--Volume dampers shall be furnished and installed for all diffusers. Blocking shall be provided on all sides of air outlets between ceiling or wall joists. Collars shall be supplied for all outlets and shall be taped and sealed in place.

Access door.--Access doors shall be provided in rigid ducts and plenums for access to volume dampers, fire dampers and control devices located within such ductwork; and shall be provided at such other locations as shown on the plans.

Ducts and vents.--Ductwork within the building shall be installed to clear lighting fixtures, doors, windows and other obstructions. Ductwork shall preserve head room and shall keep openings and passageways clear whether shown on plans or not.

Ductwork shall be installed and braced according to the latest edition of the SMACNA "HVAC Duct Construction Standards."

Slopes in sides at transitions shall be approximately one to five. The ductwork system shall not contain abrupt changes or offsets of any kind unless otherwise shown on the plans.

Where ducts pass through walls, floors or ceilings, galvanized sheet metal or steel angle collars shall be installed around the ducts.

Duct sections shall be connected by beaded sleeve-type couplings using joint sealer as recommended by the duct manufacturer. Duct sections shall be mechanically fastened with pop rivets or sheet metal screws and sealed with mastic or insulated, reinforced silver tape.

FIELD QUALITY CONTROL.--

Pre-test requirements.--Before starting or operating systems, equipment shall be cleaned and checked for proper installation, lubrication and servicing.

In each system, at least one air path, from fan to final outlet, shall have all balance dampers open. The final air quantities shall be achieved by adjusting the volume dampers or the fan RPM.

Final adjustments and balancing of the systems shall be performed in such a manner that the systems will operate as specified and as shown on the plans.

The Contractor shall replace or revise any equipment, systems or work found deficient during tests.

All automatic operating devices which are pertinent to the adjustment of the aforementioned air systems shall be set and adjusted to deliver the required quantities of air and at temperatures specified by the Engineer. All control work shall be done in collaboration with the control manufacturer's representative.

Project completion tests.--The Engineer shall be notified at least 3 working days in advance of starting project completion tests.

Upon completion of mechanical work and pre-test requirements, or at such time prior to completion as determined by the Engineer, the Contractor shall operate and test installed mechanical systems for at least 3 consecutive 8-hour days to demonstrate satisfactory overall operation.

The project completion tests shall consist of the following:

1. **Air Systems.**--All air systems shall be tested and balanced to the conditions set forth on the plans and in these special provisions. This work shall be performed by an Associated Air Balance Council (AABC) or National Environmental Balancing Bureau (NEBB) certified contractor. The air systems include, but are not necessarily limited to, the following:
 - a. Supply air systems
 - b. Return air systems
 - c. Exhaust air systems

DIVISION 16. ELECTRICAL

16.01 ELECTRICAL WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections for the thermostats, and controls specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related work.--Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

QUALITY ASSURANCE.--

Codes and standards.--All work performed and materials installed shall be in accordance with the National Electrical Code; the California Building Standards Code, Title 24, Part 3, "California Electrical Code," and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders," and all state ordinances.

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

TESTING.--

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

16.02 BASIC MATERIALS AND METHODS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval.. Any other data as requested by the Engineer shall also be submitted for approval.

PART 2.- PRODUCTS

CONDUITS AND FITTINGS.--

Rigid steel conduit and fittings.--

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

Electrical metallic tubing (EMT) and fittings.--

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, malleable iron nut and insulated plastic throat.

Flexible metallic conduit and fittings.--

Flexible metallic conduit shall be fabricated in continuous lengths from galvanized steel strip, spirally wound and formed to provide an interlocking design.

Fittings shall be electroplated screw-in type with malleable cast iron body and threaded male hub with insulated throat.

Liquid tight flexible metallic conduit and fittings.--

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

Rigid non-metallic conduit and fittings.--

Rigid non-metallic conduit shall be Schedule 40, high impact, nonconducting, self-extinguishing polyvinyl chloride (PVC) rigid non-metallic conduit for direct underground burial.

Couplings shall be PVC, socket type or thread on one end and socket type on the other end as required for the particular application.

Terminal adapters for adapting PVC conduit to boxes, threaded fittings, or metallic conduit system shall be PVC adapters with threads on one end and socket type on the other end.

CABLES AND CONDUCTORS.--

Cables.--

Cables shall be as required by the manufacturer of the equipment or as indicated on the plans.

Conductors.--

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors shall be type XHHW-2 in wet, underground, and outdoor locations.
2. Conductors shall be type THHN in dry locations.

Wire connections and devices.--

Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

ELECTRICAL BOXES.--

Outlet, device and junction boxes.--

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 100 mm square by 40 mm deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 50 mm by 75 mm by 40 mm deep.

Multiple switches shall be installed in standard gang boxes, unless otherwise specified or shown on the plans.

Cast metal boxes shall be cast iron boxes with threaded hubs and shall be of the size and configuration best suited to the application shown on the plans.

Flush-mounted boxes shall have stainless steel covers, one mm thick. Cover screws shall be metal with finish to match cover finish.

Unless otherwise shown or specified, surface-mounted boxes shall have galvanized steel covers with metal screws.

Weatherproof junction boxes shall have cast metal covers with gaskets.

Weatherproof switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

Sectional device plates will not be permitted.

Underground pull boxes.--

Pull boxes shall be high density reinforced concrete box with ultraviolet inhibitor polyethylene etched face anchored in concrete and fiberglass cover with hold down bolts. The polyethylene and fiberglass material shall be fire resistant and show no appreciable change in physical properties with exposure to the weather. No. 3 1/2 pull box shall be Brooks Products, No. 3 1/2; Christy Concrete Products, N9; or equal. No. 5 pull box shall be Brooks Products No. 5; Christy Concrete Products, N30; or equal.

RECEPTACLES AND SWITCHES.--

Ground fault circuit interrupter receptacles, (GFCI).--

Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-ampere, 125-volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

At lunchroom counter install three GFCI protected 115V duplex wall receptacles. Mount receptacles just above the back splash.

Duplex receptacles.--

Duplex receptacles shall be NEMA Type 5-20R, 3-wire, 20-ampere, 125-volt AC, safety grounding, ivory color, specification grade receptacle suitable for wiring with stranded conductors.

Install 115V duplex wall receptacles at 510 mm above the floor level, with spacing as required by code.

Snap switches.—

Snap switches shall be 20-ampere, 120/277-volt AC, quiet type, specification grade, ivory color switch with silver cadmium alloy contacts. Switch shall be suitable for wiring with stranded conductors.

MISCELLANEOUS MATERIALS.--

Warning Tape.--

Warning tape shall be 100 mm wide and contain the printed warning "CAUTION ELECTRICAL CONDUIT" in bold 19 mm black letters at 760 mm intervals on bright orange or yellow background. The printed warning shall be non-erasable when submerged under water and resistant to insects, acids, alkali, and other corrosive elements in the soil. The tape shall have a tensile strength of not less than 70 kg per 100 mm wide strip and shall have a minimum elongation of 700 percent before breaking.

Pull ropes.--

Pull ropes shall be nylon or polypropylene with a minimum tensile strength of 225 kg.

Watertight conduit plugs.--

Watertight conduit plugs shall be a hollow or solid stem expansion plugs complete with inner and outer white polypropylene compression plates and red thermoplastic rubber seal. Seal material shall be non-stick type rubber resistant to oils, salt, and alkaline substances normally available at the construction sites.

Anchorage devices.--

Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical supporting devices.--

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

Construction channel shall be 41 mm x 41 mm, 2.66 mm (12-gage) galvanized steel channel with 13 mm diameter bolt holes, 40 mm on center in the base of the channel.

Ground rod(s).--

Ground rod(s) shall be a 19 mm (minimum) galvanized or copper clad steel rod, 3 meters long.

Telephone/data outlet boxes.--

Telephone/data outlet boxes shall be 102 mm square boxes and plates with modular type telephone outlet. Boxes on stud walls shall have plaster ring.

Plates for flush mounting outlets in finished room shall be Type 430 stainless steel, one mm thick with satin finish.

Install three (3) telephone/data outlets in training room, two (2) telephone/data outlets in commander office, open office, and one telephone/data outlet in lunchroom. Install telephone cable (2-pair) and data cable (4-pair) between each outlet and telephone service box.

Telephone service box shall be installed in each module (except modules #4 and #5). In module #2 install one 53 mm conduit with pull rope between the telephone service box and LAN room.

Install one TV outlet in the east wall of training room of module #2. Install two coaxial cables type RG 59/U between TV outlet and LAN room.

PART 3.- EXECUTION**INSTALLATION.--**

Conduit, general.--Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, flexible metal conduit shall be used to connect suspended lighting fixtures, HVAC equipment, and other equipment subject to vibration in dry locations.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect HVAC equipment, and other equipment subject to vibration in wet locations.

Rigid non-metallic conduit shall be used at the locations shown on the plans for direct underground burial 762 mm below grade. All risers and elbows shall be rigid steel.

Conduit installation.--Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Conduits shall be tightly covered and well protected during construction using metallic bushings and bushing "pennies" to seal open ends.

Rigid non-metallic conduit bends of 30 degrees or greater shall be factory-made long radius sweeps. Bends less than 30 degrees shall be made using an approved heat box.

A pull rope shall be installed in all empty conduits. At least one meter of pull rope shall be doubled back into the conduit at each termination.

Locations of conduit runs shall be planned in advance of the installation and coordinated with the ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor block access to mechanical or electrical equipment.

Where practical, conduits shall be installed in groups in parallel, vertical or horizontal runs and at elevations that avoid unnecessary offsets.

Exposed conduit shall be installed parallel and at right angles to the building lines.

Conduits shall not be placed closer than 300 mm from a parallel hot water or steam pipe or 75 mm from such lines crossing perpendicular to the runs.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

Raceways of different types shall be joined using approved couplings or transition fittings.

Expansion couplings shall be installed where conduit crosses a building separation or expansion joint.

All floor and wall penetrations shall be sealed water-tight.

Conduit terminations.--Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

Warning Tape.--Warning tape shall be placed over each conduit in a trench. Each warning tape shall be centered over the conduit and shall be placed over the 150 mm layer of sand covering the conduit as described elsewhere in these special provisions.

Conductor and cable installation.--Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

All cables shall be installed and tested in accordance with manufacturer's recommendations.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 155 mm of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor identification.--The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

Ungrounded feeder and branch circuit conductors shall be color coded by continuously colored insulation, except conductors No. 6 AWG or larger may be color coded by colored tape at each connection and where accessible. Ungrounded conductor color coding shall be as follows:

SYSTEM	COLOR CODE
120/240V-Single phase	Black, blue

Once an insulated circuit conductor, including grounded and ungrounded conductors, is identified with a specific color code, that color code shall be used for the entire length of the circuit.

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers shown on the plans, approved shop drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, device and junction box installation.--Where exposed threaded steel conduits are connected to an outlet, device, or junction box below switch height, the box shall be a cast metal box. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

All boxes shall finish flush with building walls, ceiling and floors except where exposed work is called for.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Boxes in stud walls and partitions shall not be mounted back to back. Through-wall boxes shall not be used.

Fixture outlet boxes installed in suspended ceilings of gypsum board or lath and plaster construction shall be mounted on 1.52 mm (16-gage) metal channel bars attached to main ceiling runners.

Fixture outlet boxes for pendant-mounted fixtures installed in suspended ceilings supporting acoustical tiles or panels shall be supported directly from the structures above.

Underground pull box installation.--Electrical pull box covers or lids shall be marked "ELECTRICAL." Telephone service pull box covers or lids shall have plain, unmarked covers.

The bottom of pull boxes shall be bedded in 155 mm of clean, crushed rock or gravel and shall be grouted with 40 mm thick grout prior to installation of conductors. Grout shall be sloped to a 25 mm PVC pipe drain hole. Conduit shall be sealed in place with grout.

Top of pull boxes shall be flush with surrounding grade or top of curb. In unpaved areas where pull box is not immediately adjacent to and protected by a concrete foundation, pole or other protective construction, the top of pull box shall be set at plus 30 mm above surrounding grade. Pull boxes shown on the plans in the vicinity of curbs shall be placed adjacent to the back of curb. Pull boxes shown on the plans adjacent to lighting standards shall be placed on the side of foundation facing away from traffic.

Ground rod installation.--The ground rod(s) shall be driven vertically until the top is 155 mm above the surrounding surface. When vertical penetration of the ground rod cannot be obtained, an equivalent horizontal grounding system, approved by the Engineer, shall be installed.

Anchorage.--Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights.--Electrical system components shall be mounted at the following mounting heights, unless otherwise shown on the plans. The mounting height dimensions shall be measured above the finished floor to the bottom of the device or component.

Thermostats	1.1 m maximum, office areas 1.25 m maximum, hallways
Wall switches	1.0 m maximum
Convenience outlets	510 mm minimum, office areas 1.25 m minimum, all other areas
Electric water cooler outlet	As recommended by the water cooler manufacturer.
Telephone and radio outlets	510 mm minimum

16.03 SERVICE AND DISTRIBUTION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing service and distribution equipment in accordance with the requirements of the serving utilities, the details shown on the plans and these special provisions.

Attention is directed to "Utility Connection" in Division 1, "General Requirements," of these special provisions regarding arrangements, permits, licenses, charges, fees and costs for utility connections and extensions.

Attention is directed to "Utility Connection" in Section 12-1, "General Requirements," of these special provisions regarding arrangements, permits, licenses, charges, fees and costs for utility connections and extensions.

SUBMITTALS.--

Installation details.--The Contractor shall submit complete service installation details to the serving utilities for approval. Prior to submitting installation details to the serving utility, the Contractor shall have said drawings reviewed and stamped "APPROVED" by the Engineer. Submittals shall be approved by the serving utility prior to commencing work.

Product data.--A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval.. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

Service equipment.--

Service equipment shall contain a pull section, metering compartment and service disconnect switch for 120/240-volt, 200-ampere, 1-phase, 3-wire service.

Enclosure.--

Enclosure shall be NEMA 3R enclosure. Exterior shall be 2.66 mm (12-gage) and interior shall be 1.90 mm (14-gage) sheet steel. All screws, latches, hinge pins and similar hardware shall be stainless steel. Circuit breaker shall be operable with the exterior door open. Exterior door shall be lockable with a padlock. Enclosure finish shall be baked enamel or baked thermosetting polyester finish.

Contract No. 07-4H9104

Service disconnect switch.--

Service disconnect switch shall be 2-pole, 240-volt, 200-ampere frame, 200-ampere trip, molded case circuit breaker with AC magnetic trip adjusted to 600 amperes. The interrupting capacity of the circuit breaker shall be 22000 amperes (symmetrical) at 240-volt

PART 3.- EXECUTION

Installation of service and distribution equipment shall be in accordance with the requirements of the serving utilities as shown on the approved installation details.

16.04 ELECTRICAL EQUIPMENT**PART 1.- GENERAL****SUMMARY.--**

Scope.--This work shall consist of furnishing and installing panelboards, disconnect switches, and related accessories.

Related work.--Anchorage devices shall be as specified under "Basic Materials and Methods" elsewhere in this Division 16.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS**PANELBOARDS.--****Panelboard --**

Panelboard shall be factory assembled, 1-phase, 3-wire, 120/240-volt, AC panelboard at least 540 mm wide with 100-ampere main breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers. Install four (4) panelboards, one for each module #1 through #4. Panelboard shall have enough branch circuit breakers for the load required for the module plus six (6) spare spaces for future used.

SWITCHES.--**Air conditioner disconnect switch.--**

Air Conditioner Disconnect switch shall be 2-pole, 240-volt, AC, 60-ampere, fused, heavy duty safety switch in a NEMA-3R enclosure. The fuses shall be sized to suit the air conditioning unit furnished.

MISCELLANEOUS MATERIALS.--

Plywood backing board.--

Plywood backing board for mounting electrical or telephone equipment shall be 19 mm, APA plywood panels, C-D PLUGGED and touch-sanded, Exposure 1.

PART 3.- EXECUTION

INSTALLATION.--

Plywood backing board.--Plywood backing board shall be securely fastened to walls or other vertical framing.

Surface to be coated shall be cleaned of all dirt, excess materials, of filler by hand cleaning.

Plywood backing board exposed surfaces shall receive the following paint system: one prime coat, alkyd, interior wood primer and 2 finish coats, acrylic, interior enamel, semi-gloss. Color shall match surrounding surfaces, or shall be as directed by the Engineer.

Coatings shall be applied in accordance with the manufacturer's instructions. Each coat shall be applied to a uniform finish, free of skips, brush marks, laps or other imperfections.

Panelboard installation.--Set cabinets plumb and symmetrical with building lines. Train interior wiring as specified under "Conductor and Cable Installation" in "Basic Materials and Methods" of these special provisions. Touch-up paint any marks, blemishes, or other finish damage suffered during installation. Replace cabinets, doors or trim exhibiting dents, bends, warps or poor fit which may impede ready access, security or integrity.

Mounting height shall be 1.67 meters to the highest circuit breaker handle, measured above the finished floor.

Where "Future" or "Space" is indicated on the plans, branch connectors, mounting brackets, and other hardware shall be furnished and installed for future breaker.

A typewritten directory under transparent protective cover shall be provided and set in metal frame inside each cabinet door. Directory panel designation for each circuit breaker shall include complete information concerning equipment controlled, including room number or area designated on the plans.

Equipment identification.--Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

16.05 LIGHTING

GENERAL.--This work shall consist of furnishing, installing and connecting all lighting equipment in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive information, photometric curves, catalog cuts, and installation instructions shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

PRODUCTS.--

Lighting fixture lamps.--

Lighting fixture lamps shall be General Electric, Phillips, Sylvania, or equal. Fluorescent lamps, unless otherwise noted, shall be 4100K tri-phosphor with a CRI of 70 or greater.

Ballasts.--

All fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by the fixture. Fluorescent ballasts shall be UL Listed, Class P and ETL Certified ballasts with sound rating A. Fluorescent ballasts shall be high-frequency electronic ballasts with power factor greater than 0.95, nominal ballast factor of 0.88 unless specified otherwise, total harmonic distortion less than 20 percent, crest factor less than or equal to 1.7, complying with ANSI C 62.41 Category A for surge protection, and FCC Part 18 for interference.

Lighting fixtures.--

Lighting fixtures shall be 610 mm x 1220 mm, two 32-watt T8 lamp, electronic ballast, and lay-in fluorescent fixture with lamps. The lighting level for module #1, and #2 shall be 40 foot candle and for module #3, #4 and #5 shall be 20 foot candle, Outdoor luminaires shall be listed and labeled "Fixture Suitable For Wet Locations."

EXECUTION.--

LIGHTING FIXTURES.--Lighting fixtures shall be mounted securely in accordance with the manufacturer's recommendations. Mounting methods shall be suitable for the particular type of ceiling or support at each location.

The Contractor shall provide all supports, hangers, spacers, channels, fasteners and other hardware necessary to support the fixtures.