

**DEPARTMENT OF TRANSPORTATION**  
DIVISION OF ENGINEERING SERVICES  
OFFICE ENGINEER, MS 43  
1727 30<sup>TH</sup> STREET  
P.O. BOX 168041  
SACRAMENTO, CA 95816-8041  
FAX (916) 227-6214  
TTY 711



*Flex your power!  
Be energy efficient!*

July 27, 2009

12-Ora,Riv-91-15.9/18.9, 0.0/2.9  
12-OG0404  
ARRAL-P091(127)E

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN ORANGE AND RIVERSIDE COUNTIES IN ANAHEIM AND YORBA LINDA NEAR CORONA FROM 1.0 MILE EAST OF ROUTE 91/ 241 SEPARATION TO 0.8 MILE EAST OF ROUTE 91/71 SEPARATION AND IN CHINO HILL STATE PARK.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, July 30, 2009.

This addendum is being issued to revise the Notice to Bidders and Special Provisions, and the Bid book.

In the Special Provisions, Section 10-1.59, "ARCHITECTURAL TREATMENT (TEXTURED SHOTCRETE)," subsection "MEASUREMENT AND PAYMENT," the second paragraph is revised as follows:

"The contract price paid per square foot for architectural treatment (textured shotcrete) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying architectural treatment (textured shotcrete), including furnishing and placing shotcrete and bar reinforcing steel within the architectural section of the soil nail wall, complete in place, including test panels, layout of rock formations and shotcrete sculpting, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer."

In the Bid book, in the "Bid Item List," Items 62, 63, 65 and 66 are revised as attached.

To Bid book holders:

Replace the entire page 6 of the "Bid Item List" in the Bid book with the attached revised pages 6 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 3  
Page 2  
July 27, 2009

12-Ora,Riv-91-15.9/18.9, 0.0/2.9  
12-0G0404  
ARRAL-P091(127)E

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum is available for the Contractors' use on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/weekly\\_ads/addenda.php](http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addenda.php)**

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

**ORIGINAL SIGNED BY**

REBECCA D. HARNAGEL, Chief  
Office of Plans, Specifications & Estimates  
Division of Engineering Services - Office Engineer

Attachment

**BID ITEM LIST**  
**12-0G0404**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61 (F)	192020	STRUCTURE EXCAVATION (TYPE D)	CY	215		
62 (F)	192037	STRUCTURE EXCAVATION (RETAINING WALL)	CY	2,913		
63 (F)	192053	STRUCTURE EXCAVATION (TYPE Z-2) (AERIALY DEPOSITED LEAD)	CY	5,995		
64 (F)	192055	STRUCTURE EXCAVATION (SOIL NAIL WALL)	CY	8,145		
65 (F)	192057	STRUCTURE EXCAVATION (TYPE Y-1) (AERIALY DEPOSITED LEAD)	CY	1,189		
66 (F)	192058	STRUCTURE EXCAVATION (TYPE Y-2) (AERIALY DEPOSITED LEAD)	CY	3,761		
67 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	CY	1,770		
68 (F)	193013	STRUCTURE BACKFILL (RETAINING WALL)	CY	12,540		
69 (F)	193028	STRUCTURE BACKFILL (SOIL NAIL WALL)	CY	400		
70	194001	DITCH EXCAVATION	CY	126		
71	197060	SOIL NAIL ASSEMBLY	LF	141,380		
72	200001	HIGHWAY PLANTING	LS	LUMP SUM	LUMP SUM	
73	200114	ROCK BLANKET	SQYD	770		
74	203016	EROSION CONTROL (TYPE D)	SQYD	79,600		
75	203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	6		
76	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM	LUMP SUM	
77	206401	MAINTAIN EXISTING IRRIGATION FACILITIES	LS	LUMP SUM	LUMP SUM	
78	208000	IRRIGATION SYSTEM	LS	LUMP SUM	LUMP SUM	
79	016355	EXTEND 12" CONDUIT	LF	20		
80	250201	CLASS 2 AGGREGATE SUBBASE	CY	23,000		