

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe

*Serious Drought.
Help save water!*

July 17, 2015

12-Ora-57-20.7/21.2

12-0N1404

Project ID 1213000125

ACHNHP-P057(061)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN ORANGE COUNTY IN BREA FROM LAMBERT ROAD SOUTHBOUND ON RAMP TO 0.2 MILE NORTH OF LAMBERT ROAD UNDERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, August 11, 2015.

This addendum is being issued to revise the *Notice to Bidders and Special Provisions*.

In the Special Provisions, Section 83-1.02C(2), "ALTERNATIVE IN-LINE TERMINAL SYSTEM," is added as attached.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

Inform subcontractors and suppliers as necessary.

Addendum No. 1
Page 2
July 17, 2015

12-Ora-57-20.7/21.2
12-0N1404
Project ID 1213000125
ACHNHP-P057(061)E

This addendum, EBS addendum file and attachment are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/12/12-0N1404

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



ADNAN MAIAH
Deputy District Director
Capital Outlay Program/Single Focal Point

Attachment

83 RAILINGS AND BARRIERS

Replace section 83-1.02C(2) with:

83-1.02C(2) Alternative In-Line Terminal System

Alternative in-line terminal system must be furnished and installed as shown on the plans and under these special provisions.

The allowable alternatives for an in-line terminal system must consist of one of the following or a Department-authorized equal.

1. TYPE SKT-SP-MGS for steel posts or Type SKT-W-MGS for wood posts TERMINAL SYSTEM - Type SKT-MGS terminal system must be a SKT 350 sequential kinking terminal, system length 53'-1-1/2", manufactured by Road Systems, Inc., located in Big Spring, Texas, and must include items detailed for Type SKT-MGS terminal system shown on the plans. The SKT 350 sequential kinking terminal can be obtained from the distributor, Universal Industrial Sales, P.O. Box 699, Pleasant Grove, UT 84062, telephone (801) 785-0505 or from the distributor, Gregory Highway Products, 4100 13th Street, S.W., Canton, OH 44708, telephone (330) 477-4800.
2. TYPE X-LITE - Type X-Lite terminal system must be a 31" X-Lite Guard Rail End Terminal as manufactured by Barrier Systems, Inc., located in Vacaville, CA, and must include items detailed for Type 31" X-Lite terminal system shown on the plans. The 31" X-Lite Guard Rail End Terminal can be obtained from the distributor, Statewide Safety and Signs, Inc., 130 Grobric Court, Fairfield, CA 94533, telephone (800) 770-2644.
3. TYPE 31" X-TENSION - Type 31" X-Tension terminal system must be a 31" X-Tension Guard Rail End Terminal as manufactured by Barrier Systems, Inc., located in Vacaville, CA, and must include items detailed for Type 31" X-Tension terminal system shown on the plans. The 31" X-Tension Guard Rail End Terminal can be obtained from the distributor, Statewide Safety and Signs, Inc., 130 Grobric Court, Fairfield, CA 94533, telephone (800) 770-2644.

Submit a certificate of compliance for terminal systems.

Terminal systems must be installed under the manufacturer's installation instructions and these specifications. Each terminal system installed must be identified by painting the type of terminal system in neat black letters and figures 2 inches high on the backside of the rail element between system posts numbers 4 and 5. Paint must be metallic acrylic resin type spray paint. Before applying terminal system identification, the surface to receive terminal system identification must be removed of all dirt, grease, oil, salt, or other contaminants by washing the surface with detergent or other suitable cleaner. Rinse thoroughly with fresh water and allow to fully dry.

For Type SKT-SP-MGS terminal system, install the soil tube with soil plate attached at Post 1, hinged breakaway post at Post 2, and 6'-0" W6 x 9 steel posts at Posts 3 through 8. Use a W6 x 15 steel post at Post 1. The soil tube with soil plate must be, at the Contractor's option, driven with or without pilot holes, or placed in drilled holes. Space around the steel foundation tubes must be backfilled with selected earth, free of rock, placed in layers approximately 4 inches thick and each layer must be moistened and thoroughly compacted.

For Type SKT-W-MGS terminal system, install the soil tube with soil plate attached at Post 1, breakaway cable terminal post at Post 2, and controlled release terminal posts at Posts 3 through 8. The soil tube must be, at the Contractor's option, driven with or without pilot holes, or placed in a drilled hole. Space around the steel foundation tube must be backfilled with selected earth, free of rock, placed in layers approximately 4 inches thick and each layer must be moistened and thoroughly compacted. A wood post must be inserted into the steel foundation tube by hand. Before the wood terminal post is inserted, the inside surfaces of the steel foundation tube to receive the wood post must be coated with a grease that will not melt or run at a temperature of 149 degrees F or less. The edge of the wood post may be slightly rounded to facilitate insertion of the post into the steel foundation tube.

For Type 31" X-Lite terminal system, all crimped posts and line posts must be W6 x 8.5 or W6 x 9 steel posts. All posts, must be, at the Contractor's option, either driven or placed in drilled holes. Space around the crimped posts, Post 2 with attached soil plate and lines posts must be backfilled with selected earth, free of rock, placed in layers approximately 4 inches thick and each layer must be moistened and thoroughly compacted. All blocks must be wood or plastic.

For Type 31" X-Tension terminal system, the steel post and soil anchor must be, at the Contractor's option, driven with or without pilot holes, or placed in drilled holes. Space around the steel post and soil anchor must be backfilled with selected earth, free of rock, placed in layers approximately 4 inches thick and each layer must be moistened and thoroughly compacted. The wood terminal posts must be inserted into the drilled holes by hand and backfilled in the same manner as the steel post and soil anchor. Wood terminal posts must not be driven. All blocks must be wood or plastic.

For Type 31" X-Tension terminal system, the steel bottom post and I-beam post must be placed in drilled hole. The soil anchor and steel line posts must be, at the Contractor's option, either driven or placed in drilled holes. Space around the steel bottom post, steel line posts and soil anchor must be backfilled with selected earth, free of rock, placed in layers approximately 4 inches thick and each layer must be moistened and thoroughly compacted. All blocks must be plastic.

After installing the terminal system, dispose of surplus excavated material in a uniform manner along the adjacent roadway where designated by the Engineer.