

**Attachment B—Acceptable Supplemental Work Items**

**Acceptable Supplemental Work Items**

<b>Item Code</b>	<b>Supplemental Work Item</b>	<b>Standard Specification / Standard Special Provision</b>	<b>Rationale / Comments</b>
066072	Repair Detour	Section 4-1.04, "Detours"	The engineer orders the contractor to repair damage to detours caused by public traffic.
	Archaeological Investigations	Section 14-2.02, "Archaeological Resources" SSP 07-320, "Archaeological Monitoring Area"	The engineer orders the contractor to furnish labor, material, tools, and equipment to secure archaeological discovery and assist in the investigation or recovery of archaeological materials.
066041	Bird Protection	Section 14-6.02, "Bird Protection"	The engineer orders the contractor to construct exclusion devices, take nesting prevention measures, remove and dispose of partially constructed and unoccupied nests of migratory or nongame birds on a regular basis to prevent their occupation, or perform any combination of these.
066100 066101	Dust Control Dust Palliative	Section 14-9.02, "Dust Control" SSP S5-320, "Water Conservation"	The contractor is responsible for controlling dust generated by construction activities. If, based on construction staging, public traffic will be required to travel over unpaved surfaces, the engineer orders the contractor to apply water, dust palliative, or both to control dust caused by public traffic.
066177	Foundation Tests	Section 19-3.05, "Inspection"	The engineer may order the contractor to dig test pits and take test borings and foundation bearing tests.
066171	Settlement Platforms	Section 19-6.025, "Settlement Platforms"	The engineer orders the contractor to construct settlement platforms to monitor settlement progress during the settlement period.

Item Code	Supplemental Work Item	Standard Specification / Standard Special Provision	Rationale / Comments
066204	Remove Rocks and Debris	Section 20-4.03, "Preparing Planting Areas" Section 20-5.03D, "Trenching and Backfilling" Section 24-1.02, "Materials"	The engineer orders the contractor to remove and dispose of rocks and debris encountered during soil preparation for planting, or during trenching operations, or while processing native soil for lime stabilization.
066878	Repair Existing Water Line Crossovers	SSP 20-110, "Extend Irrigation Crossovers"	The engineer orders the contractor to remove debris encountered in the crossover conduit more than 3 feet from the ends being extended, or to repair existing water line crossovers.
066103	Maintain Existing Planted Areas	SSP 20-251, "Maintain Existing Planted Areas"	The engineer orders the contractor to perform extra work to maintain existing planted areas.
066256	Salvage and Stockpile Excess Screenings	Section 37-1.09, "Payment"	The engineer orders the contractor to salvage and stockpile excess seal coat screenings.
066411	Crack Repairs	Section 39-1.09D, "Geosynthetic Pavement Interlayer"	The engineer orders the contractor to repair cracks ¼ inch and wider and spalls and holes in the pavement.
066490	Pile Load Testing	Section 49-1.04, "Load Test Piles"	The engineer orders the contractor to install, operate and later remove State-furnished steel load test beams, jacks, bearing plates, drills and other test equipment.
066685	Exploratory Work - Horizontal Drain	Section 68-2.03, "Installing Horizontal Drains"	The engineer orders the contractor to perform exploratory work to determine the exact location for installing horizontal drains.

<b>Item Code</b>	<b>Supplemental Work Item</b>	<b>Standard Specification / Standard Special Provision</b>	<b>Rationale / Comments</b>
066684	Horizontal Drain	Section 68-2.05, "Payment"	Unless otherwise provided in the special provisions, the engineer orders the contractor to furnish and install a collector system for the horizontal drains.
066861	Maintain Existing and Temporary Electrical System	Section 86-1.06, "Maintaining Existing and Temporary Electrical Systems"	The engineer orders the contractor to perform extra work necessary to keep all or any part of the electrical system in effective operation.
	Additional Non-Destructive Testing (NDT)	SSP S8-W04, "Welding"	The engineer may order the contractor to perform additional NDT, to be paid for as extra work. The estimated cost of the extra work should be 1% of the cost of the furnished steel items, not to exceed \$10,000.